

THE UNITED REPUBLIC OF TANZANIA



MINISTRY OF WATER



Dar es Salaam Water Supply & Sanitation Authority

DAWASA Building, Dunga/Malaga Street, Mwananyamala Area

P. O. Box 1573, Dar es Salaam. TANZANIA.

Tel. +25522276006/15; Fax: +255222762480; E-mail: dawasaceo@dawasa.co.tz

Project Brief for the Proposed Construction of a Public Toilet at Mloganzila Bus Stand, Mloganzila Mtaa, Kwembe Ward, Ubungo District, Dar es Salaam Region

Submitted to:

National Environment Management Council

Regent Estate, Mikocheni, P. O. Box 63154, Dar es Salaam.

Tel: +255 22 2774852/ 0713608930; Fax: +255 22

2774901E-mail: *dg@nemc.or.tz*

Lead Consultant:

Prof. Rubhera RAM Mato (PhD), CEng. (T), Reg. EIA Expert

Mobile: +255754898592; E-Mail: rubheramato@gmail.com





Submission Date:

14th March 2023

ACKNOWLEDGEMENT

DAWASA, the developer of this proposed project, would like to thank every person who in one way or another participated in the ESIA study. Moreover, DAWASA appreciates the keen participation of all stakeholders. Comments given by various stakeholders were very useful for the completion of this work. The support of Ubungo Municipality through its various leadership cadres including the Mlonganzila Mtaa and Kwembe Ward leaderships deserve special mention. Last but not least, DAWASA would like to commend the good work done by our Environmental and Social Experts and their assistants in data collection and preparation of this report.

THE STUDY TEAM

| NAME | POSITION | NEMC Reg. No. | SIGNATURE |
|-----------------------------|---------------------------------------|---------------------------------------|---|
| Prof. Rubhera RAM Mato | Environmental and ESIA Team Leader | Registered NEMC/EIA/0092 |  |
| Mr. Robert Kishiki | Sociologist | Not Registered |  |
| Mr. Emmanuel Rajab | Environmental Engineer | Registered EC/EE- EIA/2021/0015 |  |
| Mr. Melkizedeck Stephano | Environmentalist | Not Registered |  |

ABBREVIATIONS

| | |
|--------|---|
| AAQ | Ambient Air Quality |
| AIDS | Acquired Immuno-Deficiency Syndrome |
| DAWASA | Dar es Salaam Water Supply and Sanitation Authority |
| EIA | Environmental Impact Assessment |
| EMP | Environmental Management Plan |
| ESIA | Environmental and Social Impact Assessment |
| ESMP | Environmental and Social Monitoring Plan |
| GoT | Government of Tanzania |
| HIV | Human Infection Virus |
| IDA | International Development Association |
| LGA | Local Government Authority |
| NEMC | National Environment Management Council |
| NEP | National Environment Policy |
| OGSP | Off-Grid Sanitation Project |
| PPE | Personal Protective Equipment |
| PVC | Polyvinyl Chloride |
| RAP | Resettlement Action Plan |
| STDS | Sexual Transmitted Diseases |

TABLE OF CONTENTS

| | |
|---|------------|
| ACKNOWLEDGEMENT | I |
| THE STUDY TEAM..... | II |
| ABBREVIATIONS | III |
| LIST OF FIGURES..... | IX |
| NON-TECHNICAL EXECUTIVE SUMMARY | 1 |
| 1.0 INTRODUCTION | 8 |
| 1.1 BACKGROUND AND JUSTIFICATION | 8 |
| 1.2. NATURE OF THE PROJECT | 10 |
| 2.0 PROJECT DESCRIPTION | 10 |
| 2.1 PROJECT LOCATION | 10 |
| 2.2 ACCESSIBILITY | 12 |
| 2.3 SPECIFIC FEATURES | 12 |
| 2.4 LAND OWNERSHIP AND LAND USE..... | 13 |
| 2.4.1 <i>Land ownership</i> | 13 |
| 2.4.2 <i>Landuse</i> | 13 |
| Figure 4: Mloganzila Hospital, bus stand and commercial building structures | 13 |
| 2.5 PROJECT ACTIVITIES | 14 |
| 2.5.1 <i>Mobilization or pre-construction phase</i> | 14 |
| 2.5.2 <i>Construction phase</i> | 14 |
| 2.5.3 <i>Demobilization phase</i> | 16 |
| 2.6 OPERATION PHASE | 16 |
| 2.7 DECOMMISSIONING PHASE..... | 17 |
| 2.8 PROJECT DESIGN..... | 17 |
| 2.8.1 <i>Toilet Design</i> | 17 |
| 2.8.2 <i>Layout Plan</i> | 18 |
| 2.9 PROJECT REQUIREMENTS AND WASTE GENERATION..... | 20 |
| 2.9.1 <i>Construction materials and labour force</i> | 20 |
| Table 3: Quantities of construction Materials | 20 |
| 2.9.2 <i>Labour force</i> | 21 |

| | | |
|------------|---|-----------|
| 2.9.3 | <i>Machinery and Equipment</i> | 21 |
| 2.9.4 | <i>Wastes generation</i> | 22 |
| 2.10 | PROJECT ALTERNATIVES..... | 23 |
| 2.10.1 | <i>No project alternative</i> | 24 |
| 2.10.2 | <i>Other project alternative</i> | 24 |
| 3.0 | POLICIES, LEGISLATION AND INSTITUTIONAL ASPECT | 25 |
| 3.1 | OVERVIEW | 25 |
| 3.2 | RELEVANT POLICIES | 25 |
| 3.2.1 | <i>National Environment Policy 2021</i> | 25 |
| 3.2.2 | <i>National Land Policy of 1997</i> | 27 |
| 3.2.3 | <i>Construction Industry Policy (2003)</i> | 27 |
| 3.2.4 | <i>National Health Policy (2003)</i> | 27 |
| 3.2.5 | <i>National Gender Policy of 2000</i> | 28 |
| 3.2.6 | <i>National Human Settlements Development Policy (2000)</i> | 28 |
| 3.3 | PRINCIPAL LEGISLATIONS AND REGULATIONS..... | 28 |
| 3.3.1 | <i>Environmental Management Act (2004)</i> | 28 |
| 3.3.2 | <i>The Environmental Management (Fees and Charges) Regulations, 2021</i> | 29 |
| 3.3.3 | <i>The Environmental Management (Control of hazardous Waste)</i> <i>Regulations, 2021</i> | 30 |
| 3.3.4 | <i>The Environmental Management (Control of Noise and vibration)</i> <i>Regulations, 2015</i> | 30 |
| 3.3.5 | <i>The Environmental Management (Prohibition of Plastic Carrier bags)</i> <i>regulations, 2019</i> | 31 |
| 3.3.6 | <i>The Environmental Management (Solid Waste Management)</i> <i>Regulations, 2007</i> | 31 |
| 3.3.7 | <i>The Environmental Management (Water Quality) regulations, 2009</i> | 32 |
| 3.3.8 | <i>The Environmental Management (Air Quality) regulations, 2009</i> | 32 |
| 3.3.9 | <i>The Environmental Management (Soil Quality) regulations, 2009</i> | 33 |
| 3.3.10 | <i>Occupational Health and Safety Act 2003</i> | 33 |
| 3.3.11 | <i>Water Supply and Sanitation Act No. 12 of 2009</i> | 34 |
| 3.3.12 | <i>Engineers Registration Act and its Amendments 1997 and 2007</i> | 34 |
| 3.3.13 | <i>Contractors Registration (Amendment) Act, 2008</i> | 34 |

| | |
|--|-----------|
| 3.3.14 Architects and Quantity Surveyors Act (1997) | 34 |
| 3.3.15 Urban Planning Act Cap. 355 (2007) | 35 |
| 3.3.16 THE URBAN PLANNING (PLANNING SPACE STANDARDS) REGULATIONS, 2018 . | 35 |
| 3.3.17 URBAN PLANNING (USE GROUPS AND USE CLASSES) REGULATIONS, 2018 | 36 |
| 3.3.18 THE URBAN PLANNING (ZONING OF LAND USE) REGULATIONS, 2018 | 36 |
| 3.3.19 Public Health Act (2009) | 37 |
| 3.3.20 WORLD BANK GUIDELINES FOR ENVIRONMENTAL MANAGEMENT | 37 |
| 4.0 BASELINE INFORMATION | 38 |
| 4.1 WATER TABLE AND WATER QUALITY ANALYSIS..... | 38 |
| 4.2 AIR QUALITY..... | 38 |
| 4.3 NOISE AND VIBRATIONS..... | 38 |
| 4.4 CLIMATE | 39 |
| 5.0 POTENTIAL IMPACTS | 40 |
| 5.1 MOBILIZATION PHASE | 40 |
| 5.1.1 POSITIVE IMPACTS | 40 |
| 5.1.1.1 <i>Employment opportunities</i> | 40 |
| 5.1.2 NEGATIVE IMPACTS..... | 40 |
| 5.1.2.1 <i>Noise pollution</i> | 40 |
| 5.1.2.2 <i>Air Pollution from dust emission</i> | 40 |
| 5.2 CONSTRUCTION PHASE | 41 |
| 5.2.1 POSITIVE IMPACTS..... | 41 |
| 5.2.1.1 <i>Employment opportunities</i> | 41 |
| 5.2.1.2 <i>Improved living conditions and economic growth</i> | 41 |
| 5.2.1.3 <i>Improved public health</i> | 41 |
| 5.2.1.4 <i>Increased socio-cultural interaction</i> | 42 |
| 5.2.1.5 <i>Increased Revenue to the nation through taxes, both direct and indirect</i> | 42 |
| 5.2.2 NEGATIVE IMPACTS..... | 42 |
| 5.2.2.1 <i>Increased HIV/AIDS and other sexual related diseases:</i> | 42 |
| 5.2.2.2 <i>Destruction and infringement of properties</i> | 43 |
| 5.2.2.3 <i>Noise pollution</i> | 43 |
| 5.2.2.4 <i>Air Pollution from dust emission</i> | 44 |
| 5.2.2.5 <i>Potential communicable diseases transmission</i> | 44 |
| 5.2.2.6 <i>Smells and flies in toilets</i> | 44 |

| | |
|--|-----------|
| 5.2.2.7 High Risk of Health associated with construction work..... | 45 |
| 5.3 OPERATION PHASE..... | 46 |
| 5.3.1 POSITIVE IMPACTS..... | 46 |
| 5.3.1.1 Improved social-economic livelihood and dignity within the beneficiary society | 46 |
| 5.3.1.2 Increased Revenue to the nation through taxes, both direct and indirect ... | 47 |
| 5.3.2 NEGATIVE IMPACTS | 47 |
| 5.3.2.1 Smells and flies in toilets..... | 47 |
| 5.3.2.2 Health Risks to Cleaners | 47 |
| 5.3.2.3 Low revenue collection due to low affordability of customers | 48 |
| 6.0 ACTION PLAN FOR PREVENTION AND MANAGEMENT OF ACCIDENTS DURING IMPLEMENTATION STAGE | 48 |
| 6.1 OCCUPATIONAL HEALTH AND SAFETY | 48 |
| 6.1.1 EMERGENCY PREPAREDNESS PLAN | 49 |
| 6.2 SECURITY | 49 |
| 6.3 MONITORING, MAINTENANCE AND REPAIR | 49 |
| 7.0 ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN | 50 |
| 7.1 ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN | 50 |
| 8.0 MONITORING PLAN..... | 61 |
| 8.1 ENVIRONMENTAL MONITORING..... | 61 |
| 9.0 PROJECT BUDGET | 66 |
| 10.0 STAKEHOLDER VIEWS ON THE PROPOSED PROJECT | 66 |
| 11.0 CONCLUSIONS AND RECOMMENDATIONS..... | 67 |
| APPENDIX I: LIST OF STAKEHOLDERS CONSULTED | 68 |
| APPENDIX II: MINUTES OF LOCAL COMMUNITY CONSULTATION | 70 |
| APPENDIX III: SCREENING LETTER FROM NEMC | 75 |
| APPENDIX IV: PERMIT TO USE THE OPEN SPACE FOR CONSTRUCTION OF PUBLIC TOILET | 76 |
| APPENDIX V: MEMORANDUM OF UNDERSTANDING BETWEEN DAWASA AND DAR ES SALAAM MUNICIPAL COUNCILS | 79 |

APPENDIX VI: ARCHITECTURAL DRAWINGS80
APPENDIX VII: NON-TECHNICAL EXECUTIVE SUMMARY (KISWAHILI VERSION) 81
MUHTASARI.....81

LIST OF FIGURES

Figure 1: A Map of Dar es salaam region showing the project Municipal..... 11
Figure 2: An Extract Google view to show the Location of the project area 12
Figure 3: Some vegetation and structures at the project site 13
Figure 4: Mloganzila Hospital, bus stand and commercial building structures 13
Figure 5: Floor Plan for Public Toilet..... 19
Figure 6: Stakeholder’s consultation meeting with Ubungo Municipal staff and
Mloganzila business people 66

LIST OF TABLES

Table 1: The coordinates of the project area 10
Table 2: The Proposed standard Public Toilet working spaces 18
Table 3: Quantities of construction Materials 20

NON-TECHNICAL EXECUTIVE SUMMARY

Comprehensive project brief for the Proposed Public Toilet to be built at Mlonganzila bus stand, Mlonganzila Mtaa, Kwembe Ward, Ubungo District, Dar es Salaam Region

Proponent: Dar es Salaam Water Supply and Sanitation Authority (DAWASA)

Proponent's Contact: DAWASA,
DAWASA Building, Dunga/Malaga Street,
Mwananyamala Area
P. O. Box 1573, Dar es Salaam. TANZANIA.
Tel. +25522276006/15; Fax: +255222762480;
E-mail: dawasaceo@dawasa.co.tz

EIA Expert: Prof. Rubhera RAM Mato (PhD), CEng. (T), Reg. EIA Expert
P. O BOX 35478, Dar es Salaam, Tanzania
Mobile: +255754898592
E-Mail: rubheramato@gmail.com

INTRODUCTION

The Government of the United Republic of Tanzania (GoT) through the Dar es Salaam Water and Sewerage Authority (DAWASA) under the Ministry of Water intends to implement an Off Grid Sanitation Project (OGSP) in Dar es Salaam City to serve peri-urban areas not connected to the central sewerage system. DAWASA has received financing from the International Development Association (IDA) in the form of a credit to implement the project. Prior to implementing the project, the law in Tanzania requires an Environmental Impact Assessment to be conducted and approved by relevant authority. In order to comply with the law in Tanzania, the DAWASA intends to apply a portion of the proceeds of the credit to eligible payments for consulting services for Preparation of Environmental and Social Impact Assessment

(ESIA) and Resettlement Action Plan (RAP) Report for construction of off grid sanitation projects.

The Off-Grid project is intended to address these challenges. The Off-Grid project is divided into several subprojects which will be implemented in the five municipalities of Dar es Salaam City. One of these is the Construction of a Public Toilet at Mloganzila bus stand, Mloganzila Mtaa, Kwembe Ward in Ubungo Municipality. The toilet will mostly serve the commuters using the bus terminal at Mloganzila.

The proposed project entails construction of an engineered sanitary depository for sewage (night soil) for public use at the Mloganzila bus stand. The nature of the project enhances environmental protection through proper handling and disposal of domestic sewage. According to First Schedule of the EIA and Audit Regulations (Amended) of 2018, the nature of the project is small and entails no significant impacts. As these Regulations, the project falls under Type B2 category, which are termed as “small-scale activities and enterprises that require registration but shall not require Environmental Impact Assessment”. The Regulations provides for B” type projects for the developer to submit a Project Brief that shall be examined and issued with an Environmental Impact Assessment Certificate by the responsible authority.

PROJECT DESCRIPTION

The project site is located at Mlonganzila hamlet (*mtaa*), Kwembe ward, Ubungo District in the Dar es Salaam Region. The project site is geographically located at 37S UTM zone with coordinates 506302 (Eastings) and 9247052 (Northings). . The site is about 33 Kilometers from City Center via Morogoro road. The main nearby landmark is the Mlonganzila Hospital. A water storage tank will be installed to ensure continuous supply of water to the toilet. An attendant will be stationed to oversee cleanliness and safety of the toilet facility.

The project intends to establish a Modern Public Toilet at Mloganzila Bus Stand, Kwembe ward in Ubungo Municipality. About 22 units each with

different size and type of service ranging from urinals, bidets, WCS, HWB, showers, lobby, storage room and office space. The Proposed Project site covers an approximately area of 120m². DAWASA has entered into a MoU with the Ubungu Municipality to run the toilet through a private operator. DAWASA shall remain the owner of the facility. The MoU includes the modalities for sharing the revenue.

The major construction activities for the sub-projects include site clearance, excavation, filling, soil sterilization and stabilization, disposal of surplus excavated material, steel works, concrete works, woodworks (carpentry), finishing including painting.

The budget for the proposed public toilet is TZS 45 Million. The money will be provided by the Government of the Republic of Tanzania through financing from the World Bank.

POLICY, LEGAL AND INSTITUTIONAL FRAMEWORK

Tanzania is committed to attaining sustainable development goals. This urge is envisaged in the National Environmental Policy and other sectoral policies including;

- National Environment Policy, 2021
- National Land Policy of 1997
- Construction Industry Policy (2003)
- National Health Policy (2003)
- National Gender Policy of 2000
- National Human Settlements Development Policy (2000)

Important laws and regulations that have relevance to road development in respect of environmental management include;

- Environmental Management Act (2004)

- The Environmental Management (Fees and Charges) Regulations, 2021
- The Environmental Management (Control of hazardous Waste) regulations, 2021
- The Environmental Management (Control of Noise and vibration) regulations, 2015
- The Environmental Management (Prohibition of Plastic Carrier bags) regulations, 2019
- The Environmental Management (Solid Waste Management) regulations, 2007
- The Environmental Management (Water Quality) regulations, 2009
- The Environmental Management (Air Quality) regulations, 2009
- The Environmental Management (Soil Quality) regulations, 2009
- Occupational Health and Safety Act 2003
- The Water Supply and Sanitation Act No. 12 of 2009
- Engineers Registration Act and its Amendments 1997 and 2007
- The Contractors Registration (Amendment) Act, 2008
- The Architects and Quantity Surveyors Act (1997)
- The Urban Planning Act (2007)
- Public Health Act (2009)
- World Bank guidelines for Environmental Management

PROJECT ENVIRONMENT

The site area lies in the tropical coastal belt of Tanzania and is influenced by two major climatic seasons, namely rainfall and temperature. Rainfall pattern is that of bimodal type with erratic conventional rains. The monsoon rains occurring almost throughout the Municipality between December and February, While the long heavy rains in the period from March to June, the amount of rainfall received ranges from 800-1200mm per annum. Temperature just like rainfall is also influenced by ocean. High temperature prevails throughout the year ranging from 25⁰C during the period of June to August up to 35⁰C in the period of January to March.

Data for Water quality from shallow wells close to the project site were not immediately available during this study. However previous studies of the similar areas indicate the high possibility of groundwater contamination from adjacent pit latrines located less than 30m horizontal distance from the shallow well (Still and Nash, 2002).

The air quality observations indicate that the general air quality in the project area is good as there is no any strange activity contributing to air pollution. However, seasonal variation as well as localized and temporal deterioration in air quality does occur. On the other hand, noise level at the project area is mainly due to moving vehicle along the road, moving air (wind) or rain and birds. Project activities during construction will change patterns and amplitude of noise in the project area.

PROJECT STAKEHOLDERS AND INVOLVEMENT

A simple methodology was adopted to identify key stakeholders and main environmental and social concerns. This involved physical observations and consultations (direct consultations). Other information on the project was obtained through a desk study.

During the conduction of this study, different stakeholders were consulted. Among these include the Ubungo Municipal Council and community at Mloganzila bus stand. During the meeting, the consultant gave a brief explanation on the proposed public toilet.

POTENTIAL SIGNIFICANT ENVIRONMENTAL AND SOCIAL IMPACTS

The following impacts were identified to be likely to occur during Mobilization Phase

- Employment opportunities
- Noise pollution
- Air Pollution from dust emission

The following impacts were identified to be likely to occur during Construction Phase

- Employment opportunities
- Improved living conditions and economic growth
- Improved public health
- Increased socio-cultural interaction
- Increased Revenue to the nation through taxes, both direct and indirect
- Increased HIV/AIDS and other sexual related diseases:
- Destruction and infringement of properties
- Noise pollution
- Air Pollution from dust emission
- Potential communicable diseases transmission
- Smells and flies in toilets
- High Risk of Health associated with construction work
- Waste generation during construction
- Groundwater contamination from soil sterilization

The following impacts were identified to be likely to occur during Operation Phase

- Improved social-economic livelihood and dignity within the beneficiary society
- Increased Revenue to the nation through taxes, both direct and indirect
- Smells and flies in toilets

PREVENTION AND MANAGEMENT OF ACCIDENTS DURING IMPLEMENTATION STAGE

The project shall be implemented in compliance to labour laws in Tanzania, in particular, the Occupational Health and Safety Act (2003). Clauses to protect the health and safety of workers shall be included in the contract documents for implementation stage which includes the following; provision and enforcement of the use of appropriate personal protective equipment for all workers e.g. overalls, gloves, masks, etc. (wherever required), presence of

the emergency preparedness plan in place prior to commencement of construction activities as well as ensuring security matter of the site by fencing the whole project area and provide gates for entrance and exit purpose.

MITIGATION MEASURES AND ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN (ESMP)

The options to minimize or prevent the identified adverse social and environmental impacts as well as a monitoring plan have been suggested in this report and are contained in the ESMP. Many of them are based on good engineering practices and the timely responsiveness of the responsible institution. The ESMP describes the implementation schedule of the proposed mitigation measures as well as planning for long-term monitoring activities. It defines the roles and responsibilities of different actors of the plan. The Approach environmental and social costs amount to TSH 38,000,000 (Excluding the costs that will appear in then (BOQ) and resettlement exercise. The estimated annual costs for carrying out the proposed environmental and social motoring program amounts to TSH 24,000,000.

CONCLUSION

It is, therefore, concluded that implementation of the proposed construction of public toilets at Mloganzila bus stand, Mloganzila Mtaa, Kwembe ward in Ubungo Municipality, Dar es Salaam will not entail detrimental impacts provided that the recommended mitigation measures are adequately and timely put in place. The identified adverse impacts shall be managed through the proposed mitigation measures and implementation regime laid down in this EIS. DAWASA is committed to implementing all the recommendations given in the EIS and further carrying out the environmental auditing and monitoring schedules.

Environmental and Social Impacts Assessment for The Proposed Public Toilet to be built at Built at Mloganzila Bus Stand, Ubungo Municipality in Dar es Salaam Region

1.0 INTRODUCTION

1.1 Background And Justification

The Government of the United Republic of Tanzania (GoT) through the Dar es Salaam Water and Sewerage Authority (DAWASA) under the Ministry of Water intends to implement an Off Grid Sanitation Project (OGSP) in Dar es Salaam City to serve peri-urban areas not connected to the central sewerage system. DAWASA has received financing from the International Development Association (IDA) in the form of a credit to implement the project. Prior to implementing the project, the law in Tanzania requires an Environmental Impact Assessment to be conducted and approved by relevant authority. In order to comply with the law in Tanzania, the DAWASA intends to apply a portion of the proceeds of the credit to eligible payments for consulting services for Preparation of Environmental and Social Impact Assessment (ESIA) and Resettlement Action Plan (RAP) Report for construction of off grid sanitation projects.

Dar es Salaam is the largest and most important commercial and industrial centre in Tanzania. According to the Tanzania National Census of August 2022, the City of Dar es Salaam has a population of 5,383,728 (sense.nbs.go.tz, accessed December 24, 2022). About 10% of the population is served by sewers and the rest almost depend on on-site sanitation systems. The sewer coverage is only limited to the area within city centre with a total length of 67.8km and the system is based on a separate systems and discharge their effluent into oxidation ponds, and into the sea through sea outfall of about 1.03km long. The onsite sanitation systems result into Faecal sludge of which handling and management throughout the sanitation chain (from domestic containment, transportation as well as disposal and treatment) is currently hygienically inadequate thus posing environmental and public health risks. The Off Grid project is intended to

address these challenges. The Off Grid project is divided into several subprojects which will be implemented in the five municipalities of Dar es Salaam City. One of these is the Construction of a Public Toilet at Mloganzila Bus Stand in Kwembe ward, Ubungo Municipality. The toilet will mostly serve the people using the Mloganzila Bus Stand (travelers, traders and their customers).

The ESIA study was conducted in accordance with Regulation 6(1) of Environmental Management (Environmental Impact Assessment and Audit) (Amendment) Regulations, 2018. These Regulations provide legal procedures for implementing the requirements of the Environmental Management Act Cap.191 of 2004. The Regulations give mandate to NEMC to oversee the EIA process, which culminates with an award of the EIA Certificate by the Ministry responsible for Environment.

In accordance with the EIA Regulations, NEMC is mandated to screen projects and make decisions of level of EIA required as well as evaluating the adequacy of respective environmental statements. Considering the nature and size of the proposed “Public Toilet Project in Ubungo Municipality”, the project falls under Category “B2” (Non-Mandatory) in accordance with Reg.4(1)(c) and First Schedule of the amended 2018 Regulations which categorizes the *night soil collection and treatment* being under the ‘*List of small-scale activities and enterprises that require registration but shall not require Environmental Impact Assessment. Further, the projects shall not require screening and scoping, rather, the Project Brief shall be examined and issued with an Environmental Impact Assessment Certificate*’.

The regulations require developers to prepare and submit to the National Management Council (NEMC) filled EIA registration forms and “Project Briefs” for all B2 projects. The preparation and content of the “Project Briefs” is provided under Reg.6(1). The same has been followed in preparing this “Project Brief”. The ESIA study that ends at the project brief stage since it is a B2 type, was conducted from July 2020 to August 2020. The subsequent corrections following NEMC reviews have been concluded in December 2022.

This project brief for the Proposed Construction of Public Toilet in Ubungo Municipality is being submitted to NEMC together with EIA Registration Forms for EIA Certificate decision.

1.2. Nature of the Project

The proposed project concerns construction of an engineered sanitary depository for sewage (night soil) for public use at Mloganzila Bus Stand, Kwembe ward, Ubungo Municipality. The nature of the project enhances environmental protection through proper handling and disposal of domestic sewage. According to First Schedule of the EIA and Audit Regulations (Amended) of 2018, the nature of the project is small and entails no significant impacts. The project can be categorised as Type B2, which according to the regulations are “small-scale activities and enterprises that require registration but shall not require Environmental Impact Assessment. Further, the projects shall not require screening and scoping, rather, the Project Brief shall be examined and issued with an Environmental Impact Assessment Certificate”.

2.0 PROJECT DESCRIPTION

2.1 Project Location

The project site is located at Mlonganzila hamlet (*mtaa*), Kwembe ward, Ubungo District in the Dar es Salaam Region. The project site is geographically located at 37S UTM zone with coordinates in Table 1. The site is about 33 Kilometers from City Center via Morogoro road. (Refer Figure 1, and Figure 2). Toilet will be supplied with water continuously. A separate storage tank will be installed to ensures continuously water availability. An attendant will be stationed to oversee cleanliness and safety of the facilities.

Table 1: The coordinates of the project area

| S/n | Coordinates | |
|-----|-------------|----------|
| | Easting | Northing |
| 1 | 506302 | 9247052 |




Figure 1: A Map of Dar es salaam region showing the project Municipal



Figure 2: An Extract Google view to show the Location of the project area

2.2 Accessibility

The project area is accessible via Morogoro road, from City Centre at Kibamba bus stop turn left heading to Mloganzila Hospital, onto the road heading to Mloganzila Hospital just 0.25 Kilometers from the Hospital turn left and the project site is about 0.3 Kilometers away from the tarmac road. Otherwise the site is accessible from all directions and there is no any physical restrictions.

2.3 Specific Features

There are some vegetation close to the proposed project site which includes tall and short grasses, palm trees (3 in number) and some bus stand ongoing construction structures. Most of the structures within the project site are; business frame buildings (Figure 3). The project site is located within the Bus stand.



Figure 3: Some vegetation and structures at the project site

2.4 Land ownership and Land Use

2.4.1 Land ownership

The proposed project site is solely owned by Ubungo Municipal Council. The land is part of the Mloganzila bus stand. The municipality has apportioned about 400 m² piece of land for public toilet construction. There is a Memorandum of Understanding (MoU) that has been signed between DAWASA and Ubungo Municipal Council for the implementation of the project (Appendix IV). In this MoU, DAWASA is responsible for the construction of the toilet while the Ubungo Municipality avails land and running the project.

2.4.2 Land-use

The main land use at the proposed project site includes; bus stand, tricycle (*Bajaji*) stand power lines, an ongoing small business premises construction and Mloganzila Hospital as seen from afar, figure 4.



Figure 4: Mloganzila Hospital, bus stand and commercial building structures

2.5 Project Activities

2.5.1 Mobilization or pre-construction phase

This phase entails mobilization of labour force, and equipment as well as acquisition of various permits as required by the law.

Other activities during this phase include;

- Topographical Survey for setting out purposes,
- Construction Materials' source Investigation,
- Land acquisition,
- Material storage and material preparation,

Duration

This phase is expected to take a total of One 1 Month.

2.5.2 Construction phase

During this phase a number of activities will be conducted, the following is the list of activities expected to be carried out during this phase;

- *Site Clearance:* The contractor shall clear the construction areas within the site of all bushes, roots, boulders, natural obstructions, rubbish and any other natural or artificial obstructions, which would interfere with construction of buildings, roads, paths and drains.
- *Excavation:* Excavations for foundations and the reinforced concrete structure shall be to the widths, depth and levels to accommodate the structure shown on the drawings. Working space has been allowed for in the measurement of excavation quantities given in these Bills of Quantities in accordance with the rules of measurement laid down elsewhere in these Bills, namely 1.00 metre from the face of any work which requires formwork over 1m deep below the starting level of excavation, and 0.30 metre from face of any work which requires formwork not exceeding 1 metre deep below starting level of excavation.

- *Filling:* The fill shall be clean, selected coarse sand or gravel. It should be taken from borrow pits if the soil on the site is found to contain too much fines and to have too low plasticity limit to be used as fill.
- *Soil Sterilization:* Anti-termite treatment is to be carried out by an approved specialist firm who will be required, upon completion of the soil sterilisation, to furnish a written guarantee qualifying the following:
 - That the chemicals applied comply with the requirements and concentration (The chemicals used shall be one of the following: Aldrin 0.5% applied in oil solution or water emulsion, Benzene hexachloride, 0.8% of gamma isomer applied in oil solution or water emulsion, Chlordane 1.0% applied in solution or water emulsion, Dieldrin 0.5% applied in oil solution or water emulsion, Lindane; 0.8% in oil solution or water emulsion, Pentachlorophenol; 5% in oil solution, Trichlorobenzene; 1 part to 3 parts oil.
 - That the treatment will remain effective against termite infestation for a period of five years.
 - The free re-treatment by the firm of any areas showing signs of infestation before the expiry of the five-year period.
- *Disposal of surplus excavated material:* Surplus excavated material will be carted away from the vicinity of the walls and deposited, spread and leveled on areas to be allocated by the Structural Engineer, reasonably adjacent to the site.
- Concrete work
- Masonry and wood works
- Steel fixing:
- Formwork preparation
- Finishing works – plastering and painting; plumbing and electrical installations.
-

Duration

This phase is expected to take a total of Six 6 Months.

2.5.3 Demobilization phase

This phase will involve the dismantling of temporary structures such as scar forming and removing/spreading spoil materials for proper restoration of the site.

Other activities include;

- General cleanliness of the area, that is clearance of all sorts of solid wastes (plastics, wood, metal, papers, etc);
- Deposit all wastes to the authorized dumpsite;

Duration

This phase is expected to take a total of One 1 Month.

2.6 Operation phase

The phase entails the actual usage of the toilet. Supply of water and toilet cleaning materials (disinfectants) are among the essentials for running the facility. Faecal sludge will be desludged using vacuum takers and disposed of at waste stabilization ponds for further treatment. The Ubungo municipality will decide on the mode of running the toilet for instance instituting fee, Standby attendants will be positioned to oversee the day to day running of the facility.

An MoU between DAWASA and Dar es Salaam City LGAs, stipulates the modalities for constructing and operating the public toilets. Under this MoU;

- The land on which the facilities have been constructed will remain under the respective municipal ownership and structures will be owned by DAWASA.
 - All facilities will be operated by outsourcing to private operators through operation contracts. Details of the private operator selection criteria are stipulated in the operation manual.
 - Private operators will be procured by DAWASA and the operation contract will be supervised by the respective DLGA's.
 - All major maintenance and repair works will be financed and carried by
-

DAWASA through revenue collected from revenue collected from the facilities user fee.

- The revenue collected from service provided will be shared between the two co-managing entities in the following distribution: DAWASA takes 75.8% of the profit while Ubungo Municipality gets 24.2%.

2.7 Decommissioning Phase

Decommissioning is not anticipated in the foreseeable future as the completed facility will be serving a lot of people from; The bus stand and the nearby market, bodaboda drivers and the passersby who at present use the existing public toilet but it does not suffice. However, if this will happen, may entail change of use (functional changes) or demolition triggered by change of land use.

2.8 Project Design

2.8.1 Toilet Design

The project intends to establish the Modern Public Toilet at Mloganzila Bus Stand, Kwembe ward in Ubungo Municipality. About 22 units each with different size and type of service ranging from urinals, bidets, WCS, HWB, showers, lobby, storage room and office space. The Proposed Project site covers an approximately area of 120m². The project is one single multipurpose facility aimed at providing services to the community. Pertinent area of each cube/partition with their number in the facility is as described in Table 2. The floor areas of the proposed public toilets presented in Table 2 were obtained partly using criteria stipulated in the Tanzania national documents, specifically, the National Guideline for Water, Sanitation and Hygiene for Tanzania Schools prepared by the Ministry of Education, Science and Technology (2016); and the Design, Construction Supervision, Operation and Maintenance (DCOM) Manual Volume II, Design of Sanitation Projects ,Fourth Edition, prepared by the Ministry of Water (2020).

Furthermore the project will involve the construction of raiser for elevated water storage tank to build adequate pressure for proper functioning of the facility.

Table 2: The Proposed standard Public Toilet working spaces

| Cube/partition | Unit area(m²) | Number of units in the Facility |
|-----------------------|---------------------------------|--|
| Ladies toilet | 24.5 | 6 |
| Gents Toilet | 24.5 | 4 |
| Disabled | 6 | 2 |
| Janitor | 3.6 | 1 |
| Store | 3.6 | 1 |
| Ladies shower | 5.5 | 3 |
| Gents Shower | 5.5 | 3 |
| Lobby | 17 | 1 |
| Reception | 2.6 | 1 |
| Total | 92.8 | 22 |

2.8.2 Layout Plan

The toilet layout plan is given in Figure 5, and other detailed architectural drawings are found in appendix III. The project is a simple structure that shall be constructed using block works, corrugated iron sheets and wooden members for doors.




Figure 5: Floor Plan for Public Toilet

2.9 Project Requirements and Waste Generation

2.9.1 Construction materials and labour force

The main materials for Public toilet include cement, aggregates (stones), water, steel, sand, timbers, blocks, uPVC pipes, IPS Pipes and gravels. All materials are available in the local sources in Tanzania. (Estimate quantities of the materials will be provided in the BoQ). Table 3 shows the types and amounts of materials to be used.

Table 3: Quantities of construction Materials

| Requirements | Type | Source | Approx. Quantity required |
|--------------|---|--------------------------------|---------------------------|
| Substructure | Hardcore | Registered Local vendors | 114m ³ |
| | Concrete | | 249 m ³ |
| | Reinforcements | | 500 m ³ |
| Frame | Hardcore | | 114m ³ |
| | Concrete | | 249 m ³ |
| | Reinforcements | | 500 m ³ |
| Walling | 230mm thick Block wall | | 83 m ² |
| | 150mm thick Block wall | | 159 m ² |
| | 100mm thick Block wall | | 83 m ² |
| Roofing | 150x150 Rafters | | 127m |
| | 150x150 Tie Beams | | 110m |
| | 150x150 King posts | | 27m |
| | 150x150 Struts | | 213m |
| | 100x50 Thick wall plates | | 36m |
| | 50x50 Purlins | | 123m |
| | 240x20 Thick stained black fascia badge boards | 54m | |
| | 150mm Half round UPVC rainwater gutter fixed to fascial board | 28m | |
| | | | |

| | | | |
|-------------------|--|--|--------|
| | 100mm Diameter UPVC rainwater downpipe | | 15m |
| Windows and Doors | Door size 850 x 2400mm high | | 11 Nos |
| | Door size 850 x 1900mm high | | 14 Nos |
| | Window size 1300 x 1500mm High | | 1 Nos |
| | Window size 775 x 1500mm High | | 2 Nos |
| | Window size 700 x 500mm High | | 20 Nos |

2.9.2 Labour force

The labour force will be determined by the Contractor; nevertheless it is projected that during the construction phase the project will require about 20 workers both skilled and non-skilled laborers. During operational phase it is estimated that 10 unskilled and semi-skilled workers will be retained for operating the facility.

2.9.3 Machinery and Equipment

The proposed project development will employ various standard construction equipment and machinery. Equipment expected to be used during the construction works are Tippers, Concrete Mixers, poker vibrators, Wheel barrow, Compactor, etc. All equipment and machineries for construction works needed by the proposed project will be determined when the bill of quantities (BoQ) and selection of Contractor is finalized. These equipments shall be temporary and shall be demobilized once project is completed. On the other hand, the hand tools which will be used during construction phase constitutes; Shovels, hoes, hammer, pickaxe, buckets etc.

2.9.4 Wastes generation

The major wastes generation associated with the project are spoil soils resulting from earthworks during the foundation excavations, solid wastes and liquid waste. The spoil soil shall be stock piled around the public toilet for further use in landscaping the site at the end of the project.

(a) Liquid waste management

A total of 0.5m³ per day of liquid waste is estimated to be generated from temporary lined pit latrines during construction phase. The project construction and operations will conform to the National Effluent Standard of Tanzania which includes pre-treatment through septic tanks before emptying and transportation of sewage to the treatment facility. After the sewage treatment process is done, the effluent which is rich in nutrients is expected to cater for irrigation activities adjacent to the treatment facility. However, in case the nutritious effluent is not used for irrigation, there is a possibility of discharging direct to the receiving water body.

(b) Solid waste management

About 50-100Kg per month of domestic refuse and other solid wastes is estimated to be generated during the construction phase. A well-established solid waste collection system will be instituted. The system will involve among other things wastes segregation at source, recycling or reuse of some wastes and final disposal to the approved dumpsite / landfill.

The project management team will provide waste bins and recycling receptacles of different type to enable sorting. Compostable materials will be sent direct to the city dumpsite area. Table 4 below shows solid and liquid waste wastes to be generated by the project and the methods of their disposal.

Table 4: Management of construction and operation wastes

| Solid waste | | | |
|--|---------------------------------------|---|---|
| Type of waste | Sources | Estimated Quantity (Kg) | Disposal / Management procedure |
| Debris and Rubble (overburden) | Site clearance | 3,000-5,000 | Fill material for road potholes, etc. |
| Biodegradable materials mainly domestic waste (food, paper, wood etc.) | - Construction crew | (20-40) per day | Accessible litter bins within the camp site and later to the city waste disposal system (engage a registered private company) |
| Non- biodegradable materials (plastic, glass) | - Construction crew | (2-5) per day | Recycling/ reuse (Plastics to be sent to authorised plastic recyclers and glass bottles to be sent to glass recyclers) |
| - Construction waste | Masonry works, carpentry and painting | 50 kg | Recycle and reuse unwanted wood pieces, saw dust (for use in stoves and poultry), and paint buckets. |
| Liquid waste | | | |
| Type of waste | Sources | Estimated Quantity (m³) per day | Disposal / Management procedure |
| - Excreta (domestic) human - Grey water /cleaners | - Toilets and floor cleaning | 3.2 | Use of septic tanks and when full will empty to the wastewater treatment facility |

2.10 Project Alternatives

Consideration of project alternatives is crucial in ensuring that the developer and decision-makers have a wider base from which they can choose the most appropriate option. In this comprehensive project brief, the following alternatives are considered.

2.10.1 No project alternative

The no project alternative entails retaining the current status quo without developing the proposed public toilet. Adopting this option would mean avoiding most of the negative effects associated with the establishment of the toilet and missing all the positive benefits that would accrue such as improved community life and reduction of the communicable diseases.

2.10.2 Other project alternative

Other alternative that would have been used includes the rounded floor plan as a new nature of building and using of other onsite wastewater treatment technologies such as ABR.

3.0 POLICIES, LEGISLATION AND INSTITUTIONAL ASPECT

3.1 Overview

According to the fundamental principles of environment, any developmental activities of this nature such as construction of Public Toilet would have socio-economic and somehow environmental impacts that must be addressed and governed in order to serve public interest and sustainable development. Given the many existing and developing environmental laws, regulations and standards in Tanzania, it is worth considering resorting to constitutional provisions to protect and manage the environment. With increasing environmental awareness in recent decades, the environment has become a higher political priority and many constitutions now expressly guarantee a 'right to a healthy environment', as well as the procedural rights necessary to implement and enforce the substantive rights granted. The public or national interest in this aspect is addressed through government Policies and regulated by Principal Acts and Regulations. The implementation of the proposed project shall touch various sectors; therefore, the developer has to comply with number of cross-sectorial policies and legislations relevant to this project. Also, the listed institutions involved in environmental management for the project is included in this chapter.

3.2 Relevant Policies

This section focuses on various policies which guide the development aspects for sustainable vision, apart from the national environmental policy, there are numbers of sector policies that are to be reviewed when executing the proposed development and these include;

3.2.1 National Environment Policy 2021

The National Environmental Policy of 2021 has just been launched in February 2021. The new policy formulation is a revision of the National Environmental Policy of 1997. The Policy serves as a national framework for planning and sustainable management of the environment in a coordinated, holistic and adaptive approach taking into consideration the prevailing and

emerging environmental challenges as well as national and international development issues. Effective implementation of this policy requires mainstreaming of environmental issues at all levels, strengthening institutional governance, and public participation in environmental management regimes. The long-term vision of this policy is geared towards the realization of environmental integrity, assurance of food security, poverty alleviation, and increased contribution of the environmental resources to the national economy. It also recommends strong institutional and governance measures to support the achievement of the desired objectives and goals.

The policy seeks to promote the economy and livelihoods of people while promoting sustainable utilization of natural resources in the country. The policy provides the framework for the formulation of plans, programmes, and guidelines for the achievement of sustainable development.

The policy overall objective is to provide a national framework for guiding harmonized and coordinated environmental management for the improvement of the welfare of present and future generations. The specific objectives are i) to strengthen coordination of environmental management in sectors at all levels; ii) to enhance environmentally sound management of land resources for socioeconomic development; iii) to promote environmental management of water sources; iv) to strengthen conservation of wildlife habitats and biodiversity; v) to enhance conservation of forest ecosystems for sustainable provision of environmental goods and services; vi) to manage pollution for the safe and healthy environment; vii) to strengthen the national capacity for addressing climate change impacts; viii) to enhance conservation of aquatic system for the sustained natural ecosystem; ix) to ensure safety at all levels of application of modern biotechnology; x) to promote gender consideration in environmental management; xi) to promote good governance in environmental management at all levels; and xii) to ensure predictable, accessible, adequate and sustainable financial resources for environmental management.

3.2.2 National Land Policy of 1997

The National Land Policy states that “the overall aim of a National Land Policy is to promote and ensure a secure land tenure system, to encourage the optimal use of land resources, and to facilitate broad-based social and economic development without upsetting or endangering the ecological balance of the environment”. This study partly responds to this requirement.

3.2.3 Construction Industry Policy (2003)

Among the major objectives of the policy, which supports a sustainable building development sector, include the promotion and application of cost effective and innovative technologies and practices to support socio-economic development activities such as sanitation, water supply, buildings, road-works, shelter delivery and income generating activities and to ensure application of practices, technologies and products which are not harmful to either the environment or human health. Proposed project is in-line with this policy as ultra-modern technology is used during construction and its operation.

3.2.4 National Health Policy (2003)

The Health Policy is a vital guide towards health development of any country. It is particularly, important in a country like ours where resources and technology are more limited than in other countries, which are relatively better off in both technology and resources. This Policy is a revision of the 1990 Health Policy, which emphasized on the need for increasing community involvement in health development and improved access and equity in health and health services.

The Policy recognizes the challenges of consolidating the principles of the previous health policy in community involvement, improved health services provision, access and equity while addressing the different dimensions of reforms that are taking place in the Public Sector.

The proposed project will adhere to policy requirements to ensure no transmission of such communicable diseases between construction workers and the community protects workers from all sorts of health risks and hazards;

and provide adequate sanitation services within the project and ensure that its activities are not a source of health issues.

3.2.5 National Gender Policy of 2000

The overall objective of the Gender and Development Policy is to promote gender equality and equal participation of men and women through facilitation of access to education, child care, and employment and decision making. Also this policy is to provide guidelines that will ensure that gender-sensitive plans and strategies are developed in all sectors and institutions. While the policy aims at establishing strategies to eradicate poverty, it emphasizes gender quality and equal opportunity of both men and women to participate in development undertakings and to value the role played by each member of society. The proposed project will follow the requirements addressed under this policy.

3.2.6 National Human Settlements Development Policy (2000)

Among the objectives of this policy is to improve the level of the provision of infrastructure and social services for the development of sustainable human settlements and to make serviced land available for shelter to all sections of the community. Such infrastructure and services constitute the backbone of urban/rural economic activities. Public Toilet is one among of the important infrastructure for Pemba Mnazi ward community and country at large

3.3 PRINCIPAL LEGISLATIONS AND REGULATIONS

The ESIA team reviewed several legislations relevant to the construction of Public toilets. These encompass Principal Acts that support and provide guidelines to implement the intended project as discussed below.

3.3.1 Environmental Management Act (2004)

Among the major purposes of the EMA are to provide the legal and institutional framework for sustainable management of the environment in Tanzania; to outline principles for management, impact and risk assessment, the prevention and control of pollution, waste management, environmental quality standards, public participation, compliance, and enforcement; to

provide the basis for the implementation of international instruments on the environment; to provide for the implementation of the National Environmental Policy; to provide for the establishment of the National Environmental Fund and to provide for other related matters.

Part III, Section 15(a) states that *"in matters about the environment, the Director of Environment shall coordinate various environment management activities being undertaken by other agencies to promote the integration of environmental considerations into development policies, plans, programs, strategies projects and undertake strategic environmental assessments to ensure the proper management and rational utilization of environmental resources on a sustainable basis for the improvement of the quality of human life in Tanzania"*.

Part X of the law deals with Environmental Quality Standards. Section 140 of this act states that *"The National Environmental Standards Committee of the Tanzania Bureau of Standards established under the Tanzania Bureau of Standards Act, 1975 shall develop, review and submit to the Minister proposal for environmental standards and criteria concerning; water quality; discharge of effluent into the water; air quality; control of noise and vibration pollution; sub-sonic vibrations; soil quality, control of noxious smells; light pollution; and any other environmental quality standard"* Some of these standards have already been published in the government *gazette* while others are not in place. This project shall consider all the standards specified by this act.

3.3.2 The Environmental Management (Fees and Charges) Regulations, 2021

These Regulations shall apply in relation to an act or service in respect of which fees and charges are payable under the Act and Regulations made there under. The regulations emphasize that "a person shall not, upon payment of fees and charges prescribed in the Schedule to these Regulations, carry on any of the following":

- Environmental Impact Assessment;
- Environmental Compliance Monitoring and Audit;

- Registration of Environmental Experts;
- Environmental Quality Standards;
- Noise and Vibrations; or
- other activities related to the environment

This project complies with the regulations since the proponent has already paid registration fees and review charges as directed by NEMC.

3.3.3 The Environmental Management (Control of hazardous Waste) Regulations, 2021

The objective of these regulations is to protect the environment and human health by preventing or reducing the generation of Hazardous waste, the adverse impacts of the generation and management of hazardous waste and by reducing overall impacts of resource use and improving the efficiency of such use, which are crucial for the transition to a circular economy. The regulation requires that “any person generating, collecting, storing, transporting, treating, recycling, reusing, recovering and disposing of hazardous waste or any person exercising jurisdiction under these Regulations shall, assure that there are no adverse impacts to be generated or caused by the activity conducted. Project developer will comply with the requirements of this regulation by reducing the construction materials which may generate hazardous impacts, as well as proper handling of such waste such as in use of fuels for various purposes etc.

3.3.4 The Environmental Management (Control of Noise and vibration) Regulations, 2015

The regulations focus on the maintenance of a healthy environment for all the people in Mainland Tanzania, the tranquility of their surrounding and their psychological well-being by regulating noise and vibration levels to prescribe the maximum permissible noise and vibration levels from a facility or activity to which a person may be exposed. The project developer will make sure that all the guidelines under this policy will be considered to ensure the healthy environment to everyone.

3.3.5 The Environmental Management (Prohibition of Plastic Carrier bags) regulations, 2019

Regulations are meant to impose a total ban on the import, export, manufacturing, sale, and use of plastic carrier bags regardless of their thickness. Plastic carrier bags has a wide definition in the Regulations, as a bag made of plastic film, with or without handles, or gussets and to which its layer is in any thickness. The Regulations also categorically state that no person shall sell or offer for sale beverages or other commodities wrapped in plastics unless the nature of such commodities require wrappings by plastics, and restricts any licensing authority from issuing any licenses after the Regulations come into force. Project developer will make sure that there will be no use of plastic bags within the project site and the whole project life time, also in case of the need of carrier bags the proponent will make sure that there will be a n alternative bags which are allowed by the regulations. For the commodities that are wrapped in plastic, then the proponent will make sure that such plastic will be handled properly.

3.3.6 The Environmental Management (Solid Waste Management) Regulations, 2007

The solid waste management regulation of 2007 provides general directive on management of solid waste as follows: -

Regulation detail the requirements and responsibilities for managing solid waste in Tanzania

Highlight waste minimization and cleaner production principles alongside the duty to safeguard the public health and the environment from adverse effects of solid waste. Detail permitting requirements, notably which any person dealing with solid waste as collector, transporter, waste depositor or manager of a transfer station will apply to the LGA for a permit. The local authority will also issue licenses to individuals or companies qualified to operate solid waste disposal sites; permit is required to operate an LGA waste disposal site. The proposed project is expected to generate solid waste in construction phase. Therefore, to comply with this regulation the Project developer will engage the registered solid waste collection contractor.

3.3.7 The Environmental Management (Water Quality) regulations, 2009

Regulations provide for institutional and legal framework for sustainable management and development of water resources; to outline principles for water resources management; to provide for the prevention and control of water pollution; to provide for participation of stakeholders and the general public in implementation of the National Water Policy. These regulations require the sustainable management of water sources and proper use of the available sources without causing any damage towards such sources. Also, the regulations emphasize that it is every one's responsibility to conserve and preserve the available water sources in Tanzania. During all phases of the project there will be water demand, hence the project developer will make sure that there will be a sustainable use of water. Also during construction and maintenance phase the developer will make sure that the water supply pipes will not be damaged in either way.

3.3.8 The Environmental Management (Air Quality) regulations, 2009

The Regulations were formed in order to: -

- Prohibit emissions and releases of hazardous substances into the environment
- Prescribe permissible emission limits and quantities of emissions of sulphur oxide, carbon monoxide, black smoke and suspended particulate matters, nitrogen oxide, ozone, hydrocarbons, dust and lead
- Empower NEMC to issue air pollutant emission permits, enforce compliance, undertake emergency prevention and issue stop orders
- Set baseline parameters on air quality and emissions based on a number of practical considerations and acceptable limits and ensure protection of human health and the environment from various sources of pollution.

The proposed project will follow the requirements of this Act, emission limits will be monitored to the permissible limits.

3.3.9 The Environmental Management (Soil Quality) regulations, 2009

These Regulations made by the Minister of State under sections 143, 144 and 230 of the Environmental Management Act, concern soil pollution and soil quality standards and provide with respect to a soil protection permit and compliance system. They also concern measures of enforcement. The object of these Regulations is to

- Set limits for soil contaminants in agriculture and habitat;
- Enforce minimum soil quality standards prescribed by the National Environmental Standards Committee.

Also, the regulations require that, the contaminants of volatile organic compounds in habitat and agricultural soils shall comply with parameters and upper limits as prescribed and contaminants of heavy metals in habitat; agricultural soils shall comply with parameters and upper limits as prescribed and contaminants of pesticides in habitat and agricultural soils shall comply with parameters and upper limits as prescribed. Local government authority may prescribe special or specific measures and guidelines for soil conservation applicable to their respective areas of jurisdictions which are not below standards prescribed under these Regulations. The Project developer will comply with the requirements made under these regulations.

3.3.10 Occupational Health and Safety Act 2003

The provisions of this law require employers to provide decent working environment to employees to guarantee their health and safety. Occupational health and safety services are important for sustainable development of a country, as they reduce occupational accidents and diseases which can have huge economic burden to individuals, enterprises and the nation as whole. Improving health and safety of workers will significantly increase productivity at the workplaces to encourage more investments, increase job creation, higher morale, and job satisfaction hence industrial harmony. The law also entails employers to fulfill obligations of ensuring safety of the equipment's used by workers and providing proper safety gears as required.

3.3.11 Water Supply and Sanitation Act No. 12 of 2009

This is also a new legislation that provides for sustainable management and adequate operation and transparent regulation of water supply and sanitation services; provides for establishment of water supply and sanitation authorities as well as community owned water supply organizations; and provides for appointment for service providers. The main aim of this law is to ensure the right of every Tanzanian to have access to efficient, effective and sustainable water supply and sanitation services for all purposes by taking into account among others protection and conservation of water resources and development and promotion of public health and sanitation; and protection of the interest of customers. Under this law, the Minister responsible for water affairs shall establish water authority and cluster water authorities in order to achieve commercial viabilities.

3.3.12 Engineers Registration Act and its Amendments 1997 and 2007

The Acts regulate the engineering practice in Tanzania by registering engineers and monitoring their conduct. It establishes the Engineering Registration Board (ERB), the law requires any local or foreigner engineer to register with (ERB) before practicing in the country. Project developer will continue to comply as it has utilized the services of registered engineering firm for its structural designs which it will continue to use to supervise the construction process.

3.3.13 Contractors Registration (Amendment) Act, 2008

The Contractors Registration Act requires contractors to be registered by the Contractors Board (CRB) before engaging in practice. It requires foreign contractors to be registered by the Board before gaining contracts in Tanzania. Project Developer shall comply with the law requirement during the recruitment of contractors for project implementation.

3.3.14 Architects and Quantity Surveyors Act (1997)

The Act requires Architects and Quantity Surveyors to be involved in the project to be registered by the Architects and Quantity Surveyor Board

(AQSB) before engaging in practice. It also requires foreign contractors to be registered by the Board before gaining contracts in Tanzania. Project Developer has complied with the law requirement during the recruitment of architects who have designed the project and will continue to utilize registered persons in the project implementation.

3.3.15 Urban Planning Act Cap. 355 (2007)

The law provides for the orderly and sustainable development of land in urban areas, to preserve and improve amenities; to provide for the grant of consent to develop land and powers of control over the use of land and to provide for other related matters. Under Section 3, among others the law seeks to improve level of the provision of infrastructure and social services for sustainable human settlement development. This act established planning authorities which include the city, municipal, town and township councils in the country which have responsibilities including:

- Secure the orderly and environmentally sustainable development of area under its jurisdiction;
- Prepare general and detailed planning schemes;
- Control building densities and access to buildings;
- Recommending approval of building schemes and subdivision of plots by developers;
- Secure cooperation of all agencies, utility bodies, land owners and other bodies and institutions involved in the preparation and implementation of planning process;

3.3.16 The Urban Planning (Planning Space Standards) Regulations, 2018

The Urban Planning Space Standards" include standards for residential areas, unplanned settlements, building height, building lines and setbacks, floor are, plot coverage and plot ratio, health facilities, education facilities, recreation facilities, beach facilities, golf course, passive and active recreation, public facilities by planning levels, public facilities by population size, parking and road width and agricultural show grounds.

3.3.17 Urban Planning (Use Groups and Use Classes) Regulations, 2018

For the purposes of planning and the control of development, all uses of land and buildings are categorized in the use groups and use classes in the First Schedule. The planning authority may, under special circumstances (Second Schedule); permit any use not classified under a separate use class in these regulations provided that such use is in the public interest.

3.3.18 The Urban Planning (Zoning Of Land Use) Regulations, 2018

These Regulations revoke the Town and Country Planning (Zoning of Land Uses) Regulations, 1960. The Regulations define the zones for land uses and mapping colours that shall be as prescribed in the Schedules to these Regulations. Where there is uncertainty with regard to the boundaries of the zones in the approved maps, schemes or plans, such uncertainty shall be referred to the Authority.

For the purposes of these Regulations, uses of land that are permitted and those that may be permitted under special circumstances by the planning authority in different zones of the local planning area shall be as follows:

- (i) Residential
- (ii) Commercial (Retail and Wholesale)
- (iii) Industrial (Light, Medium, Heavy & Service)
- (iv) Institutional
- (v) Public Utilities
- (vi) Beach, Open Spaces and Recreational
- (vii) Transportation, Communication and Microwave towers
- (viii) Agricultural
- (ix) Water bodies
- (x) Conservation
- (xi) Economic Development

3.3.19 Public Health Act (2009)

Provide for the promotion, preservation, maintenance of public health with a view to ensuring the provisions of comprehensive, functional and sustainable public health services to the general public. Part III (e) of the act requires premises owners to keep their premises free of mosquitoes and other disease vectors, vermin or causative agents; Section 54 prohibits causing or suffering from nuisance likely to be injurious or dangerous to health, land, premises, air or water; Part IV (c) assigns responsibility to City council to remove or appoint an agent to collect, transport and dispose solid and liquid waste and charge fees to beneficiaries of this service and responsibilities for prescribing types of wastes and guidelines for their collection and disposal; Section 101 it gives rights to any private sewer to connect it to any available public sewer to discharge foul or storm water therefore the project may connect to and discharge sewage or storm water into the available trunk main. However, the quality of the sewage should be as per agreed with the water authority.

The Contracting Authority will ensure that the project design, construction and operation do not constitute a nuisance; meets the requirements meets public health requirements.

3.3.20 World Bank guidelines for Environmental Management

The main objective of this EMP is to establish a set of mitigation and monitoring measures to minimize the adverse social and environmental impacts that can take place during the implementation stage of the subproject. The measures especially focus on sensitive receptors or sensitive locations. The EMP also provides specific information about the monitoring program during construction stage including locations, frequency and reporting process. This project complies with these guidelines as it has ESMP which contains mitigation and monitoring plans of the identified impacts.

4.0 BASELINE INFORMATION

4.1 Water Table and water quality analysis

While there is no permanent surface water sources in the vicinity of the proposed site for the Public Toilet, groundwater resources is of concern. Groundwater is abundant in almost the entire city of Dar es Salaam. This is evidenced by the fact that shallow wells are one of the sources of domestic water supply for most of the households around the project site and therefore the water table is high.

Data for Water quality from shallow wells close to the project site were not immediately available during this study. However previous studies of the similar areas indicate the high possibility of groundwater contamination from adjacent pit latrines located less than 30m horizontal distance from the shallow well (Still and Nash, 2002).

4.2 Air quality

The air quality observations indicate that the general air quality in the project area is good as there is no any strange activity contributing to air pollution. However, seasonal variation as well as localized and temporal deterioration in air quality does occur. Smokes and greenhouse gases such as carbon dioxide, carbon monoxide are expected to be emitted from moving vehicles due to the burning of fossil fuels which passes at Mloganzila road which and other street roads closer to the project area. During construction phase, air quality of the area will be impacted and the proponent will be advised to use good quality material transportation vehicles.

4.3 Noise and vibrations

The noise level at the project area is mainly due to moving vehicle along the road, moving air (wind) or rain and birds. Project activities during construction will change patterns and amplitude of noise in the project area. Operations of construction machines may cause adverse impacts on local residents, and on

workers. The proponent have to ensure proper provision of ear mask to the workers and all works have to be executing during the day time.

Similarly, vibration levels in the area is quite low or insignificant. Again the main source are moving vehicles. During construction phase, the constructor shall abide to national standards of 75dBA for an average noise level and 5mm/s PPV for ground vibration at all times.

4.4 Climate

Kwembe ward in Ubungo Municipality of Dar es Salaam Region in which the proposed site is located is close to the warm Indian Ocean. Thus, the area experiences a tropical wet and dry climate with hot and humid weather throughout the year. Generally, site area has two distinct rainy seasons, 'long' rains during April and May, and 'short' rains during October and November with a mean annual rainfall of between 800 – 1200mm. The average annual daily temperatures range between 21.9°C and 29.6°C. The climate is also influenced by the south-westerly monsoon winds from April to October and north-westerly monsoon winds between November and March (TMA, 2011). Implementation of Public toilet project will not affect the climate in Mloganzila area.

5.0 POTENTIAL IMPACTS

5.1 Mobilization Phase

5.1.1 Positive impacts

5.1.1.1 Employment opportunities

Labour force for the project will be originated from Kwembe ward and the surrounding communities particularly business people using the Mloganzila Bus Stand. Even though during construction the employment will be on short term basis, employees will have been benefiting from the project. Some will witness their incomes and family level of life improved.

5.1.2 Negative impacts

5.1.2.1 Noise pollution

Noise pollution is likely to occur due to the application of construction equipment and generators at the site.

Mitigation Measure

- The proponent shall maintain equipment in good running conditions to ensure that ambient noise level and vibrations pollution into the environment is very minimum to comply with Tanzania standards.
- The noisy construction activities will be scheduled at normal working hours. Regular inspection and maintenance of construction vehicles and equipment will be done to ensure that they have mufflers installed and worn parts are replaced

5.1.2.2 Air Pollution from dust emission

Air pollution is likely to occur due to the emission of suspended particulate matter (dust) to the atmosphere from the construction activities.

Mitigation Measure

- Mixing equipment shall be sealed properly and vibrating equipment will be equipped with dust removing devices.
- Also all vehicles that generate excessive black smoke will not be used.
- Adequate training and use of personal protective equipment (PPE) such as eye glasses and dust masks will be ensured in order to reduce risks associated with dust.

5.2 Construction Phase

5.2.1 Positive Impacts

5.2.1.1 Employment opportunities

Labour force for the project will be originated from Kwembe ward and the surrounding communities particularly business people using the Mloganzila Bus Stand. Even though during construction the employment will be on short term basis, employees will have been benefiting from the project. Some will witness their incomes and family level of life improved.

5.2.1.2 Improved living conditions and economic growth

The project will improve the living conditions in Ubungo Municipal whereby the project operation phase will do away with open urination. The charged fee for using the facility will be such as affordable by the intended user. Thus, there will be dignity and increased money circulation that result into increased income consequently better standard of living of people in the project area.

5.2.1.3 Improved public health

In crowded areas particularly Mloganzila Bus stands, it is normally hard to ensure safety to public health without the establishment of sound infrastructures. With the public toilet at crowded areas like markets and bus stands which offers a number of services under one umbrella, it is anticipated that the general health condition will not be endangered from health risks.

5.2.1.4 Increased socio-cultural interaction

Increased socio-cultural interaction is another anticipated positive impact. The implementation of the project will bring many people from different cultural backgrounds. The interactions may bring about social changes in the communities around the project areas. Interaction with technocrats as a result of new immigrants (customers) into the area will stimulate adoption of the new technologies.

5.2.1.5 Increased Revenue to the nation through taxes, both direct and indirect

The public toilet facility constructed by DAWASA is expected to be operated by the Ubungo Municipal. Therefore, it is expected to increase government revenue collection at Municipal and at National level. This will be enhanced by time to time payment of service by users. The revenue collected will contribute towards economic development within the municipal and the country at large.

5.2.2 Negative impacts

5.2.2.1 Increased HIV/AIDS and other sexual related diseases:

Local communities surrounding the project area have to be aware of the fact that HIV/AIDS is present in their areas but accede to it not being at an alarming rate. The communities were worried that with an influx of people into the project area the pace of spread will accelerate especially during the construction phase.

Mitigation Measures

- Contractor shall enforce a code of conduct in the project area to encourage respect for the local community and to maintain self-cleanliness of the working area at all times.

 - The contractor shall deploy locally available labour to reduce risk of spreading communicable diseases (especially STDs).
-

- In order to prevent more HIV/AIDS infection, during the implementation phase, the project should include information education and communication component (IEC) in its budget. This will help to raise more awareness on HIV/AIDS, and means to suppress its incidence.
- A safety, health and environment induction course shall be conducted to toilet operators.
- Awareness posters (like prevention against HIV/AIDS) shall be displayed at toilet facility.

5.2.2.2 Destruction and infringement of properties

Within and adjacent to the proposed project site there are small and temporary structures made from wood nailed with steel sheets and solid waste collection point. Such temporary structures accommodate the existing small businesses especially food vendors (*Mamantilie*), shops, kiosks and mini-supermarkets. Therefore construction of the Public toilet might necessitate the destruction of such facilities.

Mitigation Measures

- Close supervision of construction works shall be observed in order to confine land clearance within the area where the construction activities are to take place to avoid unnecessary demolition.

5.2.2.3 Noise pollution

Noise pollution is likely to occur due to the application of construction equipment and generators at the site.

Mitigation Measure

- The proponent shall maintain equipment in good running conditions to ensure that ambient noise level and vibrations pollution into the environment is very minimum to comply with Tanzania standards

- The noisy construction activities will be scheduled at normal working hours. Regular inspection and maintenance of construction vehicles and equipment will be done to ensure that they have mufflers installed and worn parts are replaced

5.2.2.4 Air Pollution from dust emission

Air pollution is likely to occur due to the emission of suspended particulate matter (dust) to the atmosphere from the construction activities.

Mitigation Measure

- Mixing equipment shall be sealed properly and vibrating equipment will be equipped with dust removing devices.
- Also all vehicles that generate excessive black smoke will not be used.
- Adequate training and use of personal protective equipment (PPE) such as eye glasses and dust masks will be ensured in order to reduce risks associated with dust.

5.2.2.5 Potential communicable diseases transmission

Many people from different places and of different health status will be using the toilet. This creates a premise for potential transmission of different communicable diseases of wide range including diarrheas, typhoid, COVID-19 etc.

Mitigation measures

- Ensure supply of adequate provisions like water, toilet papers, soaps, disinfectants etc
- Maintain high level of cleanliness
- Install guidelines on the usage of toilets

5.2.2.6 Smells and flies in toilets

Inadequate attention to the public toilet may render the facility a liability to adjacent land users and businesses. Drainage system blockage due to misuse of toilet can be a source of sewage overflows and hence the area around becoming a nuisance to people. Overflowing sewage will produce awful smell of decomposing organic matter that lowers the air quality in the

vicinity. Experience shows that, abandoned public toilets in Tanzania easily become centers for vagabond boys to plan evil acts in the society.

Mitigation measures

- The developer to ensure adequate supply of provisions
- Adhere to good maintenance
- Timely desludging

5.2.2.7 High Risk of Health associated with construction work

Construction activities exposes the workers to a lot of risks for example risk of falling into the excavated pits more than 3metres deep, risk of injuries from falling objects or sharp pointed objects e.t.c

Mitigation measure

- The project proponent shall ensure that all personnel are provided with appropriate protective gear.
- All works shall be planned and conducted in accordance with relevant OHS Guidelines. First Aid Kit as well as regular medical check-ups for the workers will be provided during the entire working hours.
- Adequate number of firefighting equipment/extinguishers will be provided in every few distance to help putting off fire in case of occurrence.
- Excavated pits should be protected by warning tape and guardrails to prevent workers from falling

5.2.2.8 Waste generation during construction

A lot of waste will be generated especially during construction stage. For example, excavation of foundations will generate a lot of spoil materials that will need to be disposed of. Construction of walls and roof will both generate wastes. Other wastes will be generated from cleaning of construction equipment and containers like mixers and paint buckets.

Mitigation measures:

- Stick to the design specifications
-

- Provide waste containers
- Provide training to workers and orient them towards environmental protection values

5.2.2.9 Groundwater contamination from soil sterilization

Ground water contamination from soil sterilization chemicals is likely to occur because some of the chemicals listed above are toxic to animal and plant life.

Mitigation measures:

- Stick to the design specifications
- Chemicals must be applied only with caution by an experienced person
- Treatment shall not be made when soils of fill are excessively wet or immediately after heavy rain.
- Precautions must also be taken to prevent disturbance of the treatment by animals or human contact with the treated soil.
- The treated area is to be covered as quickly as possible after treatment.
- The rate of application is to be 5 litres per square metre and the areas measured include those under floor and round wall and column foundations.

5.3 Operation Phase

5.3.1 Positive Impacts

5.3.1.1 Improved social-economic livelihood and dignity within the beneficiary society

The project will improve the living conditions in Ubungo Municipal specifically at Mloganzila bus stand whereby the project operation phase will do away with open defecation and urination. Thus, there will be increased money circulation that result into increased income consequently better standard of living of people in the project area.

5.3.1.2 Increased Revenue to the nation through taxes, both direct and indirect

Ubungo Municipall is expected to increase its revenue collection on implementing this project. This will be through daily payment of facility usage services by the respective customer. The revenue collected will contribute towards implementation of other development projects.

5.3.2 Negative Impacts

5.3.2.1 Smells and flies in toilets

Inadequate attention to the public toilet may render the facility a liability to adjacent land users and businesses. Drainage system blockage due to misuse of toilet can be a source of sewage overflows and hence the area around becoming a nuisance to people. Overflowing sewage will produce awful smell of decomposing organic matter that lowers the air quality in the vicinity. Experience shows that, abandoned public toilets in Tanzania easily become centers for vagabond boys to plan evil acts in the society.

Mitigation measures

- The developer to ensure adequate supply of provisions
- Adhere to good maintenance and good housekeeping
- Timely desludging

5.3.2.2 Health Risks to Cleaners

Cleaners who will be attending the public toilets are likely to be exposed to high risks of communicable diseases. Their work environment is at high risk of faecal contamination.

Mitigation measures

- The project proponent shall ensure that all the cleaning personnel are provided with appropriate protective gear like (gloves and masks).
 - There will be good supply of appropriate disinfectants to be applied to contaminated surface for the purpose of killing germs.
-

- Awareness seminars shall be given to cleaners once every six months apart from an obligatory induction course.

5.3.2.3 Low revenue collection due to low affordability of customers

The fact that public toilets are necessary does not mean that everyone can afford to use it. The rising cost of living in Dar es Salaam, may affect the affordability of customers to use the toilets. Should this happen, there will be a decline in revenue collections from the expected levels. On the other hand, haphazard defaecation of urination may be common around the bus stands and market areas, which can lead to unsightly environment and eruption of epidemics.

Mitigation measures

- DAWASA and Municipal Councils shall undertake a research to determine affordable prices for using the toilets.
- Alternative financing of the public toilets may be sought for example charging it through bus stand and market fees.

6.0 ACTION PLAN FOR PREVENTION AND MANAGEMENT OF ACCIDENTS DURING IMPLEMENTATION STAGE

The project shall be implemented in compliance to labour laws in Tanzania, in particular, the Occupational Health and Safety Act (2003). Clauses to protect the health and safety of workers shall be included in the contract documents for implementation stage.

6.1 Occupational Health and Safety

The proponent is committed to protect the health and safety of its employees and those of its contractors, to ensuring that activities are conducted in a manner that protects the environment and people. The Contractor shall provide and enforce the use of appropriate personal protective equipment for all workers e.g. overalls, gloves, masks, etc. (wherever required). Tanzanian/international construction standards will be followed for quality and safety to workers. First aid facility will be installed at the construction site.

6.1.1 Emergency preparedness Plan

The proponent is committed to ensure the availability of the emergency preparedness plan in place prior to commencement of construction phase. Among others the plan should contain; identified risks, Team Build up, Availability of critical information, updated alert and response procedures and ensuring that the plan is working by putting it to some tests.

6.2 Security

The whole proposed project will take care of security matter of the site by fencing the whole project area and provide gates for entrance and exit purpose. The project proponent shall have a 24 hours security services from a private company to secure the whole project premise at the site. Also since the nature of investment involves fecal sludge management facility with the potential of biogas production. The project proponent will install the best firefighting system at site. The purpose of fire protection is to protect life, good and activities within the project site.

The following are some of the active and passive fire fighting equipment that will be employed;

- Fire detection system
- Fire hydrant system
- Portable Fire Extinguishers

6.3 Monitoring, Maintenance and repair

The management of the facility will be upon both DAWASA and Ubungo Municipal Council to ensure the approved design or plan is implemented accordingly. Furthermore, provision of basic services is being executed at high quality as intended for. However, the facility users will also have to ensure they are responsible with the common matters such as general cleanliness of the facility through; thorough flushing after use, avoid disposing diapers and littering within the toilet sink, paying service fees, etc

7.0 ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN

7.1 Environmental and Social Management Plan

The Environmental and Social Management Plan (ESMP) presents the implementation schedule of the proposed mitigation measures for both environmental and social impacts. The ESMP for the proposed Construction of Public Toilet at Mloganzila Bus Stand is summarized in Table 5. The ESMP also indicates environmental costs needed to implement the recommended mitigation measures. The public toilet site selection process and engineering designs have already included some of the mitigation measures recommended in this report. Additional recommendations are provided in the ESMP to enable the public toilet to be constructed and operated in environmentally friendly manner.

DAWASA in collaboration with Ubungo Municipality shall be the main implementer of the ESMP through. The environmental measures incorporated in the detailed engineering design will be attached to the Bills of Quantities and Contract Documents. Moreover, there will be a Environmental, Social, Health and Safety (ESHS) Code of Conduct to be signed by the Contractor(s) to show their commitment in the implementation of the Environmental, Social, Health and Safety. The implementation of the Code will be supervised by DAWASA or his consultant.

The ESHS Code is a set of Guidelines attached to the Bidding Document and Contract to be adopted by Contractor during project implementation. It contains the commitment and obligations of the Contractor and its subsidiaries (i.e. Sub-Contractors and staff) to undertake construction activities in accordance with all applicable Laws, Rules, and Regulations. The Contractor and its subsidiaries shall comply with the Code of Conduct with high ethical standards. Failure to observe the Code, will subject the firm to disciplinary action, including Contract termination. Violation of the Code, is violation of Law which may result to civil and/or criminal penalties to Contractors, Supervisors or Firm.

Some of the issues to be included in the ESHS shall include;

- Site specific **ESMP, HSMP,**
- Traffic Management Plan (**TMP**), **where applicable**
- HIV/AIDS Awareness Program,
- Occupational Health and Safety Awareness Program.
- Sexual Harassment prevention Policy
- Child Labour Prevention Policy

The environmental and social mitigation and enhancement measures incorporated in the detailed engineering design will be attached to the Contract Documents. The Contractor shall take stock of the contents of the Project Brief.

Table 5: Environmental and Social Management Plan for the Proposed Construction of Public Toilet at Mloganzila Bus Stand, Kwembe ward, Ubungo Municipality

| Impact | Mitigation Measure | Responsible Institution | Estimated Time Cost (TZS) | One | Estimated Annual cost (TZS) |
|-------------------------------------|--|--|----------------------------------|------------|------------------------------------|
| Mobilization Phase | | | | | |
| Increased waste generation | <ul style="list-style-type: none"> ○ Stick to the design specifications ○ Provide waste containers ○ Provide training to workers and orient them towards environmental protection values | Contractor/DAWASA/Ubungo Municipal Council | To be included in the BOQ | | |
| Noise pollution during construction | <ul style="list-style-type: none"> ○ The proponent shall maintain equipment in good running conditions to ensure that ambient noise level and vibrations pollution into the environment is very minimum to comply with Tanzania standards ○ All construction works will be scheduled at normal working hours. ○ Proper inspection | Contractor/DAWASA/Ubungo Municipal Council | 500,000.00 | | |

Project Brief of the Proposed Public Toilet at Mloganzila Bus Stand

| Impact | Mitigation Measure | Responsible Institution | Estimated One Time Cost (TZS) | Estimated Annual cost (TZS) |
|----------------------------------|---|--|--------------------------------------|------------------------------------|
| | and maintenance of construction vehicles and equipment will be done to ensure that they have mufflers installed and worn parts are replaced | | | |
| Construction Phase | | | | |
| Increased waste generation | <ul style="list-style-type: none"> ○ Stick to the design specifications ○ Provide waste containers ○ Provide training to workers and orient them towards environmental protection values | Contractor/DAWASA/Ubungo Municipal Council | To be included in the BOQ | |
| Increased HIV/AIDS and other STD | <ul style="list-style-type: none"> ○ Contractor shall enforce a code of conduct in the project area to encourage respect for the local community and to maintain self-cleanliness of the working area at all times. ○ The contractor shall deploy locally available | Contractor/DAWASA/Ubungo Municipal Council | 5,000,000.00 | |

| Impact | Mitigation Measure | Responsible Institution | Estimated Time Cost (TZS) | One | Estimated Annual cost (TZS) |
|--------|--|-------------------------|---------------------------|-----|-----------------------------|
| | <p>labour to reduce risk of spreading communicable diseases (especially STDs).</p> <ul style="list-style-type: none"> ○ In order to prevent more HIV/AIDS infection, during the implementation phase, the project should include information education and communication component (IEC) in its budget. This will help to raise more awareness on HIV/AIDS, and means to suppress its incidence. ○ A safety, health and environment induction course shall be conducted to all workers, putting more emphasis on HIV/AIDS, which has | | | | |

Project Brief of the Proposed Public Toilet at Mloganzila Bus Stand

| Impact | Mitigation Measure | Responsible Institution | Estimated One Time Cost (TZS) | Estimated Annual cost (TZS) |
|--|---|--|--------------------------------------|------------------------------------|
| | become a national disaster. | | | |
| Land degradation and increased erosion | <ul style="list-style-type: none"> o The contractor should pave the walkways prone to erosion whose quantities are shown in the BoQ o To obtain the construction materials official negotiated should be performed with wards leaders in order to avoid conflict. | Contractor/DAWASA/Ubungo Municipal Council | 25,000,000 | |
| Noise pollution during construction | <ul style="list-style-type: none"> o The proponent shall maintain equipment in good running conditions to ensure that ambient noise level and vibrations pollution into the environment is very minimum to comply with Tanzania standards o All construction works will be scheduled at normal working hours. | Contractor/DAWASA/Ubungo Municipal Council | 1,000,000.00 | |

Project Brief of the Proposed Public Toilet at Mloganzila Bus Stand

| Impact | Mitigation Measure | Responsible Institution | Estimated One Time Cost (TZS) | Estimated Annual cost (TZS) |
|-------------------------------------|---|--|--------------------------------------|------------------------------------|
| | <ul style="list-style-type: none"> ○ Proper inspection and maintenance of construction vehicles and equipment will be done to ensure that they have mufflers installed and worn parts are replaced | | | |
| Dust generation during construction | <ul style="list-style-type: none"> ○ Mixing equipment shall be sealed properly and vibrating equipment will be equipped with dust removing devices. ○ Also all vehicles that generate excessive black smoke will not be used. ○ Adequate training and use of personal protective equipment (PPE) such as eye glasses and dust masks will be ensured in order to reduce risks associated with dust. | Contractor/DAWASA/Ubungo Municipal Council | 3,000,000.00 | |
| Health Risks | <ul style="list-style-type: none"> ○ The project proponent | Contractor/DAWASA/Ubungo | 3,000,000.00 | |

| Impact | Mitigation Measure | Responsible Institution | Estimated Time Cost (TZS) | One | Estimated Annual cost (TZS) |
|------------------------------------|--|-------------------------|---------------------------|-----|-----------------------------|
| associated with construction works | <p>shall ensure that all personnel are provided with appropriate protective gear.</p> <ul style="list-style-type: none"> ○ All works shall be planned and conducted in accordance with relevant OHS Guidelines. First Aid Kit as well as regular medical check-ups for the workers will be provided during the entire working hours. ○ Adequate number of firefighting equipment/extinguishers will be provided in every few distance to help putting off fire in case of occurrence. ○ Excavated pits should be protected by warning | Municipal Council | | | |

Project Brief of the Proposed Public Toilet at Mloganzila Bus Stand

| Impact | Mitigation Measure | Responsible Institution | Estimated Time Cost (TZS) | Estimated Annual cost (TZS) |
|-------------------------------------|---|--|---------------------------|-----------------------------|
| | <ul style="list-style-type: none"> tape and guardrails to prevent workers from falling ○ The developer to ensure adequate supply of provisions ○ Adhere to good maintenance | | | |
| Demobilization phase | | | | |
| Noise pollution during construction | <ul style="list-style-type: none"> ○ The proponent shall maintain equipment in good running conditions to ensure that ambient noise level and vibrations pollution into the environment is very minimum to comply with Tanzania standards ○ All construction works will be scheduled at normal working hours. ○ Proper inspection and maintenance of construction vehicles and | Contractor/DAWASA/Ubungo Municipal Council | 500,000.00 | |

| Impact | Mitigation Measure | Responsible Institution | Estimated One Time Cost (TZS) | Estimated Annual cost (TZS) |
|---|--|---|----------------------------------|-----------------------------|
| | equipment will be done to ensure that they have mufflers installed and worn parts are replaced | | | |
| Operational Phase | | | | |
| Health Risks associated with construction works | <ul style="list-style-type: none"> ○ The project proponent shall ensure that all personnel are provided with appropriate protective gear. ○ All works shall be planned and conducted in accordance with relevant OHS Guidelines. First Aid Kit as well as regular medical check-ups for the workers will be provided during the entire working hours. ○ Adequate number of firefighting equipment/extinguishers will be provided in every | Contractor/DAWASA/Ubugo Municipal Council | Depend on the operational manual | |

Project Brief of the Proposed Public Toilet at Mloganzila Bus Stand

| Impact | Mitigation Measure | Responsible Institution | Estimated One Time Cost (TZS) | Estimated Annual cost (TZS) |
|--------------|--|-------------------------|-------------------------------|-----------------------------|
| | <p>few distance to help putting off fire in case of occurrence.</p> <ul style="list-style-type: none"> ○ Excavated pits should be protected by warning tape and guardrails to prevent workers from falling ○ The developer to ensure adequate supply of provisions ○ Adhere to good maintenance | | | |
| Total | | | 38,000,000.00 | 38,000,000.00 |

8.0 MONITORING PLAN

8.1 Environmental Monitoring

The national EIA guidelines require the developer to prepare and undertake monitoring plan of implemented development projects. Monitoring is needed to check if and to what extent the impacts are mitigated, benefits enhanced and new problems addressed. Recommendations for monitoring have been included in the Table 5. The monitoring plan also assigns responsibilities for different actors. Moreover, the ward and street environmental committees will shoulder the long-term monitoring of the project.

Table 6: Monitoring Plan for the Proposed Construction of Public Toilet at Mloganzila Bus Stand in Kwembe ward, Ubungo Municipality

| Parameter | Monitoring Frequency | Sampling Area | Measurement Unit | Method | Target Level/Standard | Responsibility for monitoring | Estimated Annual (or once cost (TZS) |
|---------------------------|------------------------|--------------------------------|---|------------------------------------|--|---|--------------------------------------|
| Mobilization Phase | | | | | | | |
| Dust | Daily | Immediate working area | Presence of nuisance dust | Physical-visual | - | Contractor/Kwembe ward | None |
| Air Quality | Daily | Around the Inspection chambers | Presence of smells | Smelling (nasal) | Absence of nuisance smells | Kwembe ward/DAWASA/Ubungo Municipal Council | 2,500,000.00 |
| Waste Generation | Weekly | At the working area | Amount of waste | Physical measurement or estimation | All waste contained | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | In BOQ |
| Health risks | Daily | At working area | Accidents | Counting | NO accident | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | In BOQ |
| HIV/AIDS | Monthly | Workers | Training | Numbers | One per month during construction phase only | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | 5,000,000.00 |
| Biodiversity | Once (at commencement) | Working area | Destruction of habitat or removal of biodiversity | Area affected | Minimal disturbance to biodiversity | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | 1,000,000.00 |
| Construction phase | | | | | | | |
| Dust | Weekly | Immediate working | Presence of nuisance dust | Physical-visual | - | Contractor/Kwembe ward | None |

Project Brief of the Proposed Public Toilet at Mloganzila Bus Stand

| Parameter | Monitoring Frequency | Sampling Area | Measurement Unit | Method | Target Level/Standard | Responsibility for monitoring | Estimated Annual (or once cost) (TZS) |
|-----------------------------|------------------------|--------------------------------|---|------------------------------------|--|---|---------------------------------------|
| | | area | | | | | |
| Air Quality | Weekly | Around the Inspection chambers | Presence of smells | Smelling (nasal) | Absence of nuisance smells | Kwembe ward/DAWASA/Ubungo Municipal Council | 2,500,000.00 |
| Waste Generation | Weekly | At the working area | Amount of waste | Physical measurement or estimation | All waste contained | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | In BOQ |
| Health risks | Daily | At working area | Accidents | Counting | NO accident | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | In BOQ |
| HIV/AIDS | Monthly | Workers | Training | Numbers | One per month during construction phase only | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | 5,000,000.00 |
| Biodiversity | Once (at commencement) | Working area | Destruction of habitat or removal of biodiversity | Area affected | Minimal disturbance to biodiversity | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | 1,000,000.00 |
| Demobilization Phase | | | | | | | |
| Dust | Weekly | Immediate working area | Presence of nuisance dust | Physical-visual | - | Contractor/Kwembe ward | None |
| Air Quality | Weekly | Around the Inspection chambers | Presence of smells | Smelling (nasal) | Absence of nuisance smells | Kwembe ward/DAWASA/Ubungo Municipal Council | 500,000.00 |

Project Brief of the Proposed Public Toilet at Mloganzila Bus Stand

| Parameter | Monitoring Frequency | Sampling Area | Measurement Unit | Method | Target Level/Standard | Responsibility for monitoring | Estimated Annual (or once cost (TZS) |
|------------------------|------------------------|--------------------------------|---|------------------------------------|--|---|--------------------------------------|
| Waste Generation | Weekly | At the working area | Amount of waste | Physical measurement or estimation | All waste contained | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | In BOQ |
| Health risks | Daily | At working area | Accidents | Counting | NO accident | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | In BOQ |
| HIV/AIDS | Monthly | Workers | Training | Numbers | One per month during construction phase only | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | 5,000,000.00 |
| Biodiversity | Once (at commencement) | Working area | Destruction of habitat or removal of biodiversity | Area affected | Minimal disturbance to biodiversity | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | 1,000,000.00 |
| Operation phase | | | | | | | |
| Air Quality | Monthly | Around the Inspection chambers | Presence of smells | Smelling (nasal) | Absence of nuisance smells | Kwembe ward/DAWASA/Ubungo Municipal Council | 500,000.00 |
| Waste Generation | Monthly | At the working area | Amount of waste | Physical measurement or estimation | All waste contained | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | In operation manual |
| Health risks | Monthly | At working area | Accidents | Counting | NO accident | Contractor/ Kwembe ward/DAWASA/Ubungo Municipal Council | In operation manual |
| HIV/AIDS | Annually | Workers | Training | Numbers | One per month during | Contractor/ Kwembe ward/DAWASA/Ubungo | In operation manual |

Project Brief of the Proposed Public Toilet at Mloganzila Bus Stand

| Parameter | Monitoring Frequency | Sampling Area | Measurement Unit | Method | Target Level/Standard | Responsibility for monitoring | Estimated Annual (or once cost (TZS) |
|--------------|----------------------|---------------|------------------|--------|-------------------------|-------------------------------|--------------------------------------|
| | | | | | construction phase only | Municipal Council | |
| Total | | | | | | | 24,000,000.00 |

9.0 PROJECT BUDGET

The investment cost for the proposed Public Toilet is estimated to be around Tshs 45 Million that will be financed The World Bank.

10.0 STAKEHOLDER VIEWS ON THE PROPOSED PROJECT

During the conduction of this study, different stakeholders were consulted. Among these include the Ubungo Municipal Council and community at Mloganzila Bus Stand (see Figure 6). Consultations were made through meetings held on 17th July 2020.



Figure 6: Stakeholder's consultation meeting with Ubungo Municipal staff and Mloganzila business people

During the meeting, the consultant gave a brief explanation on the proposed public toilet. The project description covered proposed location, type and design of toilet (a typical design was displayed), construction materials, faecal sludge emptying and disposal. The stakeholders were given chance give their views on the project. Moreover, the consultant offered chance to clarify issues where stakeholders wanted to be given more explanations. The comments by stakeholders were analyzed and incorporated in the design of mitigation measures. Table 6 summarizes the issues raised. The names of the stakeholders consulted are given in Appendix II.

Table 7: Issues and concerns rose by stakeholders

| Institution | Name | Position | Issues/ concerns | |
|--------------------------|-------------|----------|---|--|
| UBUNGO MUNICIPAL COUNCIL | Leah Siware | MCHUMI | -The Public toilet will add revenue to the Municipality | Section 7.2.1.2 Section7.2.1.3 Section 7.2.1.5 |

11.0 CONCLUSIONS AND RECOMMENDATIONS

The proposed Public Toilet project in Mlonganzila Mtaa, Kwembe Ward, Ubungo Municipality, Dar es Salaam Region, is regarded as a small project. The project benefits includes in principle to improve promote public health through proper waste management (in particular improved sanitation). When there is a good and improved sanitation, then the outbreak of diseases like waterborne diseases are reduced or prevented hence achieving improved public health. The facility shall also generate income to the municipality. Moreover, the proposed location of the public toilet is not in environmentally sensitive area.

The anticipated impacts identified are of small dimension and of less negativity to the community and the environment. All impacts can be mitigated through available engineering practices.







Our conclusion is that implementation of the proposed construction of Public toilet at Mlonganzila Mtaa, Kwembe Ward in Ubungo Municipality will not entail detrimental impacts provided that the recommended mitigation measures are adequately and timely put in place. The identified adverse impacts shall be managed through the proposed mitigation measures and implementation regime laid down in this EIS. DAWASA is committed to implementing all the recommendations given in the EIS and further carrying out the environmental auditing and monitoring schedules.

It is, therefore, recommended that the developer can be provided with the environmental certificate in order to commence the implementation of the project.

Appendix I: List of Stakeholders Consulted


**ENVIRONMENTAL AND SOCIAL IMPACT ASSESSMENT FOR CONSTRUCTION OF OFF GRID SANITATION PROJECTS,
DAR ES SALAAM**

LIST OF STAKEHOLDERS CONSULTED

| SN | DATE/TAREHE | NAME/JINA | INSTITUTION/TAASISI | POSITION/CHEO | PHONE NO./SIMU | SIGNATURE/SAINI |
|----|-------------|-------------------|---------------------|---------------|----------------|---|
| 1 | 21/7/2020 | MATHIAS UWETEWA | UMC | Ag ME | 0714 662078 |  |
| 2 | 21/07/2020 | Mica Vekungu | UMC | Ag MESA | 0913 945430 |  |
| 3 | 21/07/2020 | LEAH SIWAU | UMC | MEHUMU | 071 3 4255 25 |  |
| 4 | 21/7/2020 | Noni A. Nyau | UMC | Architect | 0714419709 |  |
| 5 | 22/7/2020 | ROBERT AMARI | WEDJARA | ME N B | 0654496192 |  |
| 6 | 23/07/2020 | CHANDA G. MAMBAKA | WEDJARA | WED | 0713396995 |  |

ENVIRONMENTAL AND SOCIAL IMPACT ASSESSMENT FOR CONSTRUCTION OF OFF GRID SANITATION PROJECTS,
DAR ES SALAAM

LIST OF STAKEHOLDERS CONSULTED

| SN | DATE/TAREHE | NAME/JINA | INSTITUTION/TAASISI | POSITION/CHEO | PHONE NO./SIMU | SIGNATURE/SAINI |
|----|-------------|-------------------|---------------------------|---------------|----------------|---|
| | 23/07/2020 | JAHARIY MAYANGA | MMA-MATANATIMI | MTENDAJI | 0715-395350 |  |
| | 23.07.2020 | MASUDI M. MKWANGA | S/MSIWA MLEWE | M/MKUU | 0754-991385 |  |
| | 23-07-2020 | BERNARD T. NKUUBE | S/MSINGI MLEWE | MTENDAJI | 4713966970 |  |
| | 23/07/2020 | BUSIMWA R. SWOT | S/M. UKOMBOZI | M/MKUU | 0716 665870 |  |
| | 23/07/2020 | DIBNO JUNA | AFISA AFYA KATA-MANZEE | A/AFYA | 0692 547547 |  |
| | 23/07/2020 | MASHAHI ZUBIRI | AFISA AFYA KATA-MANZEE | AJ-KATA | 0743-557283 |  |

Appendix II: Minutes of local community consultation

MAJLIS YA BTHARI KWA MAZINGIRA NA
UHAWANASHAJI KWA JARUI KUTUWA MPANGO WA
KIAKAZI KIBADALA NA FIDIA ZITOKANAZO WA
KIRADI WA UJENZI WA MUNDOMBINU YA UCHAKA-
TAJI MAJI TAKA NA VYOTO YA UMMA ALKOH WA
DAR ES SALAAM. KITUO CHA JIADALA MLOGANZILA

AGENDA 23/07/2020

1. KUTUNGUWA KIKAO
2. MAELEZE KUTUWA KIRADI WA UJENZI WA CHAO
3. MASWALI / MAFONI KUTOKA KWA MADALI
4. KUATHIRIWA KIKAO

1. KUTUNGUWA KIKAO
Kikao kilifunguliwa na Mwenyekiti wa kikao ndugu Hamed Jabalu mnamo muda wa saa 4:00 asubuhi na kuwatambulisha wataalamu kutoka Kampuni ya Royal Associate Engineering JV G-PEE LTD wakiwa wameambalana na Mwekezaji wa Dawasa.

Baada ya utambulisho huo Mwenyekiti aliwa-
karibisha wataalamu kutoka Maelezo ya mudi.

2. MAELEZO KUTUWA KIRADI WA UJENZI WA CHAO
Mtaalamu ndugu Emmanuel Rajab alisimama na kueleza kuwa kutakuwa na ujenzi wa chao ambacho kitachukua ukubwa wa 20 kwa 20 la eneo. Chao hiki ni chao cha umma na hi chao cha kulipia, chao hiki kitatumiwa

na watu wote wanaume na wanawake, chao hiki kitasaidia kupunguza Magonjwa hasa ugonjwa wa Kipindupindu. Hivyo kabika kufanya tatuhini ya Mazingira na jamii tunapenda kusikia Maoni yenu na Maswali ili kuweza kufanya mradi uwe rafiki kwa jamii pia kutakuwa na chao cha wale mavu.

3. MASWALI (MAONI KUTOKA KWA WADAU)

Ahna Malki - Wafanyabiashara wa hapa hataja pata taarifa kuhusu kwenda kuhamia stendi pale

Jennifer Josephat - Je chao kitakachujengwa ni chao chakulipia?

Mtaalamu alijibu mradi ukikamilika tunakabidhi chao kwa watu wa Manispaa ila chao ni cha kulipia.

Jennifer Josephat - Alipendekera bei ya chao iwe mia tano.

Martha Kambalage - Je wafanyabiashara wanaweza kusimamia pia hiko chao.

Lewisa Juma - Aliomba kuwa na gharama mbili kofauti kuoga iwe mia tano na kujisaidia hayandiga iwe mia mbili.

Wadaw waliomba wale wafanyabiashara wa pale pale wapewe kadi ambayo itakuwa na picha ili mtu akitoa mia tano iwe siko nzima anapata huduma ya chao kwa wafanyabiashara wa pale pale

Nora Josephat - Alisema kuna waku hawana uwazi
na mtatano naomba misingatio hili

Mattha kambalage - Alionba bei uwe moja ya
Kujisaidia haja ndogo na haja kubwa.

Ndau alionba kama kadi ilapitishwa alionba hiyo
kadi ilipwe kwa mwenzi.

4. KUAHIRISHA KIKAO

Kikao kilialirishwa mnamo muda wa saa
4.30 asubuhi

Sahibu ya Mwenyekiti

Sahihi

HAMEDI JALALI
0656 6012778



Sahibu ya Mfundaji

Sahihi

FUZABETH A. MWAHOB
0715 722974

TATHIMINI YA ATHARI KWA MAZINGIRA NA JAMII NA UHAMASISHAJI KWA JAMII KUHUSU MPANGO WA MAKAZI MIBADALA NA FIDIA ZITOKANAZO NA MRADI WA UENZI WA MIUNDOMBINU YA UCHAKATAJI MAJI TAKA NA VYOO VYA UMMA MIKOA WA

DAR ES SALAAM

MAHUDHURIO KWA AJILI YA MIKUTANO, MAJADILIANO

MWIKAZAJI: DAWASA

MISHAURI: ROYAL ASSOCIATES ENGINEERING IV G-PES LTD

WILAYA: Mloganzila

KATA: Kwenye

MTAA: Mloganzila

TAREHE: 27/07/2020




| S/N | JINA | WADHIFA | NAMBA YA SIMU | SAMHI |
|-----|---------------------|-----------------|---------------|---------|
| 1 | Hamed Di Jama | Mwanenyezi Mtaa | 0656 401378 | D. R. |
| 2 | Rainabwa R. Zabwa | M/ochu | 0654 705496 | H. R. |
| 3 | M/ochu Zabwa | M/ochu | - | J. Alby |
| 4 | JASMIN ALY | - | 0655 081484 | M/ochu |
| 5 | GRACE SANGA | - | 0714 648925 | M/ochu |
| 6 | MARY CLEMENCE | - | - | M/ochu |
| 7 | ROSE CHARLES | - | - | M/ochu |
| 8 | ELIZABETH JOHN | - | 0713 252142 | M/ochu |
| 9 | PENDO JULIUS | - | 0699 524121 | M/ochu |
| 10 | ZUWENA JUMIA | - | 0715 599662 | M/ochu |
| 11 | KIDAWA KIGODI | - | 0688 279710 | M/ochu |
| 12 | VISCU NGURUBU | - | 0627 404091 | M/ochu |
| 13 | SOLOMON MANGAT | - | 0673 872860 | M/ochu |
| 14 | SENIFA SHAYO | - | 0713 243262 | M/ochu |
| 15 | ALIEA SAFARI | - | 0710 993666 | M/ochu |
| 16 | MUSINA MARIYA | - | 0716 484489 | M/ochu |
| 17 | HAMINU JUMIA | - | 0656 140760 | M/ochu |
| 18 | ASLARIA # KANIKI | - | 0784 - 735327 | M/ochu |
| 19 | KUSI R. MUMUKUTISHA | - | 0719 - 031826 | M/ochu |
| 20 | Scrabby Manda | - | 0719 - 501451 | M/ochu |
| 21 | MIRIAM JOHN MUMU | - | 0652 140805 | M/ochu |
| 22 | GENUS MATHEN | - | 0659 866670 | M/ochu |
| 23 | | - | 0718 402200 | M/ochu |
| | | - | 0716 - 632280 | M/ochu |

Appendix III: Screening Letter from NEMC

Appendix IV: Permit to use the Open Space for construction of Public Toilet

HALMASHAURI YA MANISPAA YA UBUNGO
BARUA ZOTE ZITUMWE KWA MKURUGENZI WA MANISPAA

Siku N°: 022296341
Barua pepe: ubungo@ubungo.go.tz
Tovuti: www.ubungo.go.tz
Urapojibu tafadhali taja:
Kumb. N°: AB.7/300/01/08



S.L.P. 55068, DAR ES SALAAM
Tarehe: 17/06/2020

ATISA MTENDAJI MKUU,
MAMLAKA YA MAJI SAFI NA MAJI TAKA (DAWASA),
S.L.P. 1573,
DAR ES SALAAM.

YAH: UTEKELEZAJI WA MIRADI YA MAJI SAFI WA MAZINGIRA INAYOFADHILI NA BENKI YA DUNJA
Somo: Uthibitisho wa maeneo ya Ujenzi wa Miradi


Husika na somo tajwa hapo
Tafadhali rejea barua yako ya tarehe 9/06/2020 na kupokelewa tarehe 10/06/2020 yenye kumb. N° DAWASA/DoC/004/Vol.12, inayohusu utafutezaji wa miradi tajwa hapo juu.

Nalini kuwa maeneo yaliyovainishwa yanamilikiwa na Manispaa ya Ubungo hii pokuwa kwa maeneo mawili (tumewaandikia barua ya kuamiba kuyatumia) kama ilivyovainishwa kwenye jedwali lililoambataniwa.

Aidha kwa eneo la kuchakata maji taka la Kisapiwa tunawaomba mifanyike usafi **(Site clearances of bushes and the likes)** ili tupime kponde kulingana na mahitaji yanayotakiwa.

Tunaoomba zoezi la usanifu na fathimini ya athari za mazingira lifanyike kwa haraka iwezakanavyo ili huduma tarajiwa zikwanuwashie wananchi.

Tunafanguliza shukurani


Happy Mbele
KAIMU MKURUGENZI WA MANISPAA
HALMASHAURI YA MANISPAA YA UBUNGO

Project Brief of the Proposed Public Toilet at Mloganzila Bus Stand

| MAENEO YALIYOPENDEKEZWA KWA AJILI YA UJENZI WA MIRADI YA UCHAKATAJI MAJI TAKA | | | | |
|---|---|----------------------|--|--|
| Eneo Pendekwezwa | Aina ya Mradi | Ukubwa wa eneo | Mareleo | Miliki wa Eneo |
| 1 Kisopwa | Ujenzi wa mradi wa kuchakata maji taka wenye uwezo wa kuchakata lita 100,000 kwa siku | 25,000m ² | Eneo hili limependekwezwa na Manispaa ya Ubungu na tathmini ya awali ya DAWASA inaonesha kuwa inafaa kwa ajili ya ukolelezaji wa mradi tajwa | UMC-Tunathibitisha kwa matumizi yaliyopendekwezwa inahitaji kusafishwa ili majaka iainishwe vizuri |
| 2 Samaga/Mavurunza (Primary School) | Ujenzi wa mradi wa kuchakata maji taka wenye uwezo wa kuchakata lita 50,000 kwa siku | 10,000m ² | Eneo hili limependekwezwa na Manispaa ya Ubungu na tathmini ya awali ya DAWASA inaonesha kuwa inafaa kwa ajili ya ukolelezaji wa mradi tajwa | UMC-Tunathibitisha kwa matumizi yaliyopendekwezwa |
| 3 Ujenzi wa mradi wa kuchakataji maji taka | Ujenzi wa mradi wa kuchakata maji taka wenye uwezo wa kuchakata lita 50,000 kwa siku | 15,000m ² | Eneo hili bado halijapendekezwa DAWASA inaomba Manispaa ikamilishe zoezi ili upatikanaji wa eneo hili | UMC- bado inafanya jitahidi za kupata eneo jingine |
| 4 Manzese (Mkombozi Primary School) | Ujenzi wa mradi wa kuchakata maji taka wenye uwezo wa kuchakata lita 50,000 kwa siku | 10,000m ² | Eneo hili limependekwezwa na Manispaa ya Ubungu na tathmini ya awali ya DAWASA inaonesha kuwa inafaa kwa ajili ya ukolelezaji wa mradi tajwa | UMC-Tunathibitisha kwa matumizi yaliyopendekwezwa |
| Miradi ya Ujenzi wa vyoo vya umma | | | | |
| 1 Kituo cha Daladala Mloganzila | Choo cha umma | 400m ² | Eneo hili limependekwezwa na Manispaa ya Ubungu na tathmini ya awali ya DAWASA inaonesha kuwa inafaa kwa ajili ya ukolelezaji wa mradi tajwa | UMC-Tunathibitisha kwa matumizi yaliyopendekwezwa |
| 2 Soko jipya Mbezi Luis | Choo cha umma | 400m ² | Eneo hili limependekwezwa na Manispaa ya Ubungu na tathmini ya awali ya DAWASA inaonesha kuwa inafaa kwa ajili ya ukolelezaji wa mradi tajwa | UMC-Tunathibitisha kwa matumizi yaliyopendekwezwa |

Project Brief of the Proposed Public Toilet at Mloganzila Bus Stand

| Eneo Pendekewa | Aina ya Mtradi | Ukubwa wa eneo | Maelezo | Mmiliki wa Eneo |
|--------------------------------|----------------|-------------------|--|---|
| 3 Soko la Shikilango | Choo cha umma | 400m ² | Eneo hili limependekwa na Mwanasa ya Ubungo na tathmini ya awali ya DAWASA inaonesha kuwa inafaa kwa ajili ya ukolelezaji wa mtradi tajwa | UMC-Tunathibitisha kwa matumizi yaliyopendekwa kulingana na ufryu wa eneo tunashauri usamfu wa vyoo katika eneo hili utanywe mabadiliko ya akubwa ili kuweza kuwapa wianchi huduma hi |
| 4 Soko la Siza Makubuni | Choo cha umma | 400m ² | Eneo hili limependekwa na Mwanasa ya Ubungo na tathmini ya awali ya DAWASA inaonesha kuwa inafaa kwa ajili ya ukolelezaji wa mtradi tajwa | UMC-Tunathibitisha kwa matumizi yaliyopendekwa kulingana na ufryu wa eneo tunashauri usamfu wa vyoo katika eneo hili utanywe mabadiliko ya akubwa ili kuweza kuwapa wianchi huduma hi |
| 5 Soko la Matizese | Choo cha umma | 400m ² | Eneo hili limependekwa na Mwanasa ya Ubungo na tathmini ya awali ya DAWASA inaonesha kuwa inafaa kwa ajili ya ukolelezaji wa mtradi tajwa | UMC-Tunathibitisha kwa matumizi yaliyopendekwa |
| 6 Klabu cha teni Mwananchi | Choo cha umma | 400m ² | Eneo hili limependekwa na Mwanasa ya Ubungo na tathmini ya awali ya DAWASA inaonesha kuwa inafaa kwa ajili ya ukolelezaji wa mtradi tajwa | TRC/UMC- tunathibitisha kufanika upakanaji wa eneo kutoka TRC |
| 7 Mabito Hostet EPZA | Choo cha umma | 400m ² | Eneo hili limependekwa na Mwanasa ya Ubungo na tathmini ya awali ya DAWASA inaonesha kuwa inafaa kwa ajili ya ukolelezaji wa mtradi tajwa | EPZA/UMC- tunathibitisha kufanika upakanaji wa eneo kutoka EPZA |
| 8 Hifaa cha Daladala Simu 2000 | Choo cha umma | 400m ² | Eneo hili limependekwa na Mwanasa ya Ubungo ina hitaji kufanywa tathmini ya awali na DAWASA kuona kama inafaa kwa ajili ya ukolelezaji wa mtradi tajwa | UMC-Tunathibitisha kwa matumizi yaliyopendekwa |

**Appendix V: Memorandum of Understanding between DAWASA and Dar
es Salaam Municipal Councils**



MEMORANDUM OF UNDERSTANDING
BETWEEN
MINISTRY OF WATER
AND
THE DAR ES SALAAM WATER SUPPLY AND
SEWERAGE AUTHORITY,
REGIONAL ADMINISTRATIVE SECRETARIAT
AND
DAR ES SALAAM MUNICIPAL COUNCILS
(Kinondoni, Ilala, Temeke, Ubungo, Kigamboni)

JANUARY 2019

ACRONYMS

| | |
|----------------|---|
| BC | Beneficiary Community |
| CEO | Chief Executive Officer |
| CPM | Critical Path Method |
| CV | Curriculum Vitae |
| DAWASA | Dar es Salaam Water and Sewerage Authority |
| DDCA | Drilling and Dam Construction Agency |
| DEWATS | Decentralized Wastewater Treatment System |
| DSM | Dar es Salaam |
| EMP | Environmental Management Plan |
| ESA | Environmental and Social Assessment |
| ESIA | Environmental and Social Impact Assessment |
| ESMP | Environmental and Social Management Plan |
| EWURA | Energy and Water Utilities Regulatory Authority |
| FDR | Final Design Report |
| FSM | Feacal Sludge Management |
| GIS | Geographic Information System |
| GoT | Government of the United Republic of Tanzania |
| H&S | Health and Safety |
| ICB | International Competitive Bidding |
| IFRs | Interim Financial Report |
| LGAs | Local Government Authorities |
| m ³ | Cubic meter = 1,000 litres |
| MD | Managing Director |
| MKUKUTA | National Strategy for Growth and Reduction of Poverty |
| MoEVT | Ministry of Education and Vocational Training |
| MoHCDEC | Ministry of Health, Community Development, Gender, Elderly and Children |
| MoU | Memorandum of Understanding |
| MoW | Ministry of Water |
| NCB | National Competitive Bidding |
| NEMC | National Environment Management Council |

| | |
|---------|--|
| NGO | Non-Governmental Organization |
| NWSDS | National Water Sector Development Strategy |
| O&M | Operations and Maintenance |
| PAP | Projected Affected Person |
| PERT | Program Evaluation Review Technique |
| PIM | Project Implementation Manual |
| PIP | Program Implementation Plan |
| PO | Private Operators |
| PO-RALG | Presidents Office Regional Administration and Local Government |
| PPRA | Public Procurement Regulatory Authority |
| RAP | Resettlement Action Plan |
| RAS | Regional Administrative Secretary |
| RS | Regional Secretariat |
| RFP | Request for Proposals |
| SDG | Sustainable Development Goal |
| SPS | Small Piped Water Supply |
| TBS | Tanzania Bureau of Standards |
| ToR | Terms of Reference |
| UWSA | Urban Water and Sewerage Authority |
| WC | Water Committee |
| WSDP | Water Sector Development Program |
| WSS | Water Supply and Sanitation. |
| WSSP | Water Sector Development Program |
| WSSPII | Second Water Sector Support Project |

**A MEMORANDUM OF UNDERSTANDING
FOR THE IMPLEMENTATION OF THE OFF- GRID WATER SUPPLY AND
SANITATION PROJECTS UNDER THE SECOND WATER SUPPLY AND
SANITATION PROJECT USING EARMARKED FINANCING**

Memorandum of Understanding (“MoU”) between the Ministry of Water on one part and the Dar es Salaam Water Supply and Sewerage Authority (“DAWASA”), the Dar es Salaam Regional Secretariat (RS), and the five municipalities of Dar es Salaam (collectively referred to as “the MUNICIPALITIES”) on the other part.

WHEREAS in recognition of the importance and contribution of the water sector to the social and economic development of the United Republic of Tanzania, the Government has developed a water sector support framework set out in the following documentation: (a) the National Strategy for Growth and Reduction of Poverty (“MKUKUTA, as amended”), (b) the National Water Sector Development Strategy (“NWSDS”) and (c) the Water Sector Development Program (“WSSP”).

WHEREAS after being satisfied with the objectives of the WSSP II, parties to this Memorandum have expressed their willingness to participate fully in its implementation;

WHEREAS The WSSPII project development objective is to strengthen the capacity for the integrated water resources planning and management in the United Republic of Tanzania and improve access to water supply and sanitation services in an operationally efficient manner in Dar es Salaam. The project has four components namely: Integrated Water Resources Management, Dar es Salaam Water Supply improvement, Dar es Salaam Sanitation Improvement, and Project Management and Implementation support.

WHEREAS the project is being financed by IDA Credit through Investment Project Financing, the recipient has declared its commitment to the objectives of the Project.

WHEREAS on the other part DAWASA has committed itself to the principle of harmonization and strive for the highest degree of alignment with the Government’s budgetary and accountability systems and local financial framework so as to enhance effective implementation, reduce the administrative burden on the Government, and minimize transaction costs; and

NOW THEREFORE, the parties hereby agree to cooperate in coordinating the implementation of the off-grid water supply and sanitation part of WSSP II in accordance with the principles and procedures set forth in this MoU; provided, however, that in case of any conflict between the provisions of this MoU AND THE PROJECT Financing Agreement, the provisions of the Financing Agreement shall prevail.

1. DEFINITIONS

Unless the context otherwise requires, several terms defined in the Preamble of this MoU have the respective meanings set forth therein, and the additional terms referred to below have the following meanings:

1. **Off Grid water supply** means the activities which will provide water supply services to people of Dar es Salaam, who are not connected to the formal network. The proposed solutions include decentralized Interventions, which may be an interim measure to be integrated to the grid network as it expands in the future. Schemes to be implemented include mostly independent water supply distribution systems supplied from point sources (e.g boreholes) or a bulk water supply from the DAWASA distribution system. In areas where the existing grid network is not available, independent stand-alone Small Piped Water Supply (SPS) systems will be implemented. These projects, typically involve a source of water (for example, borehole), a community-based distribution system and water points at a community and/or household level. The operations and maintenance will be supported from the tariff collected from the users.
2. **Off-Grid Sanitation** means activities which will provide sanitation services in Dar es Salaam to areas without access to sewers. This activity will support installation of improved toilets; safe emptying and transportation of the waste to a treatment facility; and treatment and safe disposal of treated waste into the environment. This will include piloting decentralized systems and other new technology.
3. **Environmental and Social Management Framework or ESMF** means the framework dated September 2006, prepared by the Government and cleared by the International Development Association, setting forth an environmental and social screening process that will enable WSSP II Implementing Agencies to identify and assess potential adverse environmental and social impacts, and offset and reduce them to acceptable levels, or enhance positive impacts, and in accordance with which environmental and social management plans will be prepared by WSSP II Implementing Agencies.
4. **MKUKUTA II** Means the Government's National Strategy for Growth and Reduction of Poverty dated July 2010, covering the period from 2011 – 12 to 2016 – 17 and subsequent versions that may be introduced by GOT.
5. **Resettlement Policy Framework** or RPF means the governing framework dated September 2006, prepared by the Government and approved by the International Development Association, for land acquisition, resettlement and compensation under the WSDP, and in accordance with which resettlement action plans will be prepared,

as necessary, as the same may be amended from time to time with the concurrence of the International Development Association;

6. **WSSP Implementation Manual** means the Project Implementation Manual (PIM) specifying implementation arrangements for the Second WSSP, including institutional arrangements; procedures for procurement, disbursement of funds, financial management, environmental and social management, and monitoring and evaluation; and progress reporting requirements, including annexes to the said manual.
7. **Project Management Team** means a team set up by DAWASA for day to day management of the off-grid water supply sub-project. Same for management of off-grid sanitation sub-project.
8. **Facilitation Team** A team appointed by the Municipal Director of the respective Municipal Council from Dar es Salaam region for the purpose of facilitating the implementation of the Off-Grid water supply projects and Off- Grid Sanitation projects. The scope of their responsibility are detailed in the PIM and summarized in this MoU.

2. UNDERLYING PRINCIPLES

2.1 The MoW, DAWASA, RS and Municipalities agree that the following are the underlying principles that govern this partnership:

- (a.) Commitment to the fulfilment of the aspirations of the National Development Vision 2025;
- (b.) Compliance with defined budgeting, procurement and public financial management rules and regulations;
- (c.) Good governance and accountability of the Government to its citizens, including an active fight against corruption;
- (d.) Coordinating the implementation of the off-grid water supply and sanitation sub-projects cost effectively; and
- (e.) Each party executing its respective roles in a timely manner

3. GENERAL PROVISIONS

3.1 Purpose

This MoU outlines the responsibilities of the **MoW, DAWASA, RS and Municipalities** with respect to the implementation of off-grid water supply and sanitation sub-projects and sets forth common institutional, environmental and social measures, monitoring and evaluation, audit and reporting arrangements. The WSSP II Implementation Manual complements procedures and arrangements set out in this MoU.

3.2 **Status of the MoU**

This MoU is not intended to create any legally binding obligations and the parties take due cognizance of the separate sector laws and regulations between the Government Institutions, and this MoU is adopted pursuant to and subject to any such regulations. In case of any conflict between the provisions of this MoU and the project Financing Agreement, the provisions of the Financing Agreement shall prevail.

4. **OFF GRID WATER SUPPLY**

4.1. **Commitment**

The DAWASA declares its commitment to the objectives of the **Second Water Sector Support Project** and will act with due diligence and efficiency to facilitate the successful implementation of the projects. To this end, DAWASA, as an Implementing Agency will effectively carry out its roles and responsibilities in the implementation of the off-grid water supply and sanitation sub-projects as defined in the WSSP II Project Implementation Manual. The Ministry of Water, as the Responsible Agency for WSSP II will have overall responsibility for the coordination and implementation of the off-grid water supply and sanitation sub-projects.

4.2 **Institutional Arrangements**

The institutional framework for overseeing the implementation of the WSSP II comprises the following key bodies, as set out in the Sections below, and in greater detail in the WSSP Implementation Manual:

1. Ministry of Water;
2. Prime Minister's Office Regional Administration and Local Government;
3. Ministry of Health, Community Development, Gender, Elderly and Children
4. Municipal Councils
5. Beneficiary Communities ("BC");

4.2.1 **Ministry of Water (MoW)**

The MoW will be responsible for provision of overall coordination and oversight. The Ministry will also provide technical and administrative support in the implementation of WSSP II, including without limitation the following activities:

1. Coordinating and consolidating the quarterly WSSP II IFRs (Interim Financial Report); semi-annual and annual progress reports; and ensuring that funds earmarked for implementation of WSSP II activities are duly considered in the annual work plans

and budgets of the implementing agencies; and that the WSSP II procurement plans are consistent with WSSP II work plans and budgets;

2. Ensuring quality and consistency of the documents referred to in subparagraph (a) above prior to consolidation as indicated in the Programme Implementation Manual and submission to the Off-Grid WSS SC for discussion;
3. Monitoring the implementation of the Annual Work Plans and Budgets by the WSSP II Implementing Agencies, at least on quarterly basis;
4. Providing oversight on financial management, controls, audit and reports; and
5. Ensuring that management decisions made by the Off-Grid WSS Steering Committee are communicated to the Implementing Agencies, implemented and monitored.

4.2.2 DAWASA

DAWASA will be responsible for overall coordination and implementation of off grid water supply activities. The off-grid water supply shall be implemented under the Directorate of Infrastructure Development (for construction arrangements) in collaboration with the Communication Unit (for coordination arrangements). The Communication Unit will be generally responsible for:-

1. Coordinating inputs as required from other units within DAWASA such as Procurement, Technical Services, and Finance, etc.
2. Supervising and monitoring contracts / agreements
3. Setting up Sub-project Agreements with beneficiary communities
4. Monitoring and reporting overall progress of the off-grid water supply sub-component.
5. Reviewing and evaluating the operation and management of the water supply sub-projects.
6. The financial aspects for off- grid water supply sub-projects will be managed as per Project Implementation Manual VOLUME II, and
7. Overall supervision of off-grid water supply activities.

4.2.3 Municipal Councils (or DLGAs)

The five Dar es Salaam Municipal Councils, through their respective Urban Planning Department, Legal Unit, Municipal Health and Water Department, will be responsible for the following tasks:

1. Creating awareness and mobilization of the communities.

2. Each DLGA will form a Municipal Facilitation Team comprising different specialists from Water, Health, Education, Community Development departments that will be tasked to assist consultants/contractors/PO on implementation and operation of Off Grid Water Supply facilities in their respective areas.
3. DLGAs through Legal unit, Health and Water department will coordinate the formation of Water Supply by-laws and regulations and thereafter enforcing for sustainability of Off Grid Water Supply facilities.
4. DLGAs will be responsible for identification and facilitation of Land acquisition for construction of Off- Grid Water Supply facilities

4.2.4 WSS Steering Committee

Given the multiplicity of institutions with varying roles, a WSS Steering Committee (SC) will be set up under the project to ensure coordination, synergy, and dovetailing. This SC will be newly set up or be adopted from some of the other projects (for example, Dar es Salaam Metropolitan Development Program [DMDP]) which may have similar steering mechanisms. This steering committee will be chaired by the Head of the Water Sector from RS and DAWASA will provide the secretary to WSS SC.

The RS will chair the Off Grid WSS Steering Committee, which will be comprised of representatives from the DAWASA, RS, WRBO, MOW, DLGAs i.e Temeke, Ilala, Kinondoni, Kigamboni and Ubungo. The Steering Committee will be responsible for providing general oversight of the selection and approval of sub-projects for implementation by the Off-Grid Water Supply and Sanitation. The key responsibilities of the Off Grid WSS Steering Committee include:

1. Reviewing overall Off Grid Sanitation implementation arrangements
2. Reviewing and approving Off Grid Sanitation sub-project operational guidelines
3. Reviewing and approving Off Grid Sanitation sub-project proposals
4. Reviewing overall Off Grid Sanitation progress and performance and providing guidance for improvements if needed
5. Conflict Resolution as per PIM.

4.2.5 Beneficiary Community

At the project level, Beneficiary Community will be involved in the project appraisal, that includes identification of sources, selection of appropriate sites, kiosk locations, and

protection of water source and infrastructures. DAWASA will be responsible for the efficient operation and management of the water supply systems.

4.2.6 Private Operator

The Private Operator (PO) may be engaged if the expansion of DAWASA grid network is beyond five years away. The PO would primarily have as its members the households from the community, with an operating body selected by the members from among themselves, with additional membership from DAWASA/DLGA. The regulation of these systems, including the tariff, would be undertaken by EWURA, as part of the overall regulation of the sector in Dar es Salaam.

Private Operator will operate, maintain, and manage the scheme under contract with DAWASA.

The Private Operator shall be responsible for keeping and maintaining appropriate records of its business activities. These shall include:

1. Customer details
2. Operation and maintenance records including volume of water produced and sold
3. Asset register, work as executed records, manuals of plant and equipment
4. Condition and expected life of assets
5. The details of network expansions as up to standards.
6. The Private Operator shall prepare monthly and quarterly operation and maintenance
7. Reports for the completed off-grid water supply subproject
8. Billing and payment records
9. Business accounts and financial statement

In general, the Operation and Maintenance Reports will address such issues as:

1. Number of registered customers in the service area
2. Number of people in the service area and number of people served
3. Business plan and budget
4. Level of service; proposed and actual
5. Revenue and expenses, progress against budget
6. Customer satisfaction
7. Maintenance activities, breakdowns, failures
8. Availability of ground /reliable water sources
9. Availability for land resources for project activities
10. Manage non-revenue water in the business area

4.3 SELECTION CRITERIA

DAWASA, in consultation with the five municipalities Ilala, Temeke, Kinondoni, Kigamboni and Ubungo will identify communities which are eligible for the Off-Grid Water Supply sub-project under the WSSP II. The identification will follow the criteria below;

1. High population density
2. Low-income areas
3. Prevalence/risk of waterborne diseases
4. No wholesome water services
5. Near-trunk infrastructure
6. Availability of sufficient land for the interventions
7. Unplanned settlements
8. Community willingness

Each of these criteria will be allocated a score, and the communities prioritized according to their total score. Keeping in mind the decisions of other interventions (for example, The Dar es salaam Metropolitan Development Program - DMDP), WSSP-II will invest in those communities which have the highest need.

5.0 OFF-GRID SANITATION

5.1 Definition.

The Off-Grid Sanitation components will provide much needed improvements to wastewater management services in areas of Dar es Salaam that are not served by DAWASA network. These improvements will be realised as a result of construction of Off-Grid sanitation stand-alone projects such as Decentralized Waste Water Treatment Systems (DEWATSs), faecal sludge treatment facilities, and condominial/simplified sewerage. The Off-Grid Sanitation Services will address the lack of sanitation services in unserved areas.

5.2 Institutional Arrangements

A strategy to address the poor sanitation in Dar es Salaam requires clarity and coordination among the various institutions involved in the sector. However, institutional responsibility is fragmented and unclear, being divided between National Ministries, City Utilities, Municipal Organizations, Regulatory Authorities, Community-Based Organizations, the Informal Private Sector and sanitation users themselves.

Currently sanitation service delivery is undertaken by a mixture of Utilities, Municipalities and Regulators. DAWASA will be responsible for overall coordination and supervision of Off-Grid sanitation activities. Other institution as detailed in PIM are summarised below:

1. MoHCDGEC,
2. MoW,
3. RS,
4. DLGAs,
5. NGOs,
6. PO

5.2.1 Ministry of Water

Ministry of Water will be responsible with setting Policy and guidelines specific to FSM and overall project coordination and implementation support .

5.2.2 DAWASA

DAWASA will provide a foundation and resources for the overall implementation of Off-Grid Sanitation.

Directorate of Infrastructure Development will be the department within DAWASA responsible for overseeing the implementation of the WSSP II including Off-Grid Sanitation Sub component. The head of this department will report directly to the DAWASA Chief Executive Officer and will generally be responsible for:

1. Coordination of the Off-Grid Sanitation Steering Committee as well as establishing a general agenda and timetable for Steering Committee meetings with consultation with Steering Committee Chairperson and providing secretariat services.
2. Coordinating inputs as required from other Directorates within DAWASA such as Procurement, Infrastructure Development, and Finance, etc.
3. Signing, supervising and monitoring contracts / agreements
4. Setting up Sub-project Agreements with successful communities.
5. Monitoring and reporting overall progress of the Off-Grid Sanitation
6. Reviewing and evaluating the operation and management of the community sanitation schemes.

In support of Sub Component 3.2: a Sanitation coordination team led by PO-RALG - Regional Secretariat will be established to coordinate implementation of the Off- Grid sanitation services. The technical department in the municipalities in coordination with DAWASA will be responsible for implementation of the off-grid sanitation component. DLGAs through Health, Legal unit and Water departments will coordinate the formation or improvement of existing Sanitation by laws and regulations and thereafter enforcing them for the sustainability of Off Grid Sanitation facilities. Areas where these facilities will be built people will be required to connect. DLGAs will be responsible for identification and facilitation of Land acquisition for construction of Off- Grid Sanitation facilities, and management of Public toilets.

5.2.3 MoHCDGEC/MoW:
Policy and guidelines specific to FSM.

5.2.4 DLGAS under Regional Secretariat:

Roles and responsibilities of the DLGAs will include:

1. Creating awareness and mobilization of the community
2. Formulation of Municipal Facilitation Team comprised of specialists from Water, Health, Education, Community Development departments that will be tasked to assist consultants/Contractors/PO on implementation and operation of Off Grid Sanitation facilities
3. Coordination of the formation of Sanitation by-laws and regulations and thereafter enforcing them for sustainability of Off Grid Sanitation facilities through Legal unit, Health and Water Department
4. Identification and facilitation of land acquisition for construction of Off- Grid Sanitation facilities
5. Establish and capacitate the grievance redress mechanism (GRM) team
6. Monitor and evaluate project implementation, trouble shooting and responding to grievances raised by Grievance Redress Mechanisms (GRM) teams
7. Prepare and submit to WSS SC a monthly project implementation progress report

5.2.5 WSS Steering Committee

Given the multiplicity of institutions with varying roles, a WSS Steering Committee (SC) will be set up under the project to ensure coordination, synergy, and dovetailing. This SC will be newly set up or be adopted from some of the other projects (for example, Dar es Salaam Metropolitan Development Program [DMDP]) which may have similar steering mechanisms. This steering committee will be chaired by the Head of the Water Sector from RS and DAWASA will provide the secretary to WSS SC.

The RS will chair the Off Grid WSS Steering Committee, which will be comprised of representatives from the DAWASA, RS, WRBO, MOW, DLGAs i.e Temeke, Ilala, Kinondoni, Kigamboni and Ubungo. The Steering Committee will be responsible for providing general oversight of the selection and approval of sub-projects for implementation by the Off-Grid Water Supply and Sanitation. The key responsibilities of the Off Grid WSS Steering Committee include:

1. Reviewing overall Off Grid Sanitation implementation arrangements
2. Reviewing and approving Off Grid Sanitation sub-project operational guidelines
3. Reviewing and approving Off Grid Sanitation sub-project proposals

4. Reviewing overall Off Grid Sanitation progress and performance and providing guidance for improvements if needed
5. Conflict Resolution as per PIM.

5.2.6 Private Operator (PO):

The domestic private sector will be a major institution which will require to be involved for sanitation in low-income settlements. Their involvement will include approaches to empty faecal sludge from latrine pits and septic tanks. This could be through vacuum trucks, or in areas where access is difficult, small 'gulper' technologies.

Private Operator will form the basic unit for planning and eventually operating and managing the community-based sanitation schemes implemented under the off-grid sanitation. Off-grid sanitation POs, will be responsible for:

1. Possession of necessary registration as per requirements.
2. Undertaking training and development in operations and maintenance, financial management, monitoring and reporting.
3. Operating and maintaining the off-grid sanitation Scheme in a sustainable manner and providing equitable access to the service for everyone in the community
4. Maintaining adequate records and reporting on technical and financial performance to DLGAs and DAWASA.

5.2.7 NGOs/ Consultant:

NGO will be responsible for Capacity building, mobilization of community; media campaigns

DAWASA will contract with a reputable NGO active in the DAWASA service area as implementing agents for the off- grid Sanitation. The key roles of the off-grid sanitation NGO include:

1. Mobilising community groups to identify all sanitation needs and raising awareness within community groups about sanitation issues.
2. Assisting community members to obtain legal status if required and to set up the necessary bank accounts, for the community to qualify for funding from micro finance institution for toilet improvements.
3. Undertaking a needs analysis and preparing a subproject proposal design, budget, impact assessment, operational and maintenance of the sanitation facility
4. Preparing subproject proposals in association with the community members for consideration by the off-grid sanitation Steering Committee.
5. Sensitization and training of POs to operate, maintain, and manage off-grid sanitation systems.

6. Assisting DAWASA to develop suitable O&M guidelines/manuals and financial management guidelines for use by the POs in operating and managing the completed schemes.

5.3 SELECTION CRITERIA

DAWASA, in consultation with the five municipalities Ilala, Temeke, Kinondoni, Kigamboni and Ubungo will identify communities which are eligible for Off-Grid Sanitation sub-project under the WSSP II, in the eligible project area using the criteria mentioned in the PIM. The criteria will include the availability of land resources for the project activities as additional criteria.

Each of these criteria will be allocated a score, and the communities prioritized according to their total score. Keeping in mind the decisions of other interventions (for example, DMDP), WSSP-II will invest in those communities, which have the highest need.

The five municipalities will be the focal point for planning, prioritizing, and implementing the off-grid sanitation in their areas. A comprehensive master sanitation plan, based on empirical data and evidence, will form the basis for this planning and implementation.

The results of the ongoing efforts to map the city on the said indicators, will form the basis for the planning efforts by the stakeholders.

Summary of Institutional Roles for Sanitation Provision

| | |
|-----------------|--|
| MoH/MoW/PO-RALG | Policy and guidelines specific to FSM |
| MoW | Overall project coordination and implementation support |
| EWURA | Regulate performance of DAWASA |
| DAWASA | Facilitating the establishment and operation of treatment facilities (FSM and the like and facilitating the development of options for transportation and treatment of this waste, establishment and management of public toilets; regulating the services of transporters |
| Municipalities | Facilitating the upgrading of unimproved household toilets to improved ones and regulation of waste disposal; facilitating the availability of land for decentralized systems; provide licenses to private transport operators |
| Private sector | Development of infrastructure for transportation and treatment, operation |
| NGOs | Capacity building, mobilization of community; media campaigns |

| | |
|------|---|
| TBS | Setting up of standards for effluent disposal |
| NEMC | Regulation of disposal of effluent |

6.0 EFFECTIVENESS AND DURATION OF MoU

- 6.1. This MoU will become effective on the date of signature by all parties.
- 6.2. This MoU shall remain in force until end Closure of the Second WSSP, or as shall be mutually agreed by the parties hereto.

7.0 AMENDMENTS

This MoU may be amended at any time with the written agreement of the parties hereto.

8.0 CONFLICT RESOLUTION

In the event of any differences arising with respect to the provisions of this MoU, the parties will endeavour to find a solution through dialogue and consultation.

9.0 INFORMATION AND NOTICES

- 9.1. The parties to this MoU will furnish to each other all such information in relation to the WSSP II as will be reasonably requested in a timely manner.
- 9.2. Any notices or documents given, made or sent by the parties in relation to this MoU will be in writing and will be deemed to have been duly given, made or sent to the organization or person to which it is addressed at the time of its delivery by hand, mail, or courier at its respective address, as listed in this MoU.
- 9.3. Any party hereto may, by written notice to the other parties, change the address to which any notice or request for the Participant so giving such notice will be addressed.
- 9.4. All communications and documents submitted to any party and by any part will be in the English language.
- 9.5. The following addresses are specified for purposes of Section 16.2.

9.6 FOR THE PARTIES

Permanent Secretary

Ministry of Water

Address

Tel:

E-mail:

Chief Executive Officer

DAWASA

Address

Tel:

E-mail:

Region Administrative Secretary

Dar es Salaam Region

Address:

Tel:

E-mail:

Municipal Director

Temeke Municipal Council

Address:

Tel:

E-mail:

Municipal Director

Ilala Municipal Council

Address:

Tel:

E-mail:

Municipal Director

Kinondoni Municipal Council

Address:

Tel:

E-mail:

Municipal Director

Ubungo Municipal Council

Address:

Tel:

E-mail:

Municipal Director









Kigamboni Municipal Council

Address:


Tel:

E-mail:

Signed by the duly authorized representatives of the parties as hereunder:

| | |
|--|--|
| Permanent Secretary Ministry of Water |  |
| | Date 18/2/2019 |
| Regional Administrative Secretary Dar es Salaam |  |
| | Date 12/2/2019 |
| CEO DAWASA |  |
| | Date 23.01.2019 |
| Municipal Director Temeke |  |
| | Date |
| Municipal Director Ilala |  |
| | Date 11/02/2019 |
| Municipal Director Ubungo |  |
| | Date 07/02/2019 |
| MD Kinondoni |  |
| | Date 07/02/2019 |
| Municipal Director Kigamboni |  |
| | Date 09/02/2019 |

Appendix VI: Architectural drawings




LEGEND

- Water Supply Elevated Storage Tank
- Water Supply Pipe
- Wastewater Chamber/Manhole
- Sinks
- Showers
- Toilets
- Wastewater/Drainage Pipe

| | | | | | | | | | |
|-------------|--|-------------|-------------|------------|---|-----------------|--|--|--|
| DESIGN BY | | SCALE | 1:50 | (REG. NO.) | PROVISION OF FACILITIES AND TECHNICAL SERVICES FOR CREATION OF SUSTAINABLE TRANSPORTATION, CAPACITY BUILDING, PREPARATION OF DETAILED ENGINEERING DESIGNS AND BIDDING DOCUMENT, AND CONSTRUCTION SUPERVISION OF THE OFF-GRADE SANITATION WORKS IN DHAIR SALAM | REVISION | | CLIENT | |
| DRAWN BY | | DATE | APRIL 2021 | TITLE | TYPICAL DRAWINGS FOR PUBLIC TOILET TYPE 3 FOR BUS STATION AREAS | DATE | | DAS IS SALAM WATER SUPPLY & SANITATION AUTHORITY (DARASA) | |
| CHECKED BY | | DRAWING NO. | PT-TYPC-209 | | WATER SUPPLY AND SANITATION SERVICES OF PUBLIC TOILET FOR DHAIR SALAM | FEATURE OF REV. | | CONSULTANT | |
| APPROVED BY | | | | | | CHECKED BY | | DOHWA ENGINEERING CO. LTD IN ASSOCIATION WITH LUPTAM CONSULT LTD AND WWS | |
| SHEET NO. | | | | | | APPROVED BY | | | |




front Elevation



Right Side Elevation



Rear Elevation




Left Side Elevation


NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN
2. DO NOT SCALE FROM THIS DRAWING
3. THE SCALES GIVEN ON THIS DRAWING REFER TO THE A1 SIZE ORIGINAL DRAWING
4. THE SUBGRADE SHALL BE COMPACTED TO 98% MAXIMUM DRY DENSITY BEFORE THE PLACEMENT OF hardcore
5. CONCRETE SHALL BE CLASS C30/37 FOR STRUCTURAL MEMBERS AND CLASS C8/10 FOR BUNDING
6. THE MAXIMUM SIZE OF AGGREGATE SHALL BE 20mm UNLESS OTHERWISE SHOWN
7. REINFORCEMENT SHALL BE HIGH TENSILE DEFORMED TYPE WITH A CHARACTERISTIC YIELD STRESS OF AT LEAST 425N/mm²
8. COVER TO REINFORCEMENT SHALL BE:
 - FOUNDATIONS 50mm
 - SLABS 25mm
 - WALLS AND BEAMS 30mm
9. LAPS TO ALL REINFORCEMENT SHALL BE 50 * BAR DIAMETER UNLESS OTHERWISE SHOWN


| | | | | | | | | | |
|-------------|--|-------------|-------------|---------|--|----------------|--|------------|---|
| DESIGN BY | | SCALE | 1:100 | PROJECT | PROVISION OF FACILITIES AND TECHNICAL SERVICES FOR CREATION OF ESSENTIAL FRAMEWORK CONDITIONS, CAPACITY BUILDING, PREPARATION OF DETAILED ENGINEERING DESIGNS AND BIDDING DOCUMENTS, AND CONSTRUCTION SUPERVISION OF PFS ON GRID SIMILATION WORKS IN DAR ES SALAAM | REVISION | | CLIENT | DAR ES SALAAM WATER SUPPLY & SANITATION AUTHORITY (DARWASA) |
| DRAWN BY | | DATE | APRIL 2021 | TITLE | TYPICAL DRAWINGS FOR PUBLIC TOILET TYPE 3 FOR BUS STAYS AND MARKET AREAS | DATE | | CONSULTANT | DOHWA Engineering CO., LTD IN ASSOCIATION WITH LUPTAN CONSULTANTS LTD AND WWS |
| CHECKED BY | | DRAWING NO. | RT-TYRC-300 | | ELEVATION VIEW OF PUBLIC TOILET FOR 100% GROUND TYPE | NATURE OF REV. | | | |
| APPROVED BY | | | | | | CHECKED BY | | | |
| SHEET NO. | | | | | | APPROVED BY | | | |



| | | | | | | | | | |
|-------------|--|-------------|-------------|---------|--|----------------|--|------------|---|
| DESIGN BY | | SCALE | AS SHOWN | PROJECT | PROMOTION OF FACILITIES AND TECHNICAL SERVICES FOR CREATION OF ESSENTIAL FRAMEWORK CONDITIONS, CAPACITY BUILDING, PREPARATION OF DETAILED ENGINEERING DESIGNS AND BIDDING DOCUMENTS, AND CONSTRUCTION SUPERVISION OF THE QATAR SANITATION WORKS IN Doha IS SALAFIN | REVISION | | CLIENT | Doha IS SALAFIN WATER SUPPLY & SANITATION AUTHORITY (DAWASA) |
| DRAWN BY | | DATE | APRIL 2021 | TITLE | TYPICAL DRAWINGS FOR PUBLIC TOILET TYPE (FOR BUS STOPS AREAS) | DATE | | CONSULTANT | DOHWA Engineering CO., LTD IN ASSOCIATION WITH LUPTAK CONSULTANTS LTD AND WWS |
| CHECKED BY | | DRAWING NO. | PT-COPI-431 | | WATER CLOSETS AND MANHOLES DETAILS FOR PUBLIC TOILET | NATURE OF REV. | | | |
| APPROVED BY | | | | | | CHECKED BY | | | |
| SHEET NO. | | | | | | APPROVED BY | | | |




SECTION B-B
SCALE 1:40




PLAN
SCALE 1:40

| | | | | | | | | | |
|-------------|--|-------------|-------------|---------|--|----------------|--|------------|--|
| DESIGN BY | | SCALE | 1:40 | PROJECT | PROVISION OF FACILITIES AND TECHNICAL SERVICES FOR CREATION OF ESSENTIAL FRAMEWORK CONDITIONS, CAPACITY BUILDING, PREPARATION OF DETAILED ENGINEERING DESIGN AND BIDDING DOCUMENTS, AND CONSTRUCTION SUPERVISION OF THE DRY-GRID SANITATION WORKS IN DAR ES SALAAM | REVISION | | CLIENT | DAR ES SALAAM WATER SUPPLY & SANITATION AUTHORITY (DAWASA) |
| DRAWN BY | | DATE | APRIL 2021 | TITLE | TYPICAL DRAWING FOR PUBLIC TOILET TYPE 3 FOR BUS STATION AREAS | DATE | | CONSULTANT | DOHWA Engineering CO., LTD IN ASSOCIATION WITH LUPTAN CONSULTING LTD AND WWS |
| CHECKED BY | | DRAWING NO. | PT-COPE-403 | | 30% TANK OVERALL ARRANGEMENT SCALE FOR PUBLIC TOILETS | NATURE OF REV. | | | |
| APPROVED BY | | | | | | CHECKED BY | | | |
| SHEET NO. | | | | | | APPROVED BY | | | |






SECTION A-A
SCALE 1/40




SECTION C-C
SCALE 1/40

| | | | | | | | | | |
|-------------|--|----------|-------------|---------|---|-------------|----------|---|--|
| DESIGN BY | | SCALE | 1:40 | PROJECT | PROVISION OF FACILITIES AND TECHNICAL SERVICES FOR CREATION OF ESSENTIAL FRAMEWORK, CONVERSIONS, CAPACITY BUILDING, PREPARATION OF DETAILED ENGINEERING DESIGN AND BIDDING DOCUMENTS, AND CONSTRUCTION SUPERVISION OF THE OFF-GIS SANITATION WORKS IN DAF ES SALAAM | REVISION | | CLIENT | DAF ES SALAAM WATER SUPPLY & SANITATION AUTHORITY (DAWASA) |
| DRAWN BY | | | | | | DATE | MAY 2021 | | |
| CHECKED BY | | DATE | APRIL 2021 | TITLE | TYPICAL DRAWINGS FOR PUBLIC TOILET TYPE 3 FOR BUS STAND AREA | CHECKED BY | |   | |
| APPROVED BY | | DATE | APRIL 2021 | | | APPROVED BY | | | |
| SHEET NO. | | REVISION | PT-COFT-024 | | SERIES 1/40 SECTION AND REINFORCEMENT DETAILS FOR PUBLIC TOILET | | | | |



SOAKAWAY PIT-1 PLAN
SC 1:25



SOAKAWAY PIT
SC 1:25



SECTION B-B
SC 1:25



| | | | | | | | | | |
|-------------|--|-------------|-------------|---------|--|----------------|--|------------|---|
| DESIGN BY | | SCALE | 1:50 | PROJECT | PROVISION OF FACILITIES AND TECHNICAL SERVICES FOR CREATION OF ESSENTIAL RAINWATER COLLECTION, CAPACITY BUILDING, PREPARATION OF LOCAL ENGINEERING DESIGN AND BIDDING DOCUMENTS, AND CONSTRUCTION SUPERVISION OF THE CITY-WIDE SANITATION WORK IN DAKA SALAM | REVISION | | CLIENT | DAK ES SALAM WATER SUPPLY & SANITATION AUTHORITY (DAWASA) |
| DRAWN BY | | DATE | APRIL 2021 | TITLE | TYPICAL DRAWING FOR PUBLIC SOLID WASTE DISPOSAL PLANT | DATE | | CONSULTANT | DOHWA Engineering CO., LTD IN ASSOCIATION WITH LUFTAN CONSULT LTD AND WWS |
| CHECKED BY | | DRAWING NO. | PT-COPT-005 | | SOAKAWAY PIT GENERAL ARRANGEMENT SECTION & REINFORCEMENT DETAILS FOR PUBLIC TOILET | NATURE OF REV. | | | |
| APPROVED BY | | | | | | CHECKED BY | | | |
| SHEET NO. | | | | | | APPROVED BY | | | |

Appendix VII: Non-Technical Executive Summary (Kiswahili Version)

MUHTASARI

Muhtasari wa kina wa mradi wa Choo cha Umma Kinachopendekezwa kujengwa katika stendi ya mabasi ya Mlonganzila, Mtaa wa Mlonganzila, Kata ya Kwembe, Wilaya ya Ubungo, Mkoa wa Dar es Salaam

Mwekezaji: Mamlaka ya Majisafi na Usafi wa Mazingira Dar es Salaam (DAWASA)

Mawasiliao ya Mwekezaji: DAWASA,

Jengo la DAWASA, Barabara ya Dunga/Malaga, Mwananyamala.

S.L. B 1573, Dar es Salaam. TANZANIA.

Simu. +25522276006/15; Faksi: +255222762480;

Barua pepe: dawasaceo@dawasa.co.tz

Mtaalam Mshauri: Prof. Rubhera RAM Mato (PhD), CEng. (T), Reg. EIA Expert

S.L.B 35478, Dar es Salaam, Tanzania

Simu ya rununu: +255754898592

Barua pepe: rubheramato@gmail.com

UTANGULIZI

SERIKALI ya Jamhuri ya Muungano wa Tanzania (GoT) kupitia Mamlaka ya Majisafi na Majitaka Dar es Salaam (DAWASA) chini ya Wizara ya Maji inatarajia kutekeleza Mradi wa Usafi wa Mazingira kwa njia ya Off Grid (OGSP) katika Jiji la Dar es Salaam ili kuhudumia maeneo ya pembezoni mwa miji. haijaunganishwa na mfumo mkuu wa maji taka. DAWASA imepata ufadhili kutoka kwa Jumuiya ya Maendeleo ya Kimataifa (IDA) ikiwa ni mkopo wa kutekeleza mradi huo. Kabla ya kutekeleza mradi huo, sheria nchini Tanzania inataka Tathmini ya Athari kwa Mazingira ifanywe na kuidhinishwa na mamlaka husika. Ili kuzingatia sheria nchini Tanzania, DAWASA inatarajia kutumia sehemu ya mapato ya mikopo kwa malipo stahiki kwa ajili ya huduma

za ushauri kwa ajili ya Maandalizi ya Tathmini ya Athari kwa Mazingira na Kijamii (ESIA) na Ripoti ya Mpango Kazi wa Makazi Mapya (RAP) kwa ajili ya ujenzi wa miradi ya usafi wa mazingira nje ya gridi ya taifa.

Mradi wa Off-Grid unakusudiwa kutatua changamoto hizi. Mradi wa Off-Grid umegawanywa katika miradi midogo kadhaa ambayo itatekelezwa katika manispaa tano za Jiji la Dar es Salaam. Mojawapo ni Ujenzi wa Choo cha Umma katika stendi ya mabasi ya Mloganzila, Mtaa wa Mloganzila, Kata ya Kwembe katika Manispaa ya Ubungo. Choo hicho kitahudumia zaidi abiria wanaotumia kituo cha mabasi cha Mloganzila.

Mradi unaopendekezwa unahusu ujenzi wa ghala la kuhifadhia maji taka kwa matumizi ya umma katika stendi ya mabasi ya Mloganzila. Asili ya mradi huongeza ulinzi wa mazingira kupitia utunzaji sahihi na utupaji wa maji taka ya ndani. Kulingana na Ratiba ya Kwanza ya EIA na Kanuni za Ukaguzi (zilizorekebishwa) za 2018, aina ya mradi ni ndogo na haijumuishi athari kubwa. Kwa kuwa Kanuni hizi, mradi uko chini ya aina ya B2, ambayo inaitwa "shughuli ndogo ndogo na biashara zinazohitaji usajili lakini hazitahitaji Tathmini ya Athari kwa Mazingira". Kanuni zinatoa miradi ya aina ya B" kwa msanidi programu kuwasilisha Muhtasari wa Mradi ambao utachunguzwa na kutolewa na Cheti cha Tathmini ya Athari kwa Mazingira na mamlaka inayohusika.

MAELEZO YA MRADI

Eneo la mradi lipo katika kitongoji cha Mloganzila (mtaa), kata ya Kwembe, Wilaya ya Ubungo katika Mkoa wa Dar es Salaam. Tovuti ya mradi iko kijiografia katika eneo la 37S UTM na kuratibu 506302 (Eastings) na 9247052 (Northings). Eneo hili liko umbali wa Kilomita 33 kutoka katikati ya Jiji kupitia barabara ya Morogoro. Kivutio kikuu cha jirani ni Hospitali ya Mloganzila. Tangi la kuhifadhia maji litawekwa ili kuhakikisha ugavi wa maji kila mara kwenye choo. Mhudumu atawekwa kusimamia usafi na usalama wa choo.

Mradi unakusudia kuanzisha Choo cha kisasa cha Umma katika Stendi ya Mabasi ya Mloganzila, kata ya Kwembe Manispaa ya Ubungo. Takriban vitengo 22 kila kimoja kikiwa na ukubwa tofauti na aina ya huduma kuanzia mikojo, bideti, WCS, HWB, vinyunyuu, ukumbi, chumba cha kuhifadha na nafasi ya ofisi. Tovuti ya Mradi Unaopendekezwa inashughulikia takriban eneo la 120m². DAWASA imeingia mkataba wa maelewano na Manispaa ya Ubungo kwa ajili ya kuendesha choo kupitia kampuni binafsi. DAWASA itabaki kuwa mmiliki wa kituo. MoU inajumuisha taratibu za kugawana mapato.

Shughuli kuu za ujenzi wa miradi midogo ni pamoja na kusafisha tovuti, uchimbaji, kujaza, kuzuia udongo na uimarishaji, utupaji wa ziada ya nyenzo zilizochimbwa, kazi za chuma, kazi za saruji, mbao (useremala), umaliziaji pamoja na uchoraji.

Bajeti ya pendekezo la choo cha umma ni TZS 45 Milioni. Fedha hizo zitatolewa na Serikali ya Jamhuri ya Tanzania kupitia ufadhili wa Benki ya Dunia.

SERA, MFUMO WA SHERIA NA TAASISI

Tanzania imejitolea kufikia malengo ya maendeleo endelevu. Msukumo huu unazingatiwa katika Sera ya Taifa ya Mazingira na sera nyingine za kisekta zikiwemo;

- Sera ya Kitaifa ya Mazingira, 2021
- Sera ya Taifa ya Ardhi ya mwaka 1997
- Sera ya Sekta ya Ujenzi (2003)
- Sera ya Taifa ya Afya (2003)
- Sera ya Taifa ya Jinsia ya 2000
- Sera ya Taifa ya Maendeleo ya Makazi (2000)

Sheria na kanuni muhimu ambazo zina umuhimu kwa maendeleo ya barabara kuhusiana na usimamizi wa mazingira ni pamoja na;

- Sheria ya Usimamizi wa Mazingira (2004)
- Kanuni za Usimamizi wa Mazingira (Ada na Ada) za 2021
- Kanuni za Usimamizi wa Mazingira (Udhibiti wa Taka hatarishi), 2021
- Kanuni za Usimamizi wa Mazingira (Udhibiti wa Kelele na Mtetemo), 2015
- Kanuni za Usimamizi wa Mazingira (Marufuku ya Mifuko ya Kubeba Plastiki), za 2019
- Kanuni za Usimamizi wa Mazingira (Udhibiti wa Taka Ngumu), 2007
- Kanuni za Usimamizi wa Mazingira (Ubora wa Maji), 2009
- Kanuni za Usimamizi wa Mazingira (Ubora wa Hewa), 2009
- Kanuni za Usimamizi wa Mazingira (Ubora wa Udongo), 2009
- Sheria ya Afya na Usalama Kazini ya 2003
- Sheria ya Ugavi wa Maji na Usafi wa Mazingira Na. 12 ya 2009
- Sheria ya Usajili wa Wahandisi na Marekebisho yake ya 1997 na 2007
- Sheria ya Usajili wa Makandarasi (Marekebisho) ya mwaka 2008
- Sheria ya Wabunifu na Wakadiriaji Majenzi (1997)
- Sheria ya Mipango Miji (2007)
- Sheria ya Afya ya Umma (2009)
- Miongozo ya Benki ya Dunia ya Usimamizi wa Mazingira

MAZINGIRA YA MRADI

Eneo la tovuti liko katika ukanda wa pwani wa tropiki wa Tanzania na huathiriwa na misimu miwili mikuu ya hali ya hewa, ambayo ni mvua na joto. Mpangilio wa mvua ni ule wa aina mbili na mvua za kawaida zisizo na uhakika. Mvua za masika zinazonyesha karibu katika Manispaa nzima kati ya Desemba na Februari, Wakati mvua kubwa za muda mrefu katika kipindi cha Machi hadi Juni, kiasi cha mvua zilizopatikana ni kati ya 800-1200mm kwa mwaka. Halijoto kama vile mvua pia huathiriwa na bahari. Joto la juu hutawala mwaka mzima kuanzia 25 °C katika kipindi cha Juni hadi Agosti hadi 35 °C katika kipindi cha Januari hadi Machi.

Data za ubora wa Maji kutoka kwenye visima vifupi karibu na eneo la mradi hazikupatikana mara moja wakati wa utafiti huu. Hata hivyo tafiti za awali za

maeneo kama hayo zinaonyesha uwezekano mkubwa wa uchafuzi wa maji chini ya ardhi kutoka kwa vyoo vya shimo vilivyo karibu vilivyo umbali wa chini ya 30m kutoka kwa kisima kifupi (Still na Nash, 2002).

Uchunguzi wa ubora wa hewa unaonyesha kuwa hali ya hewa kwa ujumla katika eneo la mradi ni nzuri kwani hakuna shughuli yoyote ya ajabu inayochangia uchafuzi wa hewa. Hata hivyo, mabadiliko ya msimu pamoja na kuzorota kwa hali ya hewa ya ndani na ya muda hutokea. Kwa upande mwingine, kiwango cha kelele katika eneo la mradi ni hasa kutokana na kusonga gari kando ya barabara, kusonga hewa (upepo) au mvua na ndege. Shughuli za mradi wakati wa ujenzi zitabadilisha mwelekeo na amplitude ya kelele katika eneo la mradi.

WADAU WA MRADI NA USHIRIKISHI

Mbinu rahisi ilipitishwa ili kubainisha washikadau wakuu na maswala makuu ya kimazingira na kijamii. Hii ilihusisha uchunguzi wa kimwili na mashauriano (mashauriano ya moja kwa moja). Taarifa nyingine kuhusu mradi huo zilipatikana kupitia utafiti wa dawati. Wakati wa kufanya utafiti huu, wadau mbalimbali walishauriwa. Miongoni mwao ni pamoja na Halmashauri ya Manispaa ya Ubungo na jumuiya ya stendi ya mabasi ya Mloganzila. Katika mkutano huo, mshauri huyo alitoa maelezo mafupi kuhusu pendekezo la choo cha umma.

ATHARI MUHIMU ZINAZOWEZEKANA KWA MAZINGIRA NA KIJAMII

Athari zifuatazo zilitambuliwa kuwa zinaweza kutokea wakati wa Awamu ya Uhamasishaji

- Fursa za ajira
- Uchafuzi wa kelele
- Uchafuzi wa Hewa kutokana na uchafuzi wa vumbi

Athari zifuatazo zilitambuliwa kuwa zinaweza kutokea wakati wa Awamu ya Ujenzi

- Fursa za ajira
- Kuboresha hali ya maisha na ukuaji wa uchumi
- Kuboresha afya ya umma
- Kuongezeka kwa mwingiliano wa kijamii na kitamaduni
- Ongezeko la Mapato kwa taifa kupitia kodi, za moja kwa moja na zisizo za moja kwa moja
- Kuongezeka kwa VVU/UKIMWI na magonjwa mengine yanayohusiana na ngono:
 - Uharibifu na ukiukaji wa mali
 - Uchafuzi wa kelele
 - Uchafuzi wa Hewa kutokana na uchafuzi wa vumbi
 - Uwezekano wa maambukizi ya magonjwa ya kuambukiza
 - Hunuka na nzi kwenye vyoo
 - Hatari kubwa ya Afya inayohusishwa na kazi ya ujenzi
 - Uzalishaji wa taka wakati wa ujenzi
 - Uchafuzi wa maji chini ya ardhi kutokana na kufungia udongo

Athari zifuatazo zilibainishwa kuwa zinaweza kutokea wakati wa Awamu ya Operesheni

- Kuboresha maisha ya kijamii na kiuchumi na heshima ndani ya jamii inayofaidika
- Ongezeko la Mapato kwa taifa kupitia kodi, za moja kwa moja na zisizo za moja kwa moja
- Hunuka na nzi kwenye vyoo

KINGA NA USIMAMIZI WA AJALI WAKATI WA HATUA YA UTEKELEZAJI

Mradi utatekezwa kwa kufuata sheria za kazi nchini Tanzania, hususan, Sheria ya Afya na Usalama Kazini (2003). Vifungu vya kulinda afya na usalama wa wafanyikazi vitajumuishwa katika hati za mkataba kwa hatua ya utekelezaji ambayo ni pamoja na yafuatayo; utoaji na utekelezaji wa matumizi ya vifaa vya kinga binafsi vinavyofaa kwa wafanyakazi wote k.m. ovaroli, glavu, barakoa, n.k. (popote inapohitajika), uwepo wa mpango wa maandalizi

ya dharura uliowekwa kabla ya kuanza kwa shughuli za ujenzi na vile vile kuhakikisha usalama wa tovuti kwa kuzungushia uzio eneo lote la mradi na kutoa milango kwa madhumuni ya kuingilia na kutoka.

HATUA ZA KUPUNGUZA NA MPANGO WA USIMAMIZI WA MAZINGIRA NA KIJAMII (ESMP)

Chaguzi za kupunguza au kuzuia athari mbaya za kijamii na kimazingira zilizotambuliwa pamoja na mpango wa ufuatiliaji zimependekezwa katika ripoti hii na zimo katika ESMP. Wengi wao ni msingi wa mazoea mazuri ya uhandisi na mwitikio wa wakati wa taasisi inayohusika. ESMP inaelezea ratiba ya utekelezaji wa mapendekezo ya hatua za kupunguza na pia kupanga shughuli za ufuatiliaji wa muda mrefu. Inafafanua majukumu na wajibu wa watendaji mbalimbali wa mpango. Gharama za Mbinu za kimazingira na kijamii ni TSH 38,000,000 (Bila gharama zitakazoonekana katika wakati huo (BOQ) na zoezi la makazi mapya. Makisio ya gharama za kila mwaka za kutekeleza pendekezo la mpango wa magari ya kimazingira na kijamii ni TSH 24,000,000.

HITIMISHO

Hivyo basi, imehitimishwa kuwa utekelezaji wa mapendekezo ya ujenzi wa vyoo vya umma katika stendi ya mabasi ya Mloganzila, Mloganzila Mtaa, kata ya Kwembe katika Manispaa ya Ubungo, Dar es Salaam hautaleta athari mbaya endapo hatua zinazopendekezwa za kupunguza makali zimewekwa ipasavyo na kwa wakati. Athari mbaya zilizotambuliwa zitadhibitiwa kupitia hatua zilizopendekezwa za kupunguza na mfumo wa utekelezaji uliowekwa katika EIS hii. DAWASA imejitolea kutekeleza mapendekezo yote yaliyotolewa katika EIS na kutekeleza zaidi ratiba za ukaguzi na ufuatiliaji wa mazingira.