

THE UNITED REPUBLIC OF TANZANIA



MINISTRY OF WATER



Dar es Salaam Water Supply and Sanitation Authority

DAWASA Building, Dunga/Malaga Street, Mwananyamala Area

P. O. Box 1573, Dar es Salaam. TANZANIA.

Tel. +25522276006/15; Fax: +255222762480; E-mail: dawasaceo@dawasa.co.tz

THE PROPOSED CONSTRUCTION OF FECAL SLUDGE TREATMENT PLANT (FSTP) TO BE BUILT AT GOLANI MTA, KIMBIJI WARD, KIGAMBONI DISTRICT, DAR ES SALAAM REGION

Submitted to:

National Environment Management Council,

Head Office, Kambarage Tower, 6th Floor, P. O. Box 2724, Dodoma.

Phone: +255 262960098, 0713608930,

Email Address: dg@nemc.or.tz

Website: www.nemc.or.tz

Lead Consultant:

Prof. Rubhera RAM Mato (PhD), CEng. (T), Reg. EIA Expert

P. O BOX 35478, Dar es Salaam, Tanzania





Mobile: +255754898592; E-Mail: rubheramato@gmail.com

Submission date: August, 2024

ACKNOWLEDGEMENT

The Proponent (DAWASA) wishes to convey a heartfelt thanks and appreciation to all stakeholders who in one way or another supported the completion of this work. Thanks very much all of you. Special thanks to the Kigamboni Municipal Council Officers for their prompt assistance during the fieldwork. Last but not least we thank the local community and wards leaderships in the project vicinity for their cooperation. A sincere appreciation for all experts and assistants who participated in data collection and preparation of this report.

THE STUDY TEAM

NAME	POSITION	NEMC Reg. No.	SIGNATURE
Prof. Rubhera RAM Mato	Environmental and ESIA Team Leader	Registered NEMC/EIA/0092	
Mr. Robert Kishiki	Sociologist	Not Registered	
Mr. Emmanuel Rajab	Environmental Engineer	Registered EC/EE- EIA/2021/0015	
Mr. Melkizedeck Stephano	Environmentalist	Not Registered	

ABBREVIATIONS

AAQ	Ambient Air Quality
AIDS	Acquired Immuno-Deficiency Syndrome
DAWASA	Dar es Salaam Water Supply and Sanitation Authority
EIA	Environmental Impact Assessment
EMP	Environmental Management Plan
ESIA	Environmental and Social Impact Assessment
ESMP	Environmental and Social Monitoring Plan
GoT	Government of Tanzania
HIV	Human Infection Virus
IDA	International Development Association
LGA	Local Government Authority
NEMC	National Environment Management Council
NEP	National Environment Policy
OGSP	Off-Grid Sanitation Project
PPE	Personal Protective Equipment
PVC	Polyvinyl Chloride
RAP	Resettlement Action Plan
STDS	Sexual Transmitted Diseases

TABLE OF CONTENTS

ACKNOWLEDGEMENT	I
THE STUDY TEAM.....	II
ABBREVIATIONS.....	I
1.0 BACKGROUND AND JUSTIFICATION	1
1.1 NATURE OF THE PROJECT	2
2.0 PROJECT DESCRIPTION	3
2.1 PROJECT LOCATION	3
2.2 ACCESSIBILITY	5
2.3 SPECIFIC FEATURES.....	5
2.4 ADJACENT LAND USE	6
2.4.1 <i>Land Ownership</i>	7
2.5 PROJECT ACTIVITIES	8
2.5.1 MOBILIZATION OR PRE-CONSTRUCTION PHASE.....	8
2.5.2 CONSTRUCTION PHASE	8
2.5.3 DEMOBILIZATION PHASE	9
2.5.4 OPERATION PHASE.....	9
2.5.5 DECOMMISSIONING PHASE	9
2.6 PROJECT DESIGN	9
2.6.1 DESIGN CRITERIA.....	9
2.6.2 TECHNOLOGY DESCRIPTION.....	10
2.6.2.1 <i>Garbage screen</i>	10
2.6.2.2 <i>Balancing tank</i>	10
2.6.2.3 <i>Biogas digester</i>	10
2.6.2.4 <i>Anaerobic Baffled Reactor (ABR)</i>	11
2.6.2.5 <i>Planted Gravel filter</i>	11
2.6.2.6 <i>Sludge Drying Bed (SDB)</i>	12
2.7 SLUDGE LOADING INTENSITY.....	12
2.8 PROPOSED PROCESSING STEPS.....	12
2.9 PROJECT REQUIREMENTS AND WASTE GENERATION	14
2.9.1 PROJECT REQUIREMENTS	14
2.9.1.1 <i>Construction materials and labour force</i>	14
2.9.1.2 <i>Labour force</i>	14
2.9.1.3 <i>Machinery and Equipment</i>	14
2.9.2 WASTES GENERATION.....	14
2.9.2.1 <i>Liquid waste management</i>	15
2.9.2.2 <i>Solid waste management</i>	15
3.0 POLICIES, LEGISLATION AND INSTITUTIONAL ASPECT	17
3.1 RELEVANT POLICIES.....	17
3.1.1 <i>National Environment Policy 2021</i>	17
3.1.2 <i>National Land Policy of 1997</i>	18
3.1.3 <i>Construction Industry Policy (2003)</i>	19
3.1.4 <i>National Health Policy (2003)</i>	19

3.1.5 National Gender Policy of 2000	19
3.1.6 National Human Settlements Development Policy (2000)	20
3.2 PRINCIPAL LEGISLATIONS AND REGULATIONS	20
3.2.1 Environmental Management Act (2004)	20
3.2.2 The Environmental Management (Fees and Charges) Regulations, 2021	21
3.2.3 The Environmental Management (Control of hazardous Waste) regulations, 2021	22
3.2.4 The Environmental Management (Control of Noise and vibration) regulations, 2015..	22
3.2.5 The Environmental Management (Prohibition of Plastic Carrier bags) regulations, 2019	22
3.2.6 The Environmental Management (Solid Waste Management) regulations, 2007	23
3.2.7 The Environmental Management (Water Quality) regulations, 2009	23
3.2.8 The Environmental Management (Air Quality) regulations, 2009.....	24
3.2.9 The Environmental Management (Soil Quality) regulations, 2009.....	24
3.2.10 Occupational Health and Safety Act 2003	25
3.2.11 The Water Supply and Sanitation Act No. 12 of 2009.....	25
3.12 Engineers Registration Act and its Amendments 1997 and 2007	26
3.2.13 The Contractors Registration (Amendment) Act, 2008.....	26
3.2.14 The Architects and Quantity Surveyors Act (1997)	26
3.2.15 The Urban Planning Act (2007).....	26
3.2.16 Public Health Act (2009)	27
4.0 BASELINE INFORMATION	28
4.1 INTRODUCTION	28
4.2 PHYSICAL CHARACTERISTICS	28
4.2.1 Climate	28
4.2.2 Groundwater sources.....	30
4.2.3 Topography.....	30
4.2.4 Air Quality and Noise Level	31
4.2.5 Noise and Vibration	31
4.4.8 WATER TABLE AND WATER QUALITY ANALYSIS.....	31
5.0 STAKEHOLDER VIEW ON THE PROPOSED PROJECT	35
6.0 POTENTIAL IMPACTS	37
6.1 POSITIVE IMPACTS.....	37
6.1.1 Improved living conditions and economic growth	37
6.1.2 Employment opportunities	37
6.1.3 Increased Revenue to the nation through taxes, both direct and indirect.....	37
6.1.4 Biogas production potential	37
6.1.5 Minimized forest products harvesting	38
6.1.6 Cost reduction for sewage management	38
6.2 NEGATIVE IMPACTS	38
6.2.1 Increased HIV/AIDS and other sexual-related diseases	38
6.2.2 Loss of biodiversity.....	39
6.2.3 Land degradation and increased erosion.....	39
6.2.4 Noise pollution	40
6.2.5 Air Pollution from dust emission	40
6.2.6 High Risk of Health associated with construction work.....	40
6.2.7 Waste generation during construction	41
7.0 ACTION PLAN FOR HEALTH AND SAFETY OF WORKERS AND COMMUNITY DURING THE IMPLEMENTATION STAGE	

7.1	GENERAL	42
7.2	HEALTH AND SAFETY MANAGEMENT SYSTEM	42
7.2.1	<i>Safety Training and Promotion</i>	42
7.2.1.1	<i>Health and Safety Induction Training</i>	43
7.2.1.2	<i>On the Job Training</i>	43
7.2.1.3	<i>Refresher courses</i>	43
7.2.1.4	<i>Tool Box Talks</i>	43
7.2.1.5	<i>Safety Promotion</i>	44
7.2.2	<i>Safety inspection and Follow up Actions</i>	44
7.2.3	<i>Reporting of Accidents, incidents & Investigation and Accident Statistics</i>	45
7.2.4	<i>Hazard Identification and Risk Assessment</i>	46
7.2.5	<i>Industrial Health and Hygiene</i>	46
7.2.6.1	<i>Hazardous substances</i>	47
7.2.6.2	<i>Heat</i>	47
7.2.6.3	<i>Dust</i>	48
7.2.6.4	<i>Noise</i>	48
7.2.6.5	<i>Vibration</i>	49
7.2.6.6	<i>Sanitary Facilities</i>	49
7.2.6	<i>Personal Protective Equipment (PPE)</i>	49
7.2.7	<i>First Aid Facilities</i>	50
7.2.8	<i>Fire Prevention and Fighting Facilities</i>	50
7.2.9	<i>Road safety management</i>	51
7.2.10	<i>Traffic management plan</i>	52
7.2.11	<i>Sub-Contractors</i>	52
7.2.12	<i>General Safety Rules</i>	53
7.3	SAFETY IN VARIOUS CONSTRUCTION ACTIVITIES	54
7.3.1	<i>Excavation</i>	54
7.3.2	<i>Reinforcement Steel Work</i>	55
7.3.3	<i>Concreting</i>	56
7.3.4	<i>Material Handling</i>	57
7.3.4.1	<i>Mechanical Handling</i>	57
7.3.4.2	<i>Manual Handling</i>	58
7.3.5	<i>Working at Height</i>	59
7.3.6.1	<i>Scaffolding</i>	59
7.3.6.2	<i>Ladders</i>	60
7.3.6	<i>Heavy equipment and workshop</i>	60
7.3.7	<i>Cable Laying, Termination and Jointing & Electrical Works:</i>	62
7.3.8	<i>Portable Power and Hand Tools</i>	64
7.4	EMERGENCY PREPAREDNESS AND RESPONSE	65
7.4.1	<i>Review and responsibilities</i>	65
8.0	ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN	67
8.1	ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN	67
9.0	MONITORING PLAN	72
9.1	<i>ENVIRONMENTAL MONITORING</i>	72
10.0	PROJECT BUDGET	74
11.0	CONCLUSION	74

REFERENCES75

APPENDIX I: LIST OF STAKEHOLDERS CONSULTED76

APPENDIX II: MINUTES OF MEETINGS WITH STAKEHOLDERS79

APPENDIX III: MEMORANDUM OF UNDERSTANDING BETWEEN DAWASA AND.....86

DAR ES SALAAM MUNICIPAL COUNCILS.....86

APPENDIX IV: SCREENING LETTER FROM NEMC.....105

APPENDIX V: PERMIT TO USE THE LAND FROM THE LOCAL GOVERNMENT AUTHORITY.....107

APPENDIX VI: ARCHITECTURAL DRAWINGS.....109

LIST OF FIGURES

Figure 1: A Map of the Dar es Salaam region showing the project Municipal4

Figure 2: An Extract of Google Image to show the Location of the project area
(Accessed 30th August 2022)5

Figure 3: Natural Vegetation species and footways at the site (Source: Site visit
August 24th 2022).....6

Figure 5: The Fecal Sludge Treatment Facility cross-section diagram..... 13

Figure 5: Stakeholder’s consultation meeting at Golani (Kimbiji Ward) and
Kigamboni Municipal Council office (Source: Fieldwork August 24th 2022).....35

LIST OF TABLES

Table 1: The coordinates of the project area.....3

Table 2: Adjacent Land use7

Table 2: Management of construction and operation wastes 15

Table 3: Stakeholders issues and concerns.....36

Table 4: Environmental and Social Management Plan for the Proposed
Construction of Feacal Sludge Treatment Plant at Golani area, Kimbiji ward,
Kigamboni Municipal.....69

Table 5: Monitoring Plan for the Proposed Construction of Feacal Sludge
Treatment Plant (FSTP) at Golani area, Kimbiji ward, Kigamboni Municipal-Dar
es Salaam.....73

Environmental and Social Impacts Assessment for The Proposed Fecal Sludge Treatment Plant (FSTP) to be built at Golani, Kimbiji Ward-Kigamboni Municipality in the Dar es Salaam Region

1.0 BACKGROUND AND JUSTIFICATION

The Government of the United Republic of Tanzania (GoT) through the Dar es Salaam Water and Sewerage Authority (DAWASA) under the Ministry of Water intends to implement an Off Grid Sanitation Project (OGSP) in Dar es Salaam City to serve peri-urban areas not connected to the central sewerage system. DAWASA has received financing from the International Development Association (IDA) in the form of a credit to implement the project. Before implementing the project, the law in Tanzania requires an Environmental Impact Assessment to be conducted and approved by the relevant authorities. To comply with the law in Tanzania, the DAWASA intends to apply a portion of the proceeds of the credit to eligible payments for consulting services for the Preparation of Environmental and Social Impact Assessment (ESIA) and Resettlement Action Plan (RAP) Report for the construction of off-grid sanitation projects.

Dar es Salaam is the largest and most important commercial and industrial center in Tanzania. The city has an estimated population of about 5.0 million and is projected to double at the end of the project horizon of 25 years. About 10% of the population is served by sewers and the rest almost depend on on-site sanitation systems. The sewer coverage is only limited to the area within the city center with a total length of 67.8km and the system is based on separate systems that discharges their effluent into oxidation ponds, and into the sea through a sea outfall of about 1.03km long. The onsite sanitation systems result in Faecal sludge of which handling and management throughout the sanitation chain (from domestic containment, transportation as well as disposal, and treatment) is currently hygienically inadequate thus posing environmental and public health risks. The Off Grid project is intended to address these challenges. The Off Grid project is divided into several subprojects which will be implemented in the five municipalities of Dar es Salaam City. One of these is

the Construction of a Faecal sludge treatment plant at Golani, Kimbiji Ward-Kigamboni Municipality.

The ESIA study will be conducted following the Environmental Management (Environmental Impact Assessment and Audit) (Amendment) Regulations, 2018 along with the Environmental Impact Assessment and Audit Regulations of 2005. These Regulations provide legal procedures for implementing the requirements of the Environmental Management Act Cap.191 of 2004. The Regulations give a mandate to NEMC to oversee the EIA process, which culminates with an award of the EIA Certificate by the Ministry responsible for Environment.

Under the EIA Regulations, NEMC is mandated to screen projects and make decisions regarding the level of EIA required as well as evaluate the adequacy of respective environmental statements. Considering the nature and size of the proposed “Faecal Sludge Project in Kigamboni Municipality”, the project falls under Category “B2” (Non-Mandatory) under Reg.4 (1) (c) and First Schedule of the amended 2018 Regulations. The regulations require developers to prepare and submit to the National Management Council (NEMC) filled EIA registration forms and “Project Briefs” for all B2 projects. The preparation and content of the “Project Briefs” are provided under Reg.6 (1). The same has been followed in preparing this “Project Brief”. The study for preparing this project brief was conducted in August 2022.

1.1 NATURE OF THE PROJECT

The proposed project concerns the construction of an engineered faecal sludge treatment facility for public use at Golani Street, Kimbiji Ward-Kigamboni Municipality. The nature of the project enhances environmental protection through proper handling and disposal of domestic sewage, also the provision of alternative energy (biogas). According to the First Schedule of the EIA and Audit Regulations (Amended) of 2018, the nature of the project is small and entails no significant impacts. The project is categorized as Type B2, which

according to the regulations are “small-scale activities and enterprises that require registration but shall not require Environmental Impact Assessment. Further, the projects shall not require screening and scoping, rather, the Project Brief shall be examined and issued with an Environmental Impact Assessment Certificate”.

2.0 PROJECT DESCRIPTION

2.1 Project Location

The project site is located at Golani street, Kimbiji ward, Kigamboni Municipal within the Dar es Salaam Region. The project site is geographically located at 37M UTM zone with coordinates in Table 1. The site is 130 meters from the downstream water stream and 40 Kilometers from the Nyerere Bridge. (Refer to Figure 1, and Figure 2).

Table 1: The coordinates of the project area

S/No.	Coordinates	
	Easting	Northing
1.	557291.68	9225496.50



Figure 1: A Map of the Dar es Salaam region showing the project Municipal (Source Consultant, 2022)



Figure 2: An Extract of Google Image to show the Location of the project area
(Source Google Earth Accessed 30th August 2022)

2.2 Accessibility

The project area is accessible through Pemba Mnazi Road from Dege-Kigamboni. The project site for construction of FSTP is about 1.5 km from Nyati Cement Factory, which is approximately 36 km from the Kigamboni Ferry.

2.3 Specific Features

The proposed project site is characterized by natural vegetation. There are tall grasses, shrubs with climbers, *Eucalyptus* plant, and *Trachycarpus fortune* Palm trees and *Senna Siamea* species within the project site. The project site is bordered with roads on the northern and western sides whereas on the southern and eastern side is bordered by footpaths (Figure 3).



Figure 3: Natural Vegetation species and footways at the site (Source: Site visit August 24th 2022)

2.4 Adjacent Land Use

The proposed site for the establishment of FSTP is located at a less populated semi-urban area. However, the project site is surrounded by Residential plots, small scale farms (mainly cassava, peppers, vegetables and some paddy farming remains) adjacent to a stream for irrigation, Ongoing construction of residential buildings, firewood gathering and some old mud-walled with thatched roof buildings as indicated in Table 2. The proposed is about 98 meters from access road and 168 meters from the residential buildings.

Table 2: Adjacent Land use

	
<p>Collected firewood</p>	<p>Locally constructed building</p>
	
<p>Footpath</p>	<p>Ongoing construction of residential buildings</p>
	
<p>Stream used for irrigation at the downstream of the project site (Source: Fieldwork August 2022)</p>	

2.4.1 Land Ownership

The proposed Faecal Sludge Treatment Plant at Golani Mtaa area, project site is solely owned by Kigamboni District. The District has apportioned about 47 Acres piece of land for small size FSTP. There is a Memorandum of Understanding (MoU) that has been signed between DAWASA and Kigamboni

District for the implementation of the project (Appendix III). In this MoU, DAWASA is responsible for the construction and operation of the FSTP while the Kigamboni District avails land and benefit from the emptying fee as revenue.

2.5 PROJECT ACTIVITIES

2.5.1 Mobilization or pre-construction phase

This phase entails mobilization of labour force, and equipment as well as acquisition of various permits as required by the law.

Other activities during this phase include;

- Topographical Survey for setting out purposes,
- Geo-technical Investigation for the areas allocated with the balancing tank and Anaerobic Baffled Reactor (ABR)
- Construction Materials' source Investigation,
- Land acquisition,
- Material storage and material preparation,
- Masonry work
- Finishing works
- Painting works

Duration 1-2 months

2.5.2 Construction phase

This phase entails all the necessary installations, site grading and placement of the facility components. Construction phase is expected to be 18 months.

The major activities include;

- Vegetation clearance and earthworks (foundations excavation),
- Dewatering and site access road formation and drainages construction;
- Construction of parking lot and access ramp for tankers;
- Construction of Garbage screen, balancing tank, Biogas digester,
- Construction of Plant Office, guard house and storage room;
- Preparation of planted gravel filter;
- Plumbing work connecting all treatment units up to the effluent

2.5.3 Demobilization phase

This phase will involve the dismantling of temporary structures such as scar forming and removing/spreading spoil materials for proper restoration of the site.

Estimate duration 1 month

Other activities include;

- General cleanliness of the area, that is clearance of all sorts of solid wastes (plastics, wood, metal, papers, etc);
- Deposit all wastes to the authorized dumpsite;

2.5.4 Operation phase

The phase entails the actual usage of the Faecal sludge Plant. Faecal sludge will be desludged using vacuum takers and disposed of at the proposed facility for further treatment. DAWASA will decide on the mode of running the FSTP for instance instituting fee, Standby attendants will be positioned to oversee the day to day running of the facility. The facility is estimated to run for 30 years with subject to minor and major repair. The memorandum of understanding is attached as Appendix III.

2.5.5 Decommissioning Phase

Decommissioning is not anticipated in the foreseeable future as the completed facility will be serving a number of houses which at present incur many costs to dispose fecal sludge and if not so tend to discharge illegally. However, if this will happen, may entail change of use (functional changes) or demolition triggered by change of land use.

2.6 PROJECT DESIGN

2.6.1 Design criteria

The proposed public design was obtained partly using criteria stipulated in the Tanzania national documents, specifically, the National Guideline for Water, Sanitation and Hygiene for Tanzania Schools prepared by the Ministry of Education, Science and Technology (2016); and the Design, Construction Supervision, Operation and Maintenance (DCOM) Manual Volume II, Design of

Sanitation Projects, Fourth Edition, prepared by the Ministry of Water (2020). The plant structures are ground surface structures hence it is accessible. The proposed technology and construction design follow the objective to execute an engineering design of fecal sludge management facility (one in number at the stated site) which will be simple, cost effective/efficient, easy to operate and maintain performance standards which conform to NEMC.

Technology selection was based on the following four main aspects;

- Land availability
- Context of the location of the treatment sites (existing infrastructures)
- Local operation and maintenance management capacity
- Revenue generation through by-products

2.6.2 Technology description

2.6.2.1 Garbage screen

Domestic sludge is dispersed directly onto the screening inlet chamber to retain the incoming debris before it goes to the preliminary treatment process.

2.6.2.2 Balancing tank

The incoming wastewater is stored in the balancing tank to allow sludge stabilization and controlling flow when it goes to the next treatment units. This tank play key role to reduce shocking loads towards the system especially when the hydraulic loading surpasses plant designed holding capacity.

2.6.2.3 Biogas digester

This unit is designed to separate the incoming wastewater in liquid and solid form as well as the biologically digestion of organic solids. The digestion process takes place without oxygen input, under anaerobic conditions, and generates biogas useful for cooking, lighting and heating. Therefore, the project will produce biogas which will be harvested and used by the nearby facilities ie the nearby residents, but the number of users depends on the volume produced from the nature of the wastewater received in the facility.

2.6.2.4 Anaerobic Baffled Reactor (ABR)

The baffled reactor consists of series of chambers in which the wastewater flows up-stream. Here, the suspended and dissolved solids in the pre-settled waste water undergo anaerobic degradation. The activated sludge settles at the bottom of each chamber and the influent wastewater is forced to flow through this sludge blanket where anaerobic bacteria make use of the pollutants for their metabolism. Progressive decomposition occurs in the successive chambers. A part of the last chambers can optionally be filled up with coarse filter material like, stones, cinder or plastic rings. The filter materials act as carrier material for an attached bio-film, which consumes the organic water pollutants. In ABR plants the BOD removal efficiency is up to 90% and the pathogen removal ranges between 40-75%. The baffled reactor is resistant to shock load and variable inflow. It operates by gravity and maintenance is reduced to desludging of the chambers at intervals of 1-2 years. This unit is advantageous since its sub-soil construction saves space.

2.6.2.5 Constructed Wetland

Constructed wetland or Planted Gravel Filter (PGF) is suitable for wastewater with low percentage of suspended solids that have already been removed by pre-treatment. The main removal of treatment mechanisms are biological conversion, physical filtration and chemical absorption. The PGF is made of planted filter bodies consisting of graded gravel. The bottom slope is 1% and the flow direction is mainly horizontal. The main plants used in this filter bed are; *Canna indica*, *Reed juncus*, *Papyrus*, *Phragmites* and *Arundo donax*. The plant selection is mainly based on their ability to grow on waste water and have their roots go deep and spread wide. Plants transport oxygen via their roots into the ground. However, in the present DEWATS design the use of plants is only to act as catalysts rather than actually be a treatment medium. BOD removal ranges between 75-90% efficiency on the other hand pathogen removal efficiency is over 95%. The operation and maintenance of the system are simple and spatial requirements for construction are compensated through beautifying landscapes.

2.6.2.6 Sludge Drying Bed (SDB)

This unit is designed for storage and drying of dislodged sludge after 3-6 months from the Biogas Settler, the sludge drying is mainly by using solar energy which kills pathogens. Sludge can then be used as compost in agricultural fields to grow various crops especially bananas.

2.7 Sludge loading intensity

There is a wide range of sludge loadings and intervals of reed beds according to previous researches, when operated with septage and pit latrine sludge. Maximal sludge loading rate of 250kg DM per m² and per years are recommended for septage, meaning sludge from septic tanks have a fairly good degree of stabilization. For this project with a mixture of sludge coming from septic tanks and lined and un-lined pit latrines, the receiving sludge is considered as partly anaerobic.

2.8 Health and Safety

The proponent is committed to protect the health and safety of its employees and those of its contractors, to ensuring that activities are conducted in a manner that protects the environment and people. The Contractor shall provide and enforce the use of appropriate personal protective equipment for all workers e.g. overalls, gloves, masks, etc. (wherever required). Tanzanian/international construction standards will be followed for quality and safety to workers. First aid facility will be installed at the construction site.

2.9 Proposed Processing steps

The treatment process of the proposed facility follows the cross-section flow diagram in figure 5 from the influents to the effluent.




Figure 4: The Fecal Sludge Treatment Facility cross-section diagram

2.10 Project requirements and waste generation

2.9.1 Project requirements

2.9.1.1 Construction materials and labour force

The main materials for Faecal Sludge Treatment Plant include cement, aggregates (stones), water, steel, sand, timbers, blocks, uPVC pipes, IPS Pipes and gravels. All materials are available in the local sources in Tanzania. The estimated quantities of the materials to be included in the BoQ.

In addition to that, material such as stone and gravels can be acquired from registered dealers such as M/S Even Enterprises Company Limited who has a license to mine at Lugoba area in Bagamoyo District, Appendix VIII.

2.9.1.2 Labour force

The labour force will be determined by the Contractor; nevertheless, it is projected that during the construction phase the project will require not less than 50 workers both skilled and non-skilled laborers for each phase of project construction.

2.9.1.3 Machinery and Equipment

The proposed project development will employ various standard construction equipment and machinery. Equipment expected to be used during the construction works are Excavators, Tippers, Concrete Mixers, poker vibrators, Wheel barrow, Compactor, etc. All equipment and machineries for construction works needed by the proposed project will be determined when the bill of quantities (BoQ) and selection of Contractor is finalized. These equipments shall be temporary and shall be demobilized once project is completed.

2.9.2 Wastes generation

The major wastes generation associated with the project are spoil soils resulting from earthworks during the foundation excavations, solid wastes and liquid waste. The spoil soil shall be stock piled around the public toilet for further use in landscaping the site at the end of the project.

2.9.2.1 Liquid waste management

A total of 50m³ per day of liquid waste is estimated to be received at the receiving chamber of the proposed facility during the maximum operation phase. The project operations will conform to the National Effluent Standard of Tanzania with regard to waste water produced by the plant. After the treatment process is done, the effluent which is rich in nutrients is expected to cater for irrigation taking the advantage of the ongoing agriculture fields adjacent to the project site. However, in case the nutritious effluent will not be used for irrigation, there is a possibility of discharging direct to the river within the marsh which drains to Indian Ocean. The site is about 65m from the River Ng'ombe before discharge all relevant authorities will be consulted by the operator.

2.9.2.2 Solid waste management

About 0.5-1 tonnes per month of domestic refuse and other solid wastes is estimated to be generated and trapped at the garbage screen during the project construction and operation phase respectively. A well-established solid waste collection system will be instituted. The system will involve among other things wastes segregation at source, recycling or reuse of some wastes and final disposal to the approved city/municipal dumpsite.

The project management team will provide waste bins and recycling receptacles of different type to enable sorting. Compostable materials will be sent direct to the city dumpsite area. Table 2 below shows solid and liquid waste wastes to be generated by the project and the methods of their disposal.

Table 3: Management of construction and operation wastes

Solid waste			
Type of waste	Sources	Estimated Quantity (Kg)	Disposal / Management procedure
Debris and Rubble (overburden)	Site clearance	3,000-5,000	Fill material for road potholes, etc.
Biodegradable materials mainly domestic waste	- Construction crew i.e. Masonry,		Accessible litter bins within the camp site and later to the city waste disposal

(food, paper, wood etc.)	Carpentry & Painting	(50-100Kg) per Month	system (engage a registered private company), Final disposal will be at Municipal dumpsite
Non-biodegradable materials (plastic, glass)	- Construction crew ie Masonry, Carpentry & Painting	(2-5) kg per day	Recycling/ reuse (Plastics to be sent to authorised plastic recyclers and glass bottles and scrape to be sent to the recyclers)
Hazardous waste, Scrap metals	- Worn out Machinery parts and other metal cuttings, oil, etc	(10-15kg) per day	Sold to authorised Scrap metal and waste oil dealers respectively.
Liquid waste			
Type of waste	Sources	Estimated Quantity (m³) per day	Disposal / Management procedure
- Excreta (domestic) human - Grey water /cleaners	- Toilets and floor cleaning	1.6	Use of septic tanks and when full will empty to the wastewater treatment facility
- Oils and greases	Machinery parts and trucks	- None	- Car maintenance will be done at proper garages

3.0 POLICIES, LEGISLATION AND INSTITUTIONAL ASPECT

According to the fundamental principles of environment, any developmental activities of this nature such as construction of Public Toilet would have socio-economic and somehow environmental impacts that must be addressed and governed in order to serve public interest and sustainable development. Given the many existing and developing environmental laws, regulations and standards in Tanzania, it is worth considering resorting to constitutional provisions to protect and manage the environment. With increasing environmental awareness in recent decades, the environment has become a higher political priority and many constitutions now expressly guarantee a 'right to a healthy environment', as well as the procedural rights necessary to implement and enforce the substantive rights granted. The public or national interest in this aspect is addressed through government Policies and regulated by Principal Acts and Regulations. The implementation of the proposed project shall touch various sectors; therefore, the developer has to comply with number of cross-sectorial policies and legislations relevant to this project. Also, the listed institutions involved in environmental management for the project is included in this chapter.

3.1 RELEVANT POLICIES

This section focuses on various policies which guide the development aspects for sustainable vision, apart from the national environmental policy, there are numbers of sector policies that are to be reviewed when executing the proposed development and these include;

3.1.1 National Environment Policy 2021

The National Environmental Policy of 2021 has just been launched in February 2021. The new policy formulation is a revision of the National Environmental Policy of 1997. The Policy serves as a national framework for planning and sustainable management of the environment in a coordinated, holistic and adaptive approach taking into consideration the prevailing and emerging environmental challenges as well as national and international development issues. Effective implementation of this policy requires mainstreaming of

environmental issues at all levels, strengthening institutional governance, and public participation in environmental management regimes. The long-term vision of this policy is geared towards the realization of environmental integrity, assurance of food security, poverty alleviation, and increased contribution of the environmental resources to the national economy. It also recommends strong institutional and governance measures to support the achievement of the desired objectives and goals.

The policy seeks to promote the economy and livelihoods of people while promoting sustainable utilization of natural resources in the country. The policy provides the framework for the formulation of plans, programmes, and guidelines for the achievement of sustainable development.

The policy overall objective is to provide a national framework for guiding harmonized and coordinated environmental management for the improvement of the welfare of present and future generations. The specific objectives are i) to strengthen coordination of environmental management in sectors at all levels; ii) to enhance environmentally sound management of land resources for socioeconomic development; iii) to promote environmental management of water sources; iv) to strengthen conservation of wildlife habitats and biodiversity; v) to enhance conservation of forest ecosystems for sustainable provision of environmental goods and services; vi) to manage pollution for the safe and healthy environment; vii) to strengthen the national capacity for addressing climate change impacts; viii) to enhance conservation of aquatic system for the sustained natural ecosystem; ix) to ensure safety at all levels of application of modern biotechnology; x) to promote gender consideration in environmental management; xi) to promote good governance in environmental management at all levels; and xii) to ensure predictable, accessible, adequate and sustainable financial resources for environmental management.

3.1.2 National Land Policy of 1997

The National Land Policy states that “the overall aim of a National Land Policy is to promote and ensure a secure land tenure system, to encourage the optimal use of land resources, and to facilitate broad-based social and economic

development without upsetting or endangering the ecological balance of the environment". This study partly responds to this requirement.

3.1.3 Construction Industry Policy (2003)

Among the major objectives of the policy, which supports a sustainable building development sector, include the promotion and application of cost effective and innovative technologies and practices to support socio-economic development activities such as sanitation, water supply, buildings, road-works, shelter delivery and income generating activities and to ensure application of practices, technologies and products which are not harmful to either the environment or human health. Proposed project is in-line with this policy as ultra-modern technology is used during construction and its operation.

3.1.4 National Health Policy (2003)

The Health Policy is a vital guide towards health development of any country. It is particularly, important in a country like ours where resources and technology are more limited than in other countries, which are relatively better off in both technology and resources. This Policy is a revision of the 1990 Health Policy, which emphasized on the need for increasing community involvement in health development and improved access and equity in health and health services.

The Policy recognizes the challenges of consolidating the principles of the previous health policy in community involvement, improved health services provision, access and equity while addressing the different dimensions of reforms that are taking place in the Public Sector.

The proposed project will adhere to policy requirements to ensure no transmission of such communicable diseases between construction workers and the community, protect workers from all sorts of health risks and hazards; and provide adequate sanitation services within the project and ensure that its activities are not a source of health issues.

3.1.5 National Gender Policy of 2000

The overall objective of the Gender and Development Policy is to promote gender equality and equal participation of men and women through facilitation

of access to education, child care, and employment and decision making. Also this policy is to provide guidelines that will ensure that gender-sensitive plans and strategies are developed in all sectors and institutions. While the policy aims at establishing strategies to eradicate poverty, it emphasizes gender quality and equal opportunity of both men and women to participate in development undertakings and to value the role played by each member of society. The proposed project will adhere the requirements addressed under this policy.

3.1.6 National Human Settlements Development Policy (2000)

Among the objectives of this policy is to improve the level of the provision of infrastructure and social services for the development of sustainable human settlements and to make serviced land available for shelter to all sections of the community. Such infrastructure and services constitute the backbone of urban/rural economic activities. Public Toilet is one among of the important infrastructure for Kampochea market, Charambe ward community and country at large

3.2 PRINCIPAL LEGISLATIONS AND REGULATIONS

The ESIA team reviewed several legislations relevant to the construction of public toilets. These encompass Principal Acts that support and provide guidelines to implement the intended project as discussed below.

3.2.1 Environmental Management Act (2004)

Among the major purposes of the EMA are to provide the legal and institutional framework for sustainable management of the environment in Tanzania; to outline principles for management, impact and risk assessment, the prevention and control of pollution, waste management, environmental quality standards, public participation, compliance, and enforcement; to provide the basis for the implementation of international instruments on the environment; to provide for the implementation of the National Environmental Policy; to provide for the establishment of the National Environmental Fund and to provide for other related matters.

Part III, Section 15(a) states that "*in matters about the environment, the Director of Environment shall coordinate various environment management activities being undertaken by other agencies to promote the integration of environmental considerations into development policies, plans, programs, strategies projects and undertake strategic environmental assessments to ensure the proper management and rational utilization of environmental resources on a sustainable basis for the improvement of the quality of human life in Tanzania*".

Part X of the law deals with Environmental Quality Standards. Section 140 of this act states that "*The National Environmental Standards Committee of the Tanzania Bureau of Standards established under the Tanzania Bureau of Standards Act, 1975 shall develop, review and submit to the Minister proposal for environmental standards and criteria concerning; water quality; discharge of effluent into the water; air quality; control of noise and vibration pollution; sub-sonic vibrations; soil quality, control of noxious smells; light pollution; and any other environmental quality standard*" Some of these standards have already been published in the government *gazette* while others are not in place. This project shall consider all the standards specified by this act.

3.2.2 The Environmental Management (Fees and Charges) Regulations, 2021

These Regulations shall apply in relation to an act or service in respect of which fees and charges are payable under the Act and Regulations made thereunder. The regulations emphasize that "a person shall not, upon payment of fees and charges prescribed in the Schedule to these Regulations, carry on any of the following":

- Environmental Impact Assessment;
- Environmental Compliance Monitoring and Audit;
- Registration of Environmental Experts;
- Environmental Quality Standards;
- Noise and Vibrations; or
- other activities related to the environment

This project complies with the regulations since the proponent has already paid registration fees and review charges as directed by NEMC.

3.2.3 The Environmental Management (Control of hazardous Waste) regulations, 2021

The objective of these regulations is to protect the environment and human health by preventing or reducing the generation of Hazardous waste, the adverse impacts of the generation and management of hazardous waste and by reducing overall impacts of resource use and improving the efficiency of such use, which are crucial for the transition to a circular economy. The regulation requires that “any person generating, collecting, storing, transporting, treating, recycling, reusing, recovering and disposing of hazardous waste or any person exercising jurisdiction under these Regulations shall, assure that there are no adverse impacts to be generated or caused by the activity conducted. Project developer will comply with the requirements of this regulation by reducing the construction materials which may generate hazardous impacts, as well as proper handling of such waste such as in use of fuels for various purposes etc.

3.2.4 The Environmental Management (Control of Noise and vibration) regulations, 2015

The regulations focus on the maintenance of a healthy environment for all the people in Mainland Tanzania, the tranquility of their surrounding and their psychological well-being by regulating noise and vibration levels to prescribe the maximum permissible noise and vibration levels from a facility or activity to which a person may be exposed. The project developer will make sure that all the guidelines under this policy will be considered to ensure the healthy environment to everyone.

3.2.5 The Environmental Management (Prohibition of Plastic Carrier bags) regulations, 2019

Regulations are meant to impose a total ban on the import, export, manufacturing, sale, and use of plastic carrier bags regardless of their thickness. Plastic carrier bags has a wide definition in the Regulations, as a bag

made of plastic film, with or without handles, or gussets and to which its layer is in any thickness. The Regulations also categorically state that no person shall sell or offer for sale beverages or other commodities wrapped in plastics unless the nature of such commodities require wrappings by plastics, and restricts any licensing authority from issuing any licenses after the Regulations come into force. Project developer will make sure that there will be no use of plastic bags within the project site and the whole project life time, also in case of the need of carrier bags the proponent will make sure that there will be an alternative bags which are allowed by the regulations. For the commodities that are wrapped in plastic, then the proponent will make sure that such plastic will be handled properly.

3.2.6 The Environmental Management (Solid Waste Management) regulations, 2007

The solid waste management regulation of 2007, provides general directive on management of solid waste as follows: -

Regulation detail the requirements and responsibilities for managing solid waste in Tanzania

Highlight waste minimization and cleaner production principles alongside the duty to safeguard the public health and the environment from adverse effects of solid waste. Detail permitting requirements, notably that any person dealing with solid waste as collector, transporter, waste depositor or manager of a transfer station will apply to the LGA for a permit. The local authority will also issue licenses to individuals or companies qualified to operate solid waste disposal sites; permit is required to operate an LGA waste disposal site. The proposed project is expected to generate solid waste in construction phase. Therefore, to comply with this regulation the Project developer will engage the registered solid waste collection contractor.

3.2.7 The Environmental Management (Water Quality) regulations, 2009

Regulations provide for institutional and legal framework for sustainable management and development of water resources; to outline principles for water resources management; to provide for the prevention and control of water

pollution; to provide for participation of stakeholders and the general public in implementation of the National Water Policy. These regulations require the sustainable management of water sources and proper use of the available sources without causing any damage towards such sources. Also, the regulations emphasize that it is every one's responsibility to conserve and preserve the available water sources in Tanzania. During all phases of the project there will be water demand, hence the project developer will make sure that there will be a sustainable use of water. Also during construction and maintenance phase the developer will make sure that the water supply pipes will not be damaged in either ways

3.2.8 The Environmental Management (Air Quality) regulations, 2009

The Regulations were formed in order to: -

- Prohibit emissions and releases of hazardous substances into the environment
- Prescribe permissible emission limits and quantities of emissions of sulphur oxide, carbon monoxide, black smoke and suspended particulate matters, nitrogen oxide, ozone, hydrocarbons, dust and lead
- Empower NEMC to issue air pollutant emission permits, enforce compliance, undertake emergency prevention and issue stop orders
- Set baseline parameters on air quality and emissions based on a number of practical considerations and acceptable limits and ensure protection of human health and the environment from various sources of pollution.

The proposed project will adhere the requirements of this Act, emission limits will be monitored to the permissible limits.

3.2.9 The Environmental Management (Soil Quality) regulations, 2009

These Regulations, made by the Minister of State under sections 143, 144 and 230 of the Environmental Management Act, concern soil pollution and soil quality standards and provide with respect to a soil protection permit and compliance system. They also concern measures of enforcement. The object of these Regulations is to

- Set limits for soil contaminants in agriculture and habitat;

- Enforce minimum soil quality standards prescribed by the National Environmental Standards Committee.

Also, the regulations require that, the contaminants of volatile organic compounds in habitat and agricultural soils shall comply with parameters and upper limits as prescribed and contaminants of heavy metals in habitat; agricultural soils shall comply with parameters and upper limits as prescribed and contaminants of pesticides in habitat and agricultural soils shall comply with parameters and upper limits as prescribed. Local government authority may prescribe special or specific measures and guidelines for soil conservation applicable to their respective areas of jurisdictions which are not below standards prescribed under these Regulations. The Project developer will comply with the requirements made under these regulations.

3.2.10 Occupational Health and Safety Act 2003

The provisions of this law require employers to provide decent working environment to employees to guarantee their health and safety. Occupational health and safety services are important for sustainable development of a country, as they reduce occupational accidents and diseases which can have huge economic burden to individuals, enterprises and the nation as whole. Improving health and safety of workers will significantly increase productivity at the workplaces to encourage more investments, increase job creation, higher morale, and job satisfaction hence industrial harmony. The law also entails employers to fulfil obligations of ensuring safety of the equipment's used by workers and providing proper safety gears as required.

3.2.11 The Water Supply and Sanitation Act No. 12 of 2009

This is also a new legislation that provides for sustainable management and adequate operation and transparent regulation of water supply and sanitation services; provides for establishment of water supply and sanitation authorities as well as community owned water supply organizations; and provides for appointment for service providers. The main aim of this law is to ensure the right of every Tanzanian to have access to efficient, effective and sustainable water supply and sanitation services for all purposes by taking into account

among others protection and conservation of water resources and development and promotion of public health and sanitation; and protection of the interest of customers. Under this law, the Minister responsible for water affairs shall establish water authority and cluster water authorities in order to achieve commercial viabilities.

3.12 Engineers Registration Act and its Amendments 1997 and 2007

The Acts regulate the engineering practice in Tanzania by registering engineers and monitoring their conduct. It establishes the Engineering Registration Board (ERB), the law requires any local or foreigner engineer to register with ERB before practicing in the country. Project developer will continue to comply as it has utilized the services of registered engineering firm for its structural designs which it will continue to use to supervise the construction process.

3.2.13 The Contractors Registration (Amendment) Act, 2008

The Contractors Registration Act requires contractors to be registered by the Contractors Board (CRB) before engaging in practice. It requires foreign contractors to be registered by the Board before gaining contracts in Tanzania. Project Developer shall comply with the law requirement during the recruitment of contractors for project implementation.

3.2.14 The Architects and Quantity Surveyors Act (1997)

The Act requires Architects and Quantity Surveyors to be involved in the project to be registered by the Architects and Quantity Surveyor Board (AQSB) before engaging in practice. It also requires foreign contractors to be registered by the Board before gaining contracts in Tanzania. Project Developer has complied with the law requirement during the recruitment of architects who have designed the project and will continue to utilize registered persons in the project implementation.

3.2.15 The Urban Planning Act (2007)

The law provides for the orderly and sustainable development of land in urban areas, to preserve and improve amenities; to provide for the grant of consent to develop land and powers of control over the use of land and to provide for

other related matters. Under Section 3, among others the law seeks to improve level of the provision of infrastructure and social services for sustainable human settlement development. This act established planning authorities which include the city, municipal, town and township councils in the country which have responsibilities including:

- Secure the orderly and environmentally sustainable development of area under its jurisdiction;
- Prepare general and detailed planning schemes;
- Control building densities and access to buildings;
- Recommending approval of building schemes and subdivision of plots by developers;
- Secure cooperation of all agencies, utility bodies, land owners and other bodies and institutions involved in the preparation and implementation of planning process;

3.2.16 Public Health Act (2009)

Provide for the promotion, preservation, maintenance of public health with a view to ensuring the provisions of comprehensive, functional and sustainable public health services to the general public. Part III (e) of the act requires premises owners to keep their premises free of mosquitoes and other disease vectors, vermin or causative agents; Section 54 prohibits causing or suffering from nuisance likely to be injurious or dangerous to health, land, premises, air or water; Part IV (c) assigns responsibility to City council to remove or appoint an agent to collect, transport and dispose solid and liquid waste and charge fees to beneficiaries of this service and responsibilities for prescribing types of wastes and guidelines for their collection and disposal; Section 101 it gives rights to any private sewer to connect it to any available public sewer to discharge foul or storm water therefore the project may connect to and discharge sewage or storm water into the available trunk main. However, the quality of the sewage should be as per agreed with the water authority.

The Contracting Authority will ensure that the project design, construction and operation does not constitute a nuisance; meets the requirements meets public health requirements

3.2.17 World Bank guidelines for Environmental Management

The main objective of this EMP is to establish a set of mitigation and monitoring measures to minimize the adverse social and environmental impacts that can take place during the implementation stage of the subproject. The measures especially focus on sensitive receptors or sensitive locations. The EMP also provides specific information about the monitoring program during construction stage including locations, frequency and reporting process. This project complies with these guidelines as it has ESMP which contains mitigation and monitoring plans of the identified impacts.

4.0 BASELINE INFORMATION

4.1 INTRODUCTION

This section provides baseline data on the relevant environmental characteristics of the project area. Much of the description of the environment is site specific. Other aspects such as that of climate and socio-economic issues are broad covering the whole Kigamboni District. The Consultant relied on primary data as collected from the site as well as secondary data and information gleaned from the literature for the project area.

4.2 PHYSICAL CHARACTERISTICS

4.2.1 Climate

The project area as compared to many other areas in Dar es Salaam city is influenced by coastal climatic conditions. The area experiences a modified type of equatorial climate.

➤ **Temperature, Sun hours and Radiation**

The region is generally hot and humid throughout the year with an average temperature of 29°C. The hottest season is from October to March during which temperatures can raise up to 31°C. It is relatively cool between July to September, with temperature around 20°C. The maximum sun hours is 9 experienced from August to October, from November to January the sun hours

is 8 while in February to March and May to July is 7 hours and the minimum is 5 hours in April. That means from October to March the operation in the project site will probably need more electricity for the purposes of culling at the office, while during coolest monthlies which is from July to September the consumption might go down see figure 4.1




Figure 4.1: Annual temperature, sun hours and radiation of the site (Kigamboni Municipal Profile, 2019)

The average radiation of an area is 20.3 MJ/m²/day, with 16.3 MJ/m²/day being the minimum in April and 23.7 MJ/m²/day maximum in October.

➤ **Wind Speed**

The region experiences the average wind speed of 5.74 m/s. The maximum wind speed is 7.63 m/s experienced in June which blows from the South South East (SSE) direction which means if the project site will produce and air pollutant all activities downstream of SSE direction will be prone to that pollution. The wind is calm around December to March. The climate is also influenced by the south-westerly monsoon winds from April to October and north-westerly monsoon winds between November and March.

➤ **Rainfall**

There are two main rain seasons; a short rain season from October to December and a long rain season between March and May. Figure 3.4 shows the effective rainfall received at Dar es Salaam region.




Figure 4.2: Average annual rainfall data for the site (Source Socio-Economic profile 2019)

4.2.2 Groundwater sources

Groundwater is abundant in almost the entire Dar es salaam City. This is because of the sea level rise. The major direct impacts of sea-level rise include inundation of low-lying areas, loss of coastal wetlands, increased rates of shoreline erosion, saltwater intrusion and increased salinity in estuaries and coastal aquifers, and higher water tables and higher extreme water levels leading to coastal flooding (Nicholls et al., 2007; Bicknell et al., 2009).

4.2.3 Topography

The landscape of the project site is highly manipulated to make the topography flat and suitable for storage activities. The highest contour elevation at the project site is 96.5m Above Mean Sea Level (AMSL) on the western side while the lowest contour elevation is 94m AMSL at eastern part of the project site, that means the rainfall runoff at the project site are directed towards southern eastern side.

4.2.4 Air Quality and Noise Level

The ambient air quality at the project area was observed to be good because the area is for residential purposes only, just because of daily activities there will be particulate matter like dust.

4.2.5 Noise and Vibration

The noise and vibration levels at the project site are rated negligible as the only source of noise at the project site are motor vehicles using the street feeder road adjacent to the project area..During construction phase the constructor shall abide to national standards of 75dBA for an average noise level and 5mm/s PPV for ground vibration at all times.

4.4.8 Water Table and water quality analysis

Groundwater is abundant in almost the entire Dar es salaam City. While there is no permanent surface water sources in the vicinity of the proposed site for FSTP, groundwater resources is of concern. Groundwater is abundant in almost the entire city of Dar es Salaam. Data for Water quality from the project site were as presented in figure 4-1 and 4-1. However, the engineering design of the facility has taken on board all factors to ensure no contamination of groundwater is likely to occur.



Figure 4.1 Water quality test results (Source Design Report 2021)

UNIVERSITY OF DAR ES SALAAM
COLLEGE OF ENGINEERING AND TECHNOLOGY
DEPARTMENT OF WATER RESOURCES ENGINEERING
P.O. BOX 3524 - DAR ES SALAAM - TANZANIA

General Tel: (+255 22) 2111111-6, 511-799
Fax: (+255 22) 2111111-6, 511-799
E-mail: info@uod.ac.tz



E-mail: info@uod.ac.tz
Website: www.uod.ac.tz

Our Ref: WRE/WQ/18/2021

Date: 27th August, 2021

WASTE WATER QUALITY TEST RESULTS

PROJECT NAME: DOWASA OFF GRID SANITATION PROJECT IN DAR ES SALAAM
CLIENT: DOWWA ENGINEERING COMPANY LIMITED

Table 1: Summary of Physical, Chemical and Bacteriological Analyses of Waste Water samples tested.

S/N	PARAMETERS	UNITS	VALUE ATTAINED				
			KINIST-01	USOM-01	TMDM-01	ILIST-01	S.OM-01
1	pH	-	7.1	7.3	7.5	7.5	6.9
2	Temperature	°C	28.7	28.0	31.5	29.7	30.2
3	EC/Conductivity	uS/cm	5500	1800	4900	3430	2800
4	Total Dissolved Solids	mg/l	2800	700	2510	1720	1440
5	Total Suspended Solids (TSS)	mg/l	450	1770	2200	400	2900
6	Total Solids	mg/l	2810	3180	2502	1860	6750
7	Total Volatile Solids	% of TSS	35	66	70	33	50
8	BOD ₅	mg/l	700	3400	4700	600	4700
9	COD	mg/l	2800	11100	10700	3000	9600
10	Nitrate (NO ₃ -N)	mg/l	146	105	220	54	243
11	Ammonia (NH ₄ -N)	mg/l	115	70	117	39	455
12	Phosphate (PO ₄ -P)	mg/l	88	233	220	263	180
13	Fecal coli form	No/100ml	1.0×10^4	3.0×10^1	2.0×10^1	1.4×10^0	2.0×10^1
14	Total Coli form	No/100ml	1.5×10^7	9.0×10^1	1.5×10^1	2.3×10^0	1.8×10^1
15	Lead (Pb)	mg/l	0.02	1.70	1.00	1.50	0.86
16	Cadmium (Cd)	mg/l	0.017	0.026	0.029	0.037	0.017
17	Chromium (Cr)	mg/l	3.60	1.73	0.88	2.54	7.06
18	Nickel (Ni)	mg/l	0.80	0.60	0.36	0.83	0.34

Signed by: 
 E. Mwangi
 Water Quality Laboratory

Date: 27th August 2021



Figure 4.2 Water quality test results (Source Design Report 2021)

5.0 STAKEHOLDER VIEW ON THE PROPOSED PROJECT

During the conduction of this study, different stakeholders were consulted. Among these include the Kigamboni Municipal Council and the community at Golani (see Figure 5). Consultations were made through meetings.



Figure 5: Stakeholder's consultation meeting at Golani (Kimbiji Ward) and Kigamboni Municipal Council office (Source: Fieldwork August 24th 2022)

During the meeting, the consultant gave a brief explanation on the proposed Faecal sludge treatment Plant. The project description covered proposed location, type and design of the plant (a typical design was displayed). The stakeholders were given chance give their views on the project. Moreover, the consultant offered chance to clarify issues where stakeholders wanted to be given more explanations. The comments by stakeholders were analyzed and incorporated in the design of mitigation measures. Table 5 summarizes the issues raised. The names of the stakeholders consulted are given in Appendix II.

Table 5-1: Stakeholders issues and concerns

Institution	Name	Position	Issues/ concerns
Golani Street (Kimbiji Ward)	1. Tabitha Yohana Lindoya	MEO	<ul style="list-style-type: none"> ○ Agreed with the project implementation and Insisted on timely implementation of the project rather than waiting for so long until the local government leadership is changed, then everything stacks with new leadership possibly unaware of the previous endeavours. ○ After cleaning the site, trees that will be cut should at least be distributed to residents. ○ During the implementation stage: Local Government leadership should closely be involved during the supervision ○ All stated mitigation measures should be implemented to avoid complaints from residents
Kigamboni Municipal Council – Environmental and Solid Waste Management Department	<ol style="list-style-type: none"> 1. Juvenalis Mauna 2. Theresia C. Sikanyi 3. Tabu Abasi 4. Jenifa Kilegu 5. Amina Adamu 6. Hussein H. Mhoma 7. Jocelyne I. Tutindaga 8. Mathayo J. Mgimwa 9. Rehema A. John 10. Witness M. Mathayo 11. Shadrack G. Mushi 12. Mfuko Fatuma 13. Asha N. Magumbo 14. John M. Suleiman 15. Furaha A. Mchayungu 	EMOs	<ul style="list-style-type: none"> ○ Consultation to create awareness among residents of Golani should be done especially during this design stage. ○ During all consultations/meetings, minutes should be prepared accordingly ○ Before consultation of residents; representatives of Golani (Residents and Local leaders) should be facilitated to visit other pilot FSTPs located within the city for familiarization with the technology, then they'll become good ambassadors to the rest of the community. ○ Air quality data of the present condition before implementations should be acquired to establish a baseline and avoid complaints in future ○ During the Operational stage, there must be clear supervision of Cesspit emptiers, Because it is likely Industrial wastewater to be brought to the facility unknowingly which will result in the malfunction of the facility.

6.0 POTENTIAL IMPACTS

6.1 Positive impacts

6.1.1 Improved living conditions and economic growth

The project will improve the living conditions in Kigamboni Municipal and Dar es Salaam at large, particularly Kimbiji residents whereby the project operation phase will do away with illegal fecal sludge dislodging especially during the rainy season or the night. The charged fee for emptying septic tanks and pit latrines will be such as affordable to the intended customer. Thus, there will be increased money circulation that results in increased income and consequently a better standard of living for people in the project area.

6.1.2 Employment opportunities

The Labour force for the project will be originated from Golani and the surrounding communities in the Kimbiji ward. Even though during construction the employment will be on a short-term basis, employees will have been benefiting from the project. Some will witness their incomes and livelihood improvement.

6.1.3 Increased Revenue to the nation through taxes, both direct and indirect

DAWASA is expected to increase government revenue collection at Municipal Council and the National level. This will be enhanced by time-to-time payment of all charges to dislodge septic tanks and pit latrines of the respective household. The revenue collected will contribute towards economic development within the municipal and the country at large.

6.1.4 Biogas production potential

Among other positive impacts, gas production for domestic uses is anticipated to serve the local communities and institutions. In this case, the residents which

are in proximity to the project site will be the immediate beneficiary of the produced biogas.

6.1.5 Minimized forest products harvesting

The Source of energy for cooking in most households originates from forest products. Charcoal and firewood are the most commonly used for domestic purposes. The biogas production from the plant will minimize the use of forest products as to why the gas will be availed to the local community. However, the quantity of the biogas produced depends on the quality of the influent on the facility.

6.1.6 Cost reduction for sewage management

The proposed facility will make it easier for the Institutions and households that at present incur unbearable costs for proper dislodging of the septic tanks when full. That simply means the households in the vicinity and the institutions will benefit through a direct connection to the treatment facility depending on the nature of the topography.

6.2 Negative impacts

6.2.1 Increased HIV/AIDS and other sexual-related diseases:

Local communities surrounding the project area have to be aware of the fact that HIV/AIDS is present in their areas but accede to it not being at an alarming rate. The communities were worried that with an influx of people into the project area the pace of spread will accelerate especially during the construction phase.

Mitigation Measures

- The contractor shall enforce a code of conduct in the project area to encourage respect for the local community and to maintain the self-cleanliness of the working area at all times.
- The contractor shall deploy locally available labor to reduce the risk of spreading communicable diseases (especially STDs).

- To prevent more HIV/AIDS infections, during the implementation phase, the project should include an information education and communication component (IEC) in its budget. This will help to raise more awareness of HIV/AIDS and means to suppress its incidence.
- A safety, health, and environment induction course shall be conducted for all workers, putting more emphasis on HIV/AIDS, which has become a national disaster.

6.2.2 Loss of biodiversity

Loss of biodiversity will be experienced during the site clearance for the construction activities to start. Huge biomass will be cleared that may include important and rare species. Among the species of trees that will be cleared at the site includes the *Eucalyptus* plant and *Trachycarpus fortune*.

Mitigation Measures

- Close supervision of earthworks shall be observed to confine land clearance within the area where the construction activities are to take place.

6.2.3 Land degradation and increased erosion

The establishment of a new facility within the project area might result in land degradation and promote soil erosion. The erosion will happen as a result of the removal of *Aristida* grasses, which are currently protecting the land against erosion.

Mitigation Measures

- Unnecessary ground clearance and sensitive re-alignments shall be avoided.
- Lined drainage channels at sensitive terrains shall be provided to control the speed and volumes of storm water.
- The contractor should plant grass or any other vegetation cover to minimize exposed soil surface.
- Directing flow to properly designated channels within the facility site.

6.2.4 Noise pollution

Noise pollution is likely to occur due to the application of construction equipment and generators at the site.

Mitigation Measure

- The proponent shall maintain equipment in good running conditions to ensure that ambient noise level and vibrations pollution into the environment is very minimum to comply with Tanzania standards
- The noisy construction activities will be scheduled at normal working hours. Regular inspection and maintenance of construction vehicles and equipment will be done to ensure that they have mufflers installed and worn parts are replaced

6.2.5 Air Pollution from dust emission

Air pollution is likely to occur due to the emission of suspended particulate matter (dust) into the atmosphere from construction activities.

Mitigation Measure

- Mixing equipment shall be sealed properly and vibrating equipment will be equipped with dust-removing devices.
- Also, all vehicles that generate excessive black smoke will not be used.
- Adequate training and use of personal protective equipment (PPE) such as eyeglasses and dust masks will be ensured to reduce risks associated with dust.

6.2.6 High Risk of Health associated with construction work

Construction activities expose the workers to a lot of risks for example risk of falling into the excavated pits more than 3 meters deep, the risk of injuries from falling objects or sharp pointed objects, etc.

Mitigation measure

- The project proponent shall ensure that all personnel is provided with appropriate protective gear.

- All works shall be planned and conducted following relevant OHS Guidelines. First Aid Kit as well as regular medical check-ups for the workers will be provided during the entire working hours.
- An adequate number of firefighting equipment/extinguishers will be provided every few distances to help put off fire in case of occurrence.
- Excavated pits should be protected by warning tape and guardrails to prevent workers from falling

6.2.7 Waste generation during construction

A lot of waste will be generated especially during the construction stage. For example, excavation of foundations will generate a lot of spoil materials that will need to be disposed of. The construction of walls and roof will both generate waste. Other wastes will be generated from cleaning construction equipment and containers like mixers and paint buckets.

Mitigation measures:

- Stick to the design specifications
- Provide waste containers
- Provide training to workers and orient them towards environmental protection values

7.0 ACTION PLAN FOR HEALTH AND SAFETY OF WORKERS AND COMMUNITY DURING THE IMPLEMENTATION STAGE

7.1 General

The project shall be implemented in compliance to labor laws in Tanzania, in particular, the Occupational Health and Safety Act (2003). Clauses to protect the health and safety of workers shall be included in the contract documents for implementation stage. All personnel are expected to comply fully with health and safety law and the associated approved codes of practice. Contractors are, in addition, to be aware of and pay due attention to guidance issued by the Health and Safety Executive as well as that issued by trade bodies and authorities, which constitute industry 'best practice'. Method and policy statements submitted for these works will be reviewed by the Site Project Manager and Safety Adviser to ensure that these standards are met. On such occasions that they fail to meet the standard they will be returned for amendment action.

7.2 Health and Safety Management System

7.2.1 Safety Training and Promotion

The aims of safety training programmers are:

- To update the safety awareness and technical skills of person in the field of application.
- To orient new employees to working environment.
- To identify and rectify hazards and convey the same to the workforce.
- To prepare the persons to select appropriate safety measure contain any unforeseen hazards/emergency situations.

To achieve the above aims, following types of training shall be conducted at the site level:

7.2.1.1 Health and Safety Induction Training

New or reassigned employees shall be given Health& Safety induction training pertaining to Health& Safety management and general safety rules and procedure, site specific Health& Safety rules and their responsibility and accountability in safety performance. Health& Safety induction shall be given to all categories of personnel at site by Health& Safety Manager. Health& Safety induction shall be recorded in the prescribed format. All employees shall acknowledge such training by signing relevant document.

7.2.1.2 On the Job Training

Based on the trade, individuals are given On the Job training. These trainings shall be focused on the safe ways of working in a particular trade including hazards involved. This shall be conducted by the foremen/supervisors in collaboration with Safety personnel and trainees' performance after the programme shall be assessed to evaluate the effectiveness of the training. All risk assessment and related knowledge shall be done by the Health & Safety Manager.

7.2.1.3 Refresher courses

Refresher courses shall be conducted to update the skill and safe methods of work for a particular job. This shall be conducted periodically for welding/cutting, plant and equipment operation, defensive driving and hazards in electrical installation.

7.2.1.4 Tool Box Talks

In addition to the formal training mentioned above, toolbox talks shall be conducted every day before the commencement of the job. The Faecal Sludge

Treatment Plant shall be designed to highlight relevant safety and individual health issue to the workforce to raise their level of awareness. Such meeting shall recall the risk assessment report and defects reported on previous performance. These shall be prepared and presented by the Supervisor/Foremen.

All trainings that are carried out shall be formally recorded on dated and signed by attendees and the copies shall be kept with the project safety focal point.

7.2.1.5 Safety Promotion

Safety Promotion schemes shall be developed and implemented at site to promote safety awareness amongst the workforce. Individuals with best safety performance shall be recognized and rewarded. A safety suggestion scheme shall be implemented at site to encourage the workforce to come up with good safety practices and suggestions for improving working condition. The best suggestion shall be selected and the person shall be rewarded.

Health& Safety posters and banners including HIV/AIDS shall be displayed around the worksite to raise the awareness among the workforce. The posters shall be prepared in English and Swahili languages.

7.2.2 Safety inspection and Follow up Actions

Contractor's Health& Safety Manager along with supervisory staff shall carry out frequent inspection with the focus on safety aspects at site and prepare reports of inspection. The frequency of inspection shall be determined by site activities and general conditions. However, the inspection shall be conducted at a minimum of once a week. Where high – risk activities are being carried out inspection shall be done at least once daily.

The inspection reports shall be discussed with the site managers and various sub – contractors (if any). In addition to these, the site staff will accompany the Engineer and other staff of Consultant for their site safety inspection.

Remedial action to rectify any deficiency identified or unsafe practices discovered during the safety inspection by developer shall be implemented immediately.

7.23 Reporting of Accidents, incidents & Investigation and Accident Statistics

Tanzania laws on incident reporting and investigation procedures shall be adhered. Such law requires reporting to the Chief inspector of Occupational Safety and Health Authority (OSHA) all lost time injuries (LTI) within twenty-four hours from the time of incident. Contractor will play this role to ensure that local requirements are followed. As per Contract Agreement the Contractor shall notify the Consultant and developer within 48 hours or as soon as reasonable possible after the occurrence of any accident which has resulted in damage or loss of property, disability or loss of human life, or which has or which could reasonably be foreseen to have a material impact on the environment and shall submit to the Consultant and developer no later than 28 days after the occurrence of such an event in the agreed format, a summary report thereof. All incidents including near misses shall be reported to the Consultant, regardless the potential of the incident.

All the incidents shall be investigated to find out the root causes and to prevent the recurrences of the same kind of incidents. If the consultant asks for the detailed investigation and the findings shall be submitting to the consultant. The methodology for the incident investigation shall be “Find out the facts, not the faults”.

Incident data, if properly collected and analyzed, indicates the trend and can show where and how problems arise. A monthly safety performance report of

the project shall be included in the Monthly Progress Report after the end of each month.

7.2.4 Hazard Identification and Risk Assessment

The purpose of the hazard identification and risk assessment is to identify all potential hazards and associated risks during construction. The contractor will take relevant measures to control all critical, high and moderate hazards. Low potential hazards will be totally eliminated. General risk assessment of this project has already been done and submitted to the relevant parts per Tanzania's Occupational Safety and Health Laws.

Depend on the severity of hazards we will be able to take necessary preventive and control measure to mitigate the hazards. Prior to the commencement of any activity, detailed hazard identification shall be done by the site supervisory staff with the assistance of Health & Safety Manager and the hazards shall be communicated to the whole team deemed to execute the task. The hazards analysis done shall be produced to Consultant for approval and mitigating measures shall be taken up to their satisfaction. Risk assessment shall be done per Occupational Safety and Health Act, number five of 2003.

7.2.5 Industrial Health and Hygiene

Hazards to health on a construction industry can arise from the use of a number of materials, substances and process if they are not properly controlled. Some of the more serious risks are caused by the inhalation of dust, toxic fumes, exposure to high temperature, noise, vibration, radioactive substances, ergonomic hazards etc.

DAWASA shall be responsible for maintaining health working conditions for all employees and sub – contractors. If it is not possible to remove the cause of

harm, then suitable and sufficient Personal Protective Equipment (PPE) shall be provide to those who could be affected.

7.2.6.1 Hazardous substances

Material Safety Data Sheet (MSDS) of all hazardous materials that are used on site (if any) shall be obtained. An inventory shall be kept of all such materials with the relevant MSDS and shall be available for the inspection of consultant. An assessment shall be conducted in relation to the intended usage of the hazardous substances on site and adequate precautionary and control measures shall be taken according to the assessment. Such MSDS shall be available for inspection from Tanzania Health and Safety law enforcer. An assessment shall be conducted in relation to the intended use of the hazardous substances on site and adequate precautionary and control measures shall be taken according to the assessment.

7.2.6.2 Heat

Illness due to heat comprises a wide range of problems from minor inconvenience to critical medical emergency and death. The functioning of the thermoregulatory system of the body gets upset, (balance between heat gain and heat loss), which results in the subsequent loss of salt and water. This takes the following forms like heat rashes; heat cramps; heat exhaustion and hear stroke. Following precautions shall be taken against heat stress.

- Wear light, airy clothes.
- Drink plenty of water even if you do not feel thirsty.
- Wear sunglass/balaclava while working outside.
- New employees shall give adequate time to acclimatize with the hot environment before deploying to the work site.

7.2.6.3 Dust

Dust control will be initiated prior to any activity in dusty condition. Such control will adopt but not limiting to de-dusting procedures. In case of unavoidable dust emissions, introduction of PPEs will be adopted. In any case no personnel shall be exposed directly to harmful airborne contaminants of Silica, Rust (ferrous oxide), Blasting grit, Asbestos, Glass wool & Paint solvent mist. Water sprinkling system shall be adopted to control the dust on all identification areas of the Project.

7.2.6.4 Noise

The Contractor shall comply with the applicable Tanzanian laws, orders and regulation concerning the prevention, control and abatement of excessive noise. Industrial deafness is cause by over exposure to high levels of noise from plant, machinery or construction processes. No employees shall be exposed to noise dose that exceeds 85 dB (A), unless they are wearing suitable hearing protectors, which effectively reduce the sound level at the user's level to or below 85 dB (A). Consideration shall be given first to reducing the noise level at source.

The precautionary measures for the exposure limits shall be as follows:

- 80 to 85 dB (A) – Provide hearing defends with proper training to use them.
- 85 dB (A) – Signposts shall be erected to inform all employees and public that usage of car defenders is mandatory in the area.
- 115dB (A) – No exposure to steady noise irrespective of hearing protection.
- 135 dB (A) – No exposure to impulse noise irrespective of duration of hearing protection.

7.2.6.5 Vibration

Vibration causes health hazards in two ways;

- Vibration of body parts due to hand held tools like concrete vibrator, plate compactor, jackhammer, hand drill, hand grinder etc.
- Vibration of the whole body experienced while traveling in vehicle and operating equipment like dozer, grader, roller etc.

Excess vibration will result in discomfort to the worker, which leads to a decrease in efficiency and finally causes damage to health. Vibrating equipment shall be equipped with proper handles to prevent causing any impact on the operator. Personnel shall be given intermittent rest or shall be changed and replaced frequently.

7.2.6.6 Sanitary Facilities

Adequate sanitary conveniences will be provided in strategic point of the workplace. Such conveniences are lavatories, showers, and washbasins. Such facilities shall be kept clean and in good working condition at all times. Domestic wastes shall be collected per environmental management plan and Environmental Guidelines.

7.2.6 Personal Protective Equipment (PPE)

PPE protects the employee from identified non-eliminated hazards at the site. Personal protective equipment safeguards the employee from the identified hazards so which he is exposed. PPE is the last line of defense for employee protection. PPE does not and cannot eliminate hazard, it can only prevent or reduce exposure to hazards and reduce the severity of the consequent injury.

All employees of the contractor shall be provided with necessary PPEs and ensure that the contractor and sub – contractor personnel are also properly

protected by appropriate PPE. Such provision will be free of charge. Employees shall be trained by line supervisors for the correct utilization of the PPE. Individuals shall not be allowed to work if they are not equipped with the appropriate PPE. Suitable signboards shall be kept in work area indicating the potential hazards (e.g. noise, radiation etc.) and PPE that is required to be worn in that area/for that activity, in applicable languages and visual signs. The signage will be in Kiswahili and English languages and posted in visible areas.

7.2.7 First Aid Facilities

All accidents, which involve personal injury, whether it is minor or major, shall be given medical treatment and report to concerned Supervisor. A first aid station shall be set up at the site office and a trained first aider will be in charge of the station. All injury cases, except minor injuries shall send to medical center for treatment. In case of an accident with personal injury doctors will attend such person in a prescribed hospital. Only ambulance will be allowed to transfer the casualties. Adequate number of first Aid boxes will be fixed in strategic points where employees will be notified the nearest location of the same, telephone number of Emergency control room will be also displayed. Adequate number of first Aid boxes shall be available site. There shall be one trained first aider in a group of 20 persons. First aid boxes shall be frequently inspected by the trained first aider and updated.

The Contractor shall comply with the Government medical or labour requirements at all times and provide, equipment and maintain base dressing stations where and at all times have trained first aider for attending minor injuries.

7.2.8 Fire Prevention and Fighting Facilities

Construction sites premises are very prone to fire hazards because of different kind of combustible material used in all the above places. The components of a fire are fuel (combustible substance), heat and oxygen. Unless all three are present fire will not occur. A fire hazard evaluation shall be conducted all the

project sites and camp to identify the fire risk at each location. Depend upon the risk factors fire prevention and fighting system shall be provided and maintained.

Following steps shall be taken to implement fire prevention system at our project premises.

- All the employees shall be education about the fire hazards, firefighting methods and precautionary measures specific to this project.
- Adequate number of portable fire extinguishers shall be placed at strategic locations.
- All employees shall be demonstrated the operation of portable fire extinguishers.
- Good housekeeping shall be maintained at all sites to reduce the fire risk.

7.2.9 Road safety management

This project as relies heavily on road transport. Analysis shows that road accidents contribute a major portion of total accidents in such construction projects. To avoid road accidents the following measures shall be adopted during the execution of project;

- A transport coordinator shall be appointed to control the movement of vehicles and equipment and he shall be responsible for safe and smooth deployment of fleet.
- All drivers and operators shall possess a valid Tanzania license for the types of vehicle being driven or machinery operated.
- All vehicles shall be kept in a plot with good conditions and preventive maintenance system shall be followed.
- An in-house training on defensive driving techniques and safe tipping operation shall be imparted to all drivers before allotting vehicles to them.
- The drivers shall follow all traffic rules and regulation of Tanzania.
- Over speeding shall not be allowed at any case and if observed do so disciplinary actions shall be taken against the defaulter.

- Drivers shall not allow working more than 8 hours shift period. The shift period includes loading, unloading, waiting and driving time.
- No vehicle shall be allowed to drive after consuming alcohol/drugs, some medicines, under fatigue or when sick or ill.
- Nobody is allowed to drive if under the influence of alcohol or drugs.
- Drivers shall wear necessary PPEs while driving.
- A driver forum shall be constituted and shall meet once in a month or immediately after an incident to discuss the general safety issues as well as specific learning points from incidents.
- Only one person shall direct the driver/operator
- Beware signage shall be established on public institutions' entrances

7.2.10 Traffic management plan

This project involves movement of heavy traffic both at the site and outside the Site. All drivers are instructed to strictly follow the minimum speed of 20 KPH at the site. Adequate sign boards will be placed at the relevant location and flag man will be assigned whenever necessary. Anybody found violating the traffic rules will be punished.

7.2.11 Sub-Contractors

Subcontractors are treated as integral part of the contract and subject to the same standard of treatment as that of main contractor's employees in all matters pertaining to Health& Safety. List of subcontractors shall get approved by developer (DAWASA) prior to their deployment in the project.

On arrival of Subcontractor's employees, Health& Safety Manager shall conduct induction program. Sub-contractor employees shall participate in all Health& Safety activities along with Contractor's personnel working under the Contract.

7.2.12 General Safely Rules

All personnel working at site always shall strictly follow following Health& Safety rules:

- Never take their eyes off the job, pay attention to what you are doing.
- Shall be on the lookout for hazardous conditions that could lead to an accident.
- Shall pay attention to what you are doing.
- Shall be in a continuous observation of hazardous conditions that could lead to an accident.
- Shall report all first aid injuries, lost time accidents and near misses immediately to their supervisors.
- Shall wear proper uniforms and other personal protective equipment necessary for the job that they have to do.
- Shall ensure that they have the right tools and equipment for the job.
- Check the tools condition before using it.
- Shall always use provided personal protective equipment like overall, helmet, goggles, shoes and balaclavas etc.
- Shall know the location of the nearest fire extinguisher first aid box.
- Shall always keep work place clean and tidy.
- Shall not play with fire. Smoking in 'No Smoking' area only.
- Shall not interfere with overhead electrical supplies and appliances.
- Shall observe all warning signs, labels and hazard notices.
- Shall not overtake and over speed vehicles in high traffic areas. Shall observe all speed limits and traffic controls.
- Shall not use unstable material/platform for working, climbing and standing purpose.
- Shall not abuse toilets and welfare facilities provided for their use.
- Shall always take care when lifting load. Keep straight back and bent knees
- Shall not keep any material or obstacle in access ways or exit path.
- Shall not operate cranes over or in the close proximity of power lines.
- Shall take sufficient water and fluid regularly during hot and humid weather conditions.

- Safety is everybody's responsibility.

7.3 Safety in Various Construction Activities

7.3.1 Excavation

Excavation is one of the important phases of the construction activity. Any insufficient attention to the safety aspects may cause of accident, therefore we shall take utmost care in planning and executing all excavations. The following precautionary measures shall be followed:

- The area to be excavated shall be inspected thoroughly by a competent person for any underground services or structures.
- It shall be ensured that a person having good knowledge and experience supervises all excavations.
- All mechanical excavations shall be carried out only in the presence of an authorized banks man.
- The integrity of excavation and supports shall be inspected prior to the commencement of work on daily basis.
- No soil or other materials shall be stored close to the sides of the excavation and at least 1m clearance shall be provide for storage and dumping of excavated materials.
- Edges of excavations shall be barricaded to prevent falling of persons and materials.
- If vehicular traffic is allowed near to the excavation, contractor shall provide adequate lighting, warning signs and concrete blocks painted with reflective paints.
- Excavations exceeding 1m shall be demarcated with solid barricades plus warning tapes. The rest shall be barricaded with warning tapes.
- Where there is a possibility of ingress of water then pumping sumps shall be established with pumps being readily available for use and additional ladders placed for use in the event of emergency evacuation.

- Adequate means for entry and exit shall be provided for excavations over 1.5m and it shall be either ramp or ladder.
- All the personnel engaged shall be made aware about safe digging practices, hazards in the operation and emergency procedures.
- Adequate number of strong and stable temporary crossing with handrails shall be provided for personnel.

7.3.2 Reinforcement Steel Work

Reinforcement steel work is an essential part of any construction phase. The activity involves unloading, bar bending, cutting and fixing of bars in position and people's unsafe acts. The main hazards are handling hazards, working with machinery, using of electricity, falling of material on body and taken.

- Loading and unloading of steel shall be done by proper lifting equipment lifting tackles and under proper supervision.
- All persons handling steel bars shall be provided with necessary PPE required for the job.
- The lengthy steel bars shall be stored in safe manner to avoid in tripping hazards and protruding hazards. Proper signage shall also be provided.
- Bar cutting machines and bending machines shall be in good working condition and provided with emergency stop switches and necessary guards. Both the machine shall be placed in such a way that the operation on it shall not create any danger to nearby workers.
- The electrical connections to the machine shall be done by electrician by providing appropriate circuit breakers and proper earthing after conducting risk assessment.
- Persons deployed for cutting and bending shall be trained and instructed about the job and its inherent hazards.
- The work area shall be kept clean and steel cut pieces will be kept separate.
- Adequate number of works shall be deployed to handle and fix the steel.

- The tools used for fixing the steel in place shall be inspected regularly and maintained properly.
- If the steel fixing work is at height or in an excavated pit/trench, safety measures shall be taken in accordance with the accordance with the particular procedure.

7.3.3 Concreting

This includes shuttering, formwork, de-shuttering and concreting. The main hazards are falling of objects; struck by object, falling of persons from height, crush injuries and impact injuries, ergonomic related, tripping and slipping. The following practices shall be adhered to ensure the safe operation in these activities.

- The persons deployed on work shall be given a safety induction related to the job. They shall participate in the risk assessment.
- The persons deployed on work shall have well experience and provided with all tools in good working condition.
- Handling, erection and dismantling of heavy shuttering shall be done with proper lifting equipment under close supervision.
- Required PPE shall be provided to all persons engaged in the job.
- The workers shall be informed about the hazards of the activity.
- The area shall be barricaded to prevent the entry of unauthorized persons and visitors.
- Hand tools shall be inspected on daily basis.
- There shall be effective communication between the crew members while erecting and dismantling the shuttering.
- Good housekeeping shall be maintained all over the area.
- Formwork for the concreting shall be inspected by a competent person, prior to the pouring.
- The concrete pump shall jack-up properly and park at firm and level ground.

- Two persons wearing reflective jackets shall be deployed to hold the concrete pouring pipe.
- Always look for overhead electrical cables while parking the concrete pump.
- Temporary platforms shall be provided on steel work for people to stand while working at the area.
- Tipping shall be away from overhead power lines

7.3.4 Material Handling

7.3.4.1 Mechanical Handling

Lifting equipment and lifting gears shall be inspected per Occupational Safety and Health Laws of this Country and should be used for handling of construction materials. All lifting equipment shall be checked and ensured that they are in good operating condition and free from defects. All lifting equipment and tackles shall have valid third party certificate. Inspection intervals shall be as per Tanzania laws and safety regulations. Inspection and certification shall be done from Tanzania's approved competent authority which is Occupational Safety and Health Authority (OSHA). Colour coding system for lifting equipment shall be followed. All lifting operations shall be done by experienced persons and supervised by competent persons. In case of tandem lifting only the Project Manager shall authorize such lifting. The following safe practices shall be adhered in all mechanical lifting operation. The following safe practices shall be adhered in all mechanical lifting operation.

- All lifting equipment and tackles shall be maintained in good operative condition.
- Every dangerous and rotating parts of lifting equipment shall be guarded.
- Care shall be taken to avoid the overloading lifting equipment and tackles.

- All lifting operation shall be performed under the supervision of an experienced and trained supervisor.
- Signaller with reflective jacket shall be deployed with the lifting equipment.
- Only one signaller shall direct the operator
- Proper communication shall be maintained between the operator and signaller during the operation.
- Wind speed shall be taken into consideration before lifting and if it exceeds the safe limit all lifting operation shall be ceased.
- Extreme care shall be taken while working near overhead power lines and safe distance shall be maintained.
- Toolbox talks shall be conducted before lifting operation for prevention of incidents.
- Only the project Manager shall authorize tandem lifting.

7.3.4.2 Manual Handling

Correct manual lifting and handling procedures can prevent back injuries and strains that account for a major portion of all industrial injuries. Before handling any material, its weight, size, shape and physical characteristics are to be seen and further action shall be taken accordingly. Following are the measures to prevent the incidents during manual handling.

- Load to be lifted shall be assessed for its weight, shape and size.
- Load shall be sized up and assistance sought if necessary.
- Proper method and posture of lifting shall be adopted.
- Load being carried shall not obstruct the view in front.
- Do not change position of load while moving.
- Slipping and tripping hazards shall be taken care of.

7.3.5 Working at Height

7.3.6.1 Scaffolding

Proper scaffolding and working platform shall be provided to work at height. All scaffolds shall be designed by a competent person and shall be made of good and standard materials. Prior to use, all scaffolds shall be subjected to the inspection of Consultant and shall get approval. All persons involved in the erection and dismantling of scaffold shall be trained and experienced for the same. No persons other than the supervisor involved shall be permitted to be upon any part of an incomplete scaffold.

- All personnel shall be provided with necessary PPE.
- Persons with vertigo shall not be allowed to work at any height.
- All poles, planks and general materials used for scaffolding shall be kept in good condition and be inspected by a competent person on each occasion before being issued from stores.
- As long as the scaffold is in use, supervisor concerned shall inspect it daily before allowing persons to work on it and satisfy himself that the scaffold is complete and is fit for use.
- Subsequent to rain or heavy wind, the scaffolding supervisor shall inspect all scaffolds prior to restart the work.
- All working platforms shall be close boarded and all boards shall be lashed and secured.
- Handrail and toe board shall be provided for all scaffolds and the planks shall be tied to the ledgers properly.
- Scaffolds shall be supported adequately wherever possible
- Always ensure that no loose items and materials are left at height that may fall on person working or passing beneath.
- In case of mobile towers, the height shall never exceed three times the length of the shortest side and there shall be only one working platform on a mobile scaffold.

- The mobile tower shall only be moved by pulling or pushing the base and the working platform shall be clear of men and materials when the tower is being moved.
- The wheels of mobile tower shall be turned outwards and brakes shall be on and locked before use.
- Diagonal bracing shall be fitted on all lifts on all sides and cross bracing shall be fitted at the base and every alternative lifts of an independent tower scaffold.
- Adequate ladders shall be provided for the access to and egress from the scaffold.

7.3.6.2 Ladders

- All ladders shall be factory made and of sound construction.
- Wooden ladders shall not be used with the scaffold.
- If the work is being done in and around electrical equipment and/or cables only wooden (non-conductive) ladders shall be used.
- Ladders shall not be painted.
- Ladders shall be secured properly at top and base.
- Ladder shall be extended for at least one meter above the landing.
- Ladders shall not be used as working platform or part of load bearing component of a scaffold.
- The base to height ratio of ladder shall be maintained as 1:4 such that the angle is 75° from the horizontal can be maintained.

7.3.6 Heavy equipment and workshop

Faecal Sludge Treatment Plant construction project mostly depends on heavy equipment like Dozer, Excavator, Grader, Wheel Loader, Backhoe and Crane. So, the safe operation and maintenance of heavy equipment play a major role in accident prevention. A workshop facility shall be set up in the lay down area

to perform routine maintenance and repairs of equipment deployed for the project. Following measures shall be taken to ensure safe operation and maintenance of equipment and plant:

- Equipment shall be put into service after obtaining approval by a competent technical authority.
- All the operators shall have valid Tanzania license and thoroughly educated about the safe operation and maintenance of equipment.
- It shall be ensured that operators are performing daily checks before commencing the activity and report abnormalities, if any.
- All operators shall undergo frequent refresher training on safe operation and basic firefighting.
- No one shall be allowed to travel in the cabin along with the operator.
- Equipment shall be transported from one place to another only by low bed trailers and proper lashing shall be ensured while transporting through road.
- Adequate space shall be available in the workshop for free movement of vehicle / equipment and each activity shall be performed in a clearly defined area.
- Hazardous activities like painting, welding, cutting, grinding etc. shall segregate from other activities normally will do in dedicated booths.
- Storage of hazardous materials shall be in a secured and dedicated area as per Tanzania Policy standards.
- Emergency exit, fire alarm and firefighting equipment, first aid box, requirement to wear PPE and other necessary safety information shall be displayed at prominent locations with visible signs.
- Adequate lighting and ventilations shall be provided in all work places.
- Adequate provision shall be made for the collection, temporary storage and disposal of solid and liquid waste material from all workplace.
- Good housekeeping standards shall be maintained.
- Smoking and consumption of food shall be restricted to designate area.
- No horseplay or practical work jokes shall be allowed in work place.

7.3.7 Cable Laying, Termination and Jointing& Electrical Works:

Laying of high voltage and low voltage cable and other Electrical works are one of the activities in this project. The main hazards involved in these are struck by, falling of materials, fall of persons, and failure of lifting equipment and tackles, fire and burn injuries. Following precautionary measures shall be taken to avoid any incidents during this stage.

- Risk assessment shall be conducted prior to execution of such job.
- All electrical works shall be performed by qualified persons who shall be provided with adequate and necessary personal protective equipment.
- Prior to maintenance operations on any electrical equipment or appliances, the electrical current shall be disconnected, (lockout and tag out) with a lock or any other adequate means and tagged out to ensure the prevention of reenergizing of the equipment by any person during work.
- Employees working in electricity shall be instructed in using the proper fire extinguishers in electrical fires such as Dry Chemical and CO₂ extinguishers.
- Water or extinguishers containing water shall not be used in extinguishing electrical fires which occur in electrical equipment or conductors as water is a good conductor which causes electrical shocks for the person using the extinguisher.
- Metal ladders or non-insulated hand tools shall not be used while working in electrical installations. (Handles of all hand tools used shall be insulated and wooden ladders shall be used)
- When the fuse or circuit breaker disconnect the electrical circuit, electrical current shall not be re-connected before inspecting the cause of the fault and repair it and thus replace the fuse with other fuse of the same rating or the circuit breaker shall be returned to its first position by a qualified employee.
- Electrical circuit shall not be overloaded to prevent occurrence of fires.
- Electrical wires shall not be passed through doors or windows and shall be kept away from heating sources such as heaters and shall not be

hung from nails to prevent the damage or wearing of the insulating material.

- Defective or corroded electrical wires shall not be used and shall immediately replace.
- Cable drums shall be placed on level and firm ground and properly wedged to prevent rolling.
- Jacks and other accessories for cable laying shall be inspected by a competent person to make sure that it is free from defects.
- Rollers shall be placed properly to avoid the over exertion of force on cables while laying.
- The winch shall be fixed firmly on ground to prevent any unintended movement while pulling the cable.
- Experienced and trained persons shall be deployed for cable laying and winch operation.
- All cable jointing and terminations shall be done by certified and approved cable jointers.
- Adequate fire safety measures shall be taken care while termination and jointing the cable.
- The area shall be barricaded to prevent the entry of unauthorized persons during the operation.
- In case a person receives an electrical shock, this person shall not be touched, first, disconnect the power and remove the injured person away using a piece of wood or any other insulated material, and then, first aid shall be provided to the injured person such as Cardiac Pulmonary Resuscitation (CPR). The doctor shall be informed immediately or the injured person shall be taken to the nearest hospital.
- When recharging batteries, employees shall be instructed not touch the battery liquids, and shall be provided with adequate and suitable personal protective equipment when doing that (Face shield, rubber gloves, aprons) and when refilling batteries by acid, acid shall be added to water (and not water to acid), in case any burns by the effects of acids occurred, immediately flush the burn with big amount of water.

7.3.8 Portable Power and Hand Tools

The main causes of most injuries involving hand tools are the use of unsuitable tools, their incorrect use or their incorrect storage. Inspect the tool and ensure that it is in good condition. Unsafe tools include wrenches with cracked or worn jaws, screwdrivers with broken tips etc.

- Select the right tools for the job.
- Use all tools correctly.
- Keep tools in a safe place.
- We shall train the workers to select the right tools for each job, and ensure that the tools are available.
- Protect the edges of the sharp tools while carrying.
- Tools shall not be kept lying on floor, walkways or scaffolds,
- Tools shall not throw from one level to another. It shall be lifted and lowered by hand lines.
- All guards and covers shall be securely fitted and correctly adjusted.

7.3.9 Transportation

This section outlines the procedure and guideline for avoidance for motor vehicle accidents.

- Every person driving a motor vehicle or operating a machine must possess valid driving licenses appropriate to the class of vehicle being driven.
- All drivers should observe posted speed limits. Adverse weather conditions, traffic and light (visibility) require lower speeds than posted speed limit. Maximum speed limit must be limited 40 KPH in camps and 60 KPH on haul roads.
- All vehicles shall be parked uniformly and where provided, in designated parking areas. Parked vehicle shall not be obstructing other vehicle, roads, and access ways for fire hydrants.
- Vehicle shall be maintained in good condition and regular inspection carried out to check steering system, foot and parking breaks, tyres, seat

belts, horn, Head lights, tail lights, stop light and indicators, rear view mirrors, wind shield wipers and washer, crank case and radiator level.

- Drivers and passengers in all vehicles including buses should wear seat belts.
- Driver shall slowdown in inter section, blind corners and stop completely at all stop.

7.4 Emergency Preparedness and Response

DAWASA plan to construct a Faecal sludge treatment plant at Golani, Mtaa, Kimbiji Ward in Kigamboni Municipality. This DAWASA Emergency Response Plan (ERP) has been prepared to establish the procedures for responding to specific emergencies that may occur. Copies of these plans are maintained at the contractor office, DAWASA office and at each FSTP site. The Emergency Response Plan includes protocols to ensure close coordination with local area emergency response organizations, agencies and also with existing state and local Emergency Preparedness Plans. In the event there is a conflict within the standards or regulations or within pre-established site safety guidelines, the more stringent shall govern.

7.4.1 Review and responsibilities

- **DAWASA Management:** The management is committed to the principle of the safe working and desires that on no account, should any person ever put him to risk.
- **Contractor:** It is the responsibility of the site management to review and ensure awareness of emergency procedure among all the site personnel.
- **Contractor Employees:** It is also the responsibility of all employees to continually familiarize themselves with the assembly procedures for their relevant areas of work.

- **General:** Any information being relayed about an emergency shall be clear and precise giving the exact location, the nature of the emergency and the seriousness of the emergency and contact numbers and names.

8.0 ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN

8.1 Environmental and Social Management Plan

The Environmental and Social Management Plan (ESMP) presents the implementation schedule of the proposed mitigation measures for both environmental and social impacts. The ESMP for the proposed Construction of the Faecal Sludge Treatment Plant (FSTP) in the Golani area is summarized in Table 4. The ESMP also indicates the environmental costs needed to implement the recommended mitigation measures. The Faecal Sludge site selection process and engineering designs have already included some of the mitigation measures recommended in this report. Additional recommendations are provided in the ESMP to enable the Faecal Sludge Treatment Plant to be constructed and operated in an environmentally friendly manner.

DAWASA in collaboration with Kigamboni Municipality shall be the main implementer of the ESMP through. The environmental measures incorporated in the detailed engineering design will be attached to the Bills of Quantities and Contract Documents. Moreover, there will be an Environmental, Social, Health and Safety (ESHS) Code of Conduct to be signed by the Contractor(s) to show their commitment to the implementation of the Environmental, Social, Health, and Safety. The implementation of the Code will be supervised by DAWASA or his consultant.

The ESHS Code is a set of Guidelines attached to the Bidding Document and Contract to be adopted by the Contractor during project implementation. It contains the commitment and obligations of the Contractor and its subsidiaries (i.e. Sub-Contractors and staff) to undertake construction activities following all applicable Laws, Rules, and Regulations. The Contractor and its subsidiaries shall comply with the Code of Conduct with high ethical standards. Failure to observe the Code will subject the firm to disciplinary action, including Contract termination. Violation of the Code is a violation of Law that may result in civil and/or criminal penalties to Contractors, Supervisors, or Firm.

Some of the issues to be included in the ESHS shall include;

- Site-specific **ESMP & HSMP**,
- Traffic Management Plan (**TMP**), **where applicable**
- HIV/AIDS Awareness Program
- Occupational Health and Safety Awareness Program
- Sexual Harassment Prevention Policy
- Child Labour Prevention Policy

The environmental and social mitigation and enhancement measures incorporated in the detailed engineering design will be attached to the Contract Documents. The Contractor shall take stock of the contents of the Project Brief.

Table 5: Environmental and Social Management Plan for the Proposed Construction of Feacal Sludge Treatment Plant at Golani area, Kimbiji ward, Kigamboni Municipal

Impact	Mitigation Measure	Responsible Institution	Estimated One Time Cost (TZS)	Estimated Annual cost (TZS)
Mobilization Phase				
Increased waste generation	<ul style="list-style-type: none"> ○ Stick to the design specifications ○ Provide waste containers ○ Provide training to workers and orient them towards environmental protection values 	DAWASA	To be included in the BOQ	
Noise pollution during construction	<ul style="list-style-type: none"> ○ The proponent shall maintain equipment in good running conditions to ensure that ambient noise level and vibrations pollution into the environment is very minimum to comply with Tanzania standards ○ All construction works will be scheduled at normal working hours. ○ Proper inspection and maintenance of construction vehicles and equipment will be done to ensure that they have mufflers installed and worn parts are replaced 	DAWASA	500,000.00	
Construction Phase				
Increased waste generation	<ul style="list-style-type: none"> ○ Stick to the design specifications ○ Provide waste containers ○ Provide training to workers and orient them towards environmental protection values 	DAWASA	To be included in the BOQ	

Project Brief of the Proposed Fecal Sludge Treatment Plant at Golani Street-Kimbiji Ward

Impact	Mitigation Measure	Responsible Institution	Estimated One Time Cost (TZS)	Estimated Annual cost (TZS)
Increased HIV/AIDS and other STD	<ul style="list-style-type: none"> ○ The contractor shall enforce a code of conduct in the project area to encourage respect for the local community and to maintain self-cleanliness of the working area at all times. ○ The contractor shall deploy locally available labor to reduce the risk of spreading communicable diseases (especially STDs). ○ To prevent more HIV/AIDS infections, during the implementation phase, the project should include an information education and communication component (IEC) in its budget. This will help to raise more awareness on HIV/AIDS and means to suppress its incidence. ○ A safety, health, and environment induction course shall be conducted for all workers, putting more emphasis on HIV/AIDS, which has become a national disaster. 	DAWASA	5,000,000.00	
Land degradation and increased erosion	<ul style="list-style-type: none"> ○ The contractor should pave the walkways prone to erosion whose quantities are shown in the BoQ ○ To obtain the construction materials official negotiations should be performed with wards leaders to avoid conflict. 	DAWASA	25,000,000	
Noise pollution during construction	<ul style="list-style-type: none"> ○ The proponent shall maintain equipment in good running conditions to ensure that ambient 	DAWASA	1,000,000.00	

Project Brief of the Proposed Fecal Sludge Treatment Plant at Golani Street-Kimbiji Ward

Impact	Mitigation Measure	Responsible Institution	Estimated One Time Cost (TZS)	Estimated Annual cost (TZS)
	<p>noise level and vibrations pollution into the environment is very minimum to comply with Tanzania standards</p> <ul style="list-style-type: none"> ○ All construction works will be scheduled at normal working hours. ○ Proper inspection and maintenance of construction vehicles and equipment will be done to ensure that they have mufflers installed and worn parts are replaced 			
Dust generation during construction	<ul style="list-style-type: none"> ○ Mixing equipment shall be sealed properly and vibrating equipment will be equipped with dust-removing devices. ○ Also, all vehicles that generate excessive black smoke will not be used. ○ Adequate training and use of personal protective equipment (PPE) such as eyeglasses and dust masks will be ensured to reduce risks associated with dust. 	DAWASA	3,000,000.00	
Health Risks associated with construction works	<ul style="list-style-type: none"> ○ The project proponent shall ensure that all personnel is 	DAWASA	33000,000.00	

Project Brief of the Proposed Fecal Sludge Treatment Plant at Golani Street-Kimbiji Ward

Impact	Mitigation Measure	Responsible Institution	Estimated One Time Cost (TZS)	Estimated Annual cost (TZS)
	<p>provided with appropriate protective gear.</p> <ul style="list-style-type: none"> ○ All works shall be planned and conducted following relevant OHS Guidelines. First Aid Kit as well as regular medical check-ups for the workers will be provided during the entire working hours. ○ An adequate number of firefighting equipment/extinguishers will be provided every few distances to help to put off the fire in case of occurrence. ○ Excavated pits should be protected by warning tape and guardrails to prevent workers from falling <p>Sensitization/Awareness of the beneficiary community on the importance of the Facility and the associated benefits</p>			
Demobilization phase				
Noise pollution during construction	<ul style="list-style-type: none"> ○ The proponent shall maintain equipment in good running conditions to ensure that ambient noise level and vibrations pollution into the environment is very minimum to comply with Tanzania standards 	DAWASA	500,000.00	

Project Brief of the Proposed Fecal Sludge Treatment Plant at Golani Street-Kimbiji Ward

Impact	Mitigation Measure	Responsible Institution	Estimated One Time Cost (TZS)	Estimated Annual cost (TZS)
	<ul style="list-style-type: none"> ○ All construction works will be scheduled at normal working hours. ○ Proper inspection and maintenance of construction vehicles and equipment will be done to ensure that they have mufflers installed and worn parts are replaced 			
Operational Phase				
Health Risks associated with Operation works	<ul style="list-style-type: none"> ○ The project proponent shall ensure that all visitors and personnel are provided with appropriate protective gear. ○ An adequate number of firefighting equipment/extinguishers will be provided every few distances to help to put off the fire in case of occurrence. ○ Adhere to good maintenance ○ Sensitization/Awareness of the beneficiary community on the importance of the Facility and the associated benefits 	DAWASA	Depend on the operational manual	
Total			68,000,000.00	68,000,000.00

9.0 MONITORING PLAN

9.1 Environmental Monitoring

The national EIA guidelines require the developer to prepare and undertake a monitoring plan of implemented development projects. Monitoring is needed to check if and to what extent the impacts are mitigated, benefits enhanced and new problems addressed. Recommendations for monitoring have been included in Table 5. The monitoring plan also assigns responsibilities to different actors. Moreover, the ward and street environmental committees will shoulder the long-term monitoring of the project.

Table 6: Monitoring Plan for the Proposed Construction of Fecal Sludge Treatment Plant (FSTP) at Golani area, Kimbiji ward, Kigamboni Municipal-Dar es Salaam

Parameter	Monitoring Frequency	Sampling Area	Measurement Unit	Method	Target Level/Standard	Responsibility for monitoring	Estimated Annual (or once cost (TZS)
Mobilization Phase							
Dust (PM 2.5, PM 10)	Daily	Immediate working area	µg/Nm ³	Physical-visual	Daily average of hourly values shall not exceed 0.10 µg/Nm ³ and hourly values shall not exceed 0.20 µg/Nm ³	DAWASA	None
Air Quality (SO ₂ , NO ₂)	Daily	Around the Inspection chambers	ppm	Smelling (nasal)	0.2 ppm for 10 and 0.1 ppm for 8 hours of exposure respectively	DAWASA	2,500,000.00
Waste Generation	Weekly	At the working area	Amount of waste	Physical measurement or estimation	All waste contained	DAWASA	In BOQ
Health risks	Daily	At working area	Accidents	Counting	NO accident	DAWASA	In BOQ
HIV/AIDS	Monthly	Workers	Training	Numbers	One per month during construction phase only	DAWASA	5,000,000.00
Biodiversity	Once (at commencement)	Working area	Destruction of habitat or removal of biodiversity	Area affected	Minimal disturbance to biodiversity	DAWASA	1,000,000.00
Construction phase							
Dust (PM 2.5, PM 10)	Weekly	Immediate working area	µg/Nm ³	Physical-visual	Daily average of hourly values shall not exceed 0.10 µg/Nm ³ and hourly values shall not exceed 0.20 µg/Nm ³	DAWASA	None
Air Quality (SO ₂ , NO ₂)	Weekly	Around the Inspection chambers	ppm	Smelling (nasal)	0.2 ppm for 10 and 0.1 ppm for 8 hours of exposure respectively	DAWASA	2,500,000.00

Parameter	Monitoring Frequency	Sampling Area	Measurement Unit	Method	Target Level/Standard	Responsibility for monitoring	Estimated Annual (or once cost (TZS)
Waste Generation	Weekly	At the working area	Amount of waste	Physical measurement or estimation	All waste contained	DAWASA	In BOQ
Health risks	Daily	At working area	Accidents	Counting	NO accident	DAWASA	In BOQ
HIV/AIDS	Monthly	Workers	Training	Numbers	One per month during construction phase only	DAWASA	5,000,000.00
Biodiversity	Once (at commencement)	Working area	Destruction of habitat or removal of biodiversity	Area affected	Minimal disturbance to biodiversity	DAWASA	1,000,000.00
Demobilization Phase							
Dust (PM 2.5, PM 10)	Weekly	Immediate working area	µg/Nm3	Physical-visual	Daily average of hourly values shall not exceed 0.10 µg/Nm3 and hourly values shall not exceed 0.20 µg/Nm3	DAWASA	None
Air Quality (SO ₂ , NO ₂)	Weekly	Around the Inspection chambers	ppm	Smelling (nasal)	0.2 ppm for 10 and 0.1 ppm for 8 hours of exposure respectively	DAWASA	500,000.00
Waste Generation	Weekly	At the working area	Amount of waste	Physical measurement or estimation	All waste contained	DAWASA	In BOQ
Health risks	Daily	At working area	Accidents	Counting	NO accident	DAWASA	In BOQ
HIV/AIDS	Monthly	Workers	Training	Numbers	One per month during construction phase only	DAWASA	5,000,000.00
Biodiversity	Once (at commencement)	Working area	Destruction of habitat or removal of biodiversity	Area affected	Minimal disturbance to biodiversity	DAWASA	1,000,000.00
Operation phase							
Air Quality (SO ₂ , NO ₂)	Monthly	Around the Inspection chambers	ppm	Smelling (nasal)	0.2 ppm for 10 and 0.1 ppm for 8 hours of exposure respectively	DAWASA	500,000.00

Parameter	Monitoring Frequency	Sampling Area	Measurement Unit	Method	Target Level/Standard	Responsibility for monitoring	Estimated Annual (or once cost (TZS))
Waste Generation	Monthly	At the working area	Amount of waste	Physical measurement or estimation	All waste contained	DAWASA	In operation manual
Health risks	Monthly	At working area	Accidents	Counting	NO accident	DAWASA	In operation manual
HIV/AIDS	Annually	Workers	Training	Numbers	One per month during construction phase only	DAWASA	In operation manual
Total							28,000,000.00

10.0 COST BENEFIT ANALYSIS

10.1 JUSTIFICATION FOR RESOURCE EVALUATION

Regulation 18(1) of the Environmental Impact Assessment and Audit Regulations, 2005, requires that an Environmental Impact Statement should contain among others, a section discussion on the project's "resource evaluation or cost benefit analysis". The rule is that a Project should be undertaken if lifetime expected benefits exceeds all expected costs. The art of the analysis process comes in the measurement of these impacts, their adjustment for market failure, and for the effects of time, income distribution, incomplete information and potentially irreversible consequences. Although complexities arise when costs and benefits are being measured and corrected, CBA is a simple tool with numerous uses and applications, especially in the environmental assessment sphere. Its use increases accountability and consistency in decision-making.

10.2 ACTIVITIES COST

The project site will be developed and will include the construction of Feacal Sludge Treatment Plant FSTP, but will also be funded by World Bank

Activities conducted to date include:

- Topographical Survey for setting out purposes,
- Geo-technical Investigation for the areas allocated with the balancing tank and Anaerobic Baffled Reactor (ABR)
- Construction Materials' source Investigation,
- ESIA Study - Site visits were also conducted to obtain the physical environment properties (vegetation, fauna, water resources, topography) of the site and surrounding area. Consultation with relevant regulatory, surrounding communities and project stakeholders is also being undertaken during this phase for collecting social – economic information.

There will be cost for management of the potential impacts that mainly storm water management, sewage management, water resources protection and solid waste management.

DAWASA recognizes the significance of ensuring that the environmental impacts on site are minimized or eliminated. DAWASA will adopt the following hierarchy in environmental risks management;

- Eliminate the hazard altogether - get rid of the unacceptable technology in wastewater treatment.
- Substitute the hazard with a safer alternative – replace adopt the best available disposal technology.
- Isolate the hazard from anyone who could be harmed – ensure no interaction between unacceptable discharge/emission with environmental aspects.
- Use engineering controls to reduce the risk – incorporate environmental and safety issues in design stage.
- Use administrative controls to reduce the risk – training to users for appropriate operations.
- Use personal protective equipment (PPE) – additional protective gears to unavoidable risk which is always acceptable.

10.3 COST BENEFIT ANALYSIS CONCLUSIVE REMARKS

The direct benefits accrued by the communities through improved sanitation services, employment, to surrounding communities resulting in the stimulation of the local economy and environmental conservation make this Project a viable Project. Furthermore, environmental costs from impacts are to be mitigated and managed according to the proposed plan.

10.4 PROJECT BUDGET

The investment cost for the proposed Faecal Sludge Treatment Plant is estimated to be around Tshs. 0.7 billion that will be financed by The World Bank.

11.0 CHAPTER ELEVEN: CONCEPTUAL DECOMMISSIONING PLAN

No life span can be predicted and its potential impacts analyzed precisely for this project of an educational facility. Possibilities will be transfer of the ownership of the land, activities, rehabilitation/renovations, modification and additional infrastructures. The Environmental Management Act stipulates requirements that need to be adhered.

In event that no health activities or part of the facility or infrastructures change their intended use, the acceptable decommission plan for both NEMC and DAWASA will be developed. The plan should address how DAWASA will rehabilitate the disturbed area closer to its original state and will fund the whole closure process.

11.1 Conceptual closure plan

- The long-term preservation of water resources, wastewater treatment and Solid waste disposal facilities.
- The removal and or acceptable disposal of all internal road, structures, and equipment that will not be required after the end of the project life or by the next land user;
- The long-term stabilization of all exposed erodible materials;
- The natural integration of disturbed areas into the surrounding landscape, and the restoration of a natural appearance to the disturbed areas after camp ceases, to the best practical extent; and
- The establishment of a self-sustaining cover of vegetation that is consistent with existing biological environment;
- Reasonable notice for all affected stakeholders such as suppliers, employees and other indirect beneficiaries and
- Appropriate employment termination will be made as per work related governing laws.

12.0 CONCLUSION

The proposed project is of greater profit to the community and the country at large as it promotes and improve sanitation in the streets. When there is good and improved sanitation, then the outbreak of diseases like diarrhoea and associated stomach and waterborne diseases are also reduced and prevented hence improved public health.

The impacts identified are preventable and of less negativity to the community, therefore the developer can be provided with the environmental clearance certificate in order to commence the implementation of the project.

It is, therefore, concluded that implementation of the proposed construction of the Faecal sludge treatment plant at Golani mtaa will entail no detrimental impacts provided that the recommended mitigation measures are adequately and timely put in place. The identified adverse impacts shall be managed through the proposed mitigation measures and implementation regime laid down in this EIS. DAWASA is committed to implementing all the recommendations given in the EIS and further carrying out the environmental auditing and monitoring schedules.






References

1. Bicknell, J.; Dodman, D., and Satterthwaite, D., (eds.), 2009. Adapting Cities to Climate Change: Understanding and Addressing the Development Challenges. London, UK: Earthscan, 397p.
2. Investment profile of Kigamboni District
3. Nicholls, R.J., Wong, P.P., Burkett, V.R., Codignotto, J.O., Hay, J.E., McLean, R.F., Ragoonaden, S. and Woodroffe, C.D. 2007. Coastal systems and low-lying areas. In: M.L. Parry, O.F. Canziani, J.P. Palutikof, P.J. van der Linden, and C.E. Hanson, (Eds), Climate Change 2007: Impacts, Adaptation and Vulnerability. Contribution of Working Group II to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change, Cambridge University Press, Cambridge, UK, p. 315-356.
4. Population and Assets Exposure to Coastal Flooding in Dar es Salaam (Tanzania): Vulnerability to Climate Extremes
5. Kigamboni District Socio-economic profile 2010/2011

Appendix I: List of Stakeholders Consulted

ENVIRONMENTAL AND SOCIAL IMPACT ASSESSMENT FOR THE PROPOSED CONSTRUCTION OF OFF-GRID SANITATION PROJECTS, DARE ES SALAAM

LIST OF CONSULTED STAKEHOLDERS

SN	DATE/TARAAHI	NAME/JINA	INSTITUTION/TAASISI	POSITION/CHO	PHONE NO./SINI	SIGNATURE/SALMI
1	24/07/2023	Francis Mwangi	ARROW	AREA	0724-295737 0945-877887	
2	-11-	Theodore Mwangi	KENAC	CEO	0724-11503	
3	11	Tabu Mwa Ngugi	71	23	0729-44005	
4	11	JENIFA KIMANI	11	11	0728791075	
5	11	ANITA MWA NGUGI	11	11	067362677	

ENVIRONMENTAL AND SOCIAL IMPACT ASSESSMENT FOR THE PROPOSED CONSTRUCTION OF OFF-GRID SANITATION PROJECTS, DAR ES SALAAM

LIST OF CONSULTED STAKEHOLDERS

S/N	DATE/TARIHI	NAME/JINA	INSTITUTION/TAASISI	POSITION/CHED	PHONE NO./SIMU	SIGNATURE/SAITI
1		JUVENALIS MAYANA	Kigamboshi HC	Environment Officer	976 240685	[Signature]
2	24-09-2022	Husein M. MAYANA	-/-	-/-	0716 35125	[Signature]
3	"	Jocelyne J. TUMINDATA	-/-	-/-	0654 310954	[Signature]
4		MATHEO J. MAYANA	"	"	0685 257025	[Signature]
5	"	REHENA A. JOHN	"	"	06 210 8371	[Signature]
6	-/-	NICHOLAS A. MAYANA	-/-	-/-	0752276225	[Signature]

ENVIRONMENTAL AND SOCIAL IMPACT ASSESSMENT FOR THE PROPOSED CONSTRUCTION OF OFF-GRID SANITATION PROJECTS, DAR ES SALAAM

LIST OF CONSULTED STAKEHOLDERS

SN	DATE/TARİHE	NAME/İSİMİ	INSTITUTION/TRAHİDE	POSITION/CEHO	PHONE NO./SİHU	SIGNATURE/İSİMİ
	29/08/2022	SHEDRAK G. MUMU	KITAMBONI MC	EMO	0772 21571	
	— II —	MIFIKO FATUMA	— II —	EMO	0743 651115	
		ADHA M. MUMU	— II —	EMO	0655826719	
		JOHN M. SUEIKAN	— II —	EMO	0747-5150 23	
		FIRANA A. NICHATUNGI	— II —	EMO	0872 20453	

Appendix II: Minutes of Meetings with stakeholders



- 1. **Project Site** - The site is located in the Kimbiji Ward, Golani Street, Nairobi. It is a vacant plot of land, approximately 100m x 100m, situated in an urban area. The site is bounded by residential plots on three sides and a road on the fourth. The site is currently used as a parking area for the adjacent building.
- 2. **Project Objectives** - The main objective of the project is to provide a sustainable and hygienic solution for the collection, treatment, and disposal of fecal sludge from the surrounding residential areas. The project aims to improve public health, reduce environmental pollution, and create a safe and healthy environment for the community.
- 3. **Project Scope** - The project scope includes the design, construction, and operation of a fecal sludge treatment plant (FSTP) with a capacity of 100,000 liters per day. The FSTP will consist of a collection system, a treatment tank, and a disposal system. The collection system will be a network of underground pipes and manholes that will collect fecal sludge from the surrounding residential areas. The treatment tank will use a combination of natural and artificial processes to break down the sludge and remove the pathogens. The disposal system will be a composting system that will produce a safe and healthy compost for use in agriculture.
- 4. **Project Budget** - The estimated budget for the project is KES 10 million. This includes the cost of land, design, construction, and operation. The budget is based on current market prices and is subject to change. The project is funded by the Government of Nairobi and the Kimbiji Ward Council.
- 5. **Project Risks** - The main risks of the project are the lack of funding, the lack of technical expertise, and the lack of community support. The project team will work to address these risks by seeking additional funding, hiring experienced professionals, and engaging the community in the project.

17. *[Faint handwritten text]*

[Faint handwritten text]

[Faint handwritten text]

[Faint handwritten text]





Area	Location	Material	Quantity	Unit	Remarks
Area 1	1.1	Concrete	100	m ³	For foundation
	1.2	Brick	5000	nos	For walls
	1.3	Roofing	100	m ²	For roof
	1.4	Plaster	200	m ³	For walls
	1.5	Paint	100	liters	For walls
	1.6	Iron	100	kg	For reinforcement
	1.7	Wood	100	m ³	For roof
	1.8	Labour	100	man-days	For construction
	1.9	Transport	100	trucks	For material transport
	1.10	Other	100	units	For miscellaneous
Area 2	2.1	Concrete	150	m ³	For foundation
	2.2	Brick	6000	nos	For walls
	2.3	Roofing	150	m ²	For roof
	2.4	Plaster	300	m ³	For walls
	2.5	Paint	150	liters	For walls
	2.6	Iron	150	kg	For reinforcement
	2.7	Wood	150	m ³	For roof
	2.8	Labour	150	man-days	For construction
	2.9	Transport	150	trucks	For material transport
	2.10	Other	150	units	For miscellaneous

**Appendix III: Memorandum of Understanding between DAWASA and
Dar es Salaam Municipal Councils**



**MEMORANDUM OF UNDERSTANDING
BETWEEN
MINISTRY OF WATER
AND
THE DAR ES SALAAM WATER SUPPLY AND
SEWERAGE AUTHORITY,
REGIONAL ADMINISTRATIVE SECRETARIAT
AND
DAR ES SALAAM MUNICIPAL COUNCILS
(Kisumuini, Haha, Teremko, Ubungu, Kigamboni)**

JANUARY 2019

100	Non-Technical Summary
101000	General Work Item Description Summary
1010	Operations and Maintenance
101	Process Manual Parts
1001	Process Control System Technology
100	Project Implementation Manual
10	Project Management Plan
10	Project Overview
100000	Process Flow Diagram, Description and Unit Descriptions
1000	Unit Processory Equipment Details
100	Instrumentation Details
100	Process Automation System
10	Project Summary
100	Project Set Point
100	Process Description List
100	Plant Part Name Lists
100	General Process of Treatment
100	Process Flowchart
10000	Unit Name and General Details
10	Water Collection
1000	Water Treatment Development Program
100	Water Supply and Distribution
1000	Water Supply Development Program
10000	General Water Supply System

**A MEMORANDUM OF UNDERSTANDING
FOR THE IMPLEMENTATION OF THE CITY OF NAIROBI WATER SUPPLY AND
SANITATION PROJECT UNDER THE SEWERAGE WATER SUPPLY AND
SANITATION PROJECT USING KENYAN AND FINANCING**

Heretoafter (‘‘the Memorandum of Understanding’’ (‘‘MoU’’)) between the Ministry of Water on one part and the City of Nairobi Water Supply and Sewerage Authority (‘‘WSSA’’), the City of Nairobi Regional Commissioner and the five municipalities (City of Nairobi, Nairobi City Council, Kiambu Municipal Council, Thika Municipal Council and Machakos Municipal Council) on the other part.

WHEREAS the Government of Kenya has approved and coordinated the urban water supply and sewerage development of the Nairobi Region of Nairobi, the Government has approved a main water supply treatment plant in the following programme, viz the National Strategy for Growth and Reduction of Poverty (‘‘NSRF’’), in particular (i) the National Water Supply Management Strategy (‘‘NWSM’’), and (ii) the Water Sector Development Program (‘‘WSDP’’).

WHEREAS the City of Nairobi, with the assistance of the WSDP, is to be the main water supply treatment plant in the Nairobi Region of Nairobi.

WHEREAS the WSDP project implementation objectives are to regulate the supply of the improved water services, planning and management of the water supply of Nairobi and improve water supply and sanitation services to communities, urban areas, and rural areas. The project has four components, namely: (i) Improved Water Services Management; (ii) Improved Water Supply Infrastructure; (iii) Improved Sanitation Infrastructure; and (iv) Improved Management and Institutional Support.

WHEREAS the project is being financed by the City of Nairobi through the WSDP Project Financing, the project has obtained the commitment of the Government of Kenya.

WHEREAS on the other part WSSA, has committed itself to the principle of transparency and accountability in the highest degree of alignment with the Government’s policies and accounting systems and legal framework so as to ensure efficient implementation, which by administrative bodies of the Government, and national financial institutions.

WITH THESE VIEWS, the parties hereby agree to cooperate in implementing the implementation of the water supply and sewerage project (‘‘WSP’’) in accordance with the objectives and principles set forth in this MoU, provided, however, that in case of any conflict between the provisions of this MoU and the PROJECT Financing Agreement, the provisions of the Financing Agreement shall prevail.

as necessary, as the project may be awarded from tenders will be coordinated by the Government Development Authorities.

2. **NSRF Implementation Manual** issued by Project Implementation Manual (PIM) specifies implementation arrangements for the National NSRF, including institutional arrangements, procedures for procurement, disbursement of funds, financial management, environmental and social management, and monitoring and evaluation, and project reporting requirements, including annexes to the manual.
3. **Project Management Team** issued a letter of intent by DANIDA, for the management of the off-grid water supply sub-project, from the management of off-grid sanitation sub-project.
4. **Facilities Team** A team composed by the District Director of the respective Municipal Council from the respective region for the purpose of facilitating the implementation of the NSRF water supply projects and the off-grid sanitation projects. The scope of their responsibility was defined in the TOR and transmitted to the NSRF.

2. OPERATIONAL PRINCIPLES

- 1) The NSRF, DANIDA, NS and Municipalities agree that the following are the underlying principles for project (P) financing:
 - (a) Commitment to the fullness of the objectives of the National Development Vision 2030;
 - (b) Consistent with national budgeting, procurement and public financial management related regulations;
 - (c) Good governance and accountability of the Government to its citizens, including an active fight against corruption;
 - (d) Compliance to the requirements of the off-grid water supply and sanitation sub-projects and facilities and
 - (e) Full and correct implementation of the (P) project.

2. GENERAL PROVISIONS

1) Types:

This bill contains the responsibilities of the NSRF, DANIDA, NS and Municipalities with respect to the construction of off-grid water supply and sanitation sub-projects and also their national institutional, environmental and social measures, monitoring and evaluation, and reporting arrangements. The NSRF is implementation manual complementary procedures and arrangements to be in the NSRF.

3.2. **Responsibility of the MPW**

The MPW is not intended to create any legal liability for any of the project stakeholders. The responsibility of the contractor shall be to ensure that all obligations towards the Government Institutions and the public are upheld. The contractor shall be subject to the work regulations of any of the entities between the purview of the MPW and the other Planning Agreement for purposes of the Financing Agreement and period.

4. **OPERATIONAL WATER SUPPLY**

4.1. **Overview**

The MPWALA retains its commitment to the provision of the Sewerage Water Supply Project and will, in full, assist the contractor and all others in facilitating the successful implementation of the project. To that end, MPWALA, as an implementing Agency will ultimately carry out all roles and responsibilities in the implementation of the all-kind water supply infrastructure interventions outlined in the WSP (Supply Rehabilitation Manual, The Ministry of Water as the Responsible Agency for WSP) and will have overall responsibility for the construction and implementation of the 10-year water supply and sanitation programs.

4.2. **Institutional Arrangement**

The institutional framework for executing the implementation of the WSP is comprised of following entities to be involved in the implementation, and as per the MPW (Supply Rehabilitation Manual):

- 1. Ministry of Water;
- 2. Rural Water Supply Office Regional (Water Resource and Social Development);
- 3. Ministry of Health, Community Development, Gender, Disability and Children;
- 4. Municipal Councils;
- 5. Beneficiary Communities (BCs).

4.2.1. **Ministry of Water (MoW)**

The MoW will be responsible for provision of overall coordination and oversight. The Ministry will also provide technical and administrative support in the implementation of WSP, including various functions as follows:

- 1. Coordinating and monitoring the quality of water supply (WSP) and ensure financial support – cost control and overall program implementation; and ensuring the funds allocated to implementation of WSP are used as they are intended to be used with great

and budget of the implementing agency, and that the WMP is consistent with the conditions of the WSCF's work plan and budget.

5. Ensuring quality and consistency of the documents referred to in sub-paragraph (a) above prior to submission as indicated in the Programme Implementation Manual and sub-paragraph (a) of the WMP to the WSCF for processing.
6. Monitoring the implementation of the Annual Work Plan and Budget for the WMP by the implementing agencies, at least on quarterly basis.
7. Providing oversight on financial management, controls, audits and reports, and
8. Ensuring that management decisions made by the official WMP Steering Committee are communicated to the implementing agencies, implemented and monitored.

4.2.2. WSCF

WSCF will be responsible for overall coordination and implementation of all JGJ water supply activities. The off-grid water supply shall be implemented under the Supervision of Professional Consultants who are under the management and coordination with the Commission (JGJ) for construction development. The Commission will also be generally responsible for:

1. Coordinating inputs on regional data other than within JGJ/WSCF such as procurement, technical services and financial etc.
2. Approving and monitoring contracts/agreements.
3. Working on the project agreements with Ministry/communities.
4. Monitoring and reporting overall progress of the off-grid water supply sub-projects.
5. Reviewing and approving the financial and management of the water supply sub-projects.
6. The Council agrees to all grid water supply sub-projects will be covered by all JGJ/WSCF/communities (WMP/VOL/3/2/1/4).
7. Overall approval of off-grid water supply sub-projects.

4.2.3. Municipal Council for WSCF

The District or Village Municipal Councils through their respective Water Planning Department, Local Govt, Municipal Council and Water Department, will be responsible for the following roles:

1. Ensuring operational maintenance of the water supply.

operation of water services and infrastructure. DA WASS will be responsible for the efficient operation and management of the water supply system.

4.2.6 Fines System

The Fines System (FFS) will be adopted if the expansion of DA WASS grid network is beyond five years time. The FFS would primarily target and deter the illegal disposal of fecal sludge, with an operating body advised by the committee that would liaise with additional personnel from DA WASS/CLGSA. The operation of these systems, including the costs, would be undertaken by WFP/DA, as part of the overall operations of the water supply system.

Fines System will assess, collect, and manage the illegal water connection and use of the grid.

The Fines System shall be responsible for tracking and monitoring operations made in the following activities: Street grid activities:

1. Current status
2. Operational requirements, works including status of water pipeline and all other utilities, work on network, records of plant and equipment
3. Condition and capacity of lines
4. The status of network expansion in specific locations
5. The Fines System shall provide records and generate reports and information
6. Reports to be completed on grid water supply activities
7. Billing and payment records
8. Revenue received and financial statement

In general, the Operation and Maintenance System will address such issues as:

1. Number of registered customers in the network area
 2. Volume of people in the network area and number of people served
 3. Network size and layout
 4. Level of service, proposed and actual
 5. Revenue and expenditure against operating budget
 6. Customer satisfaction
 7. Maintenance activities, breakdown, failure
 8. Availability of assets including spare parts
 9. Availability of land resources for project activities
- III. Managing the network water supply business unit

4.3. SELECTION CRITERIA

DAWAHA, in consultation with the Municipalities (Gole, Kimbiji, Kijungu, Kileleshwa and Uthmaniyah) and Nairobi Metropolitan Council will select the winning team to supply and operate under the WSP E. The shortlisting will follow the criteria below:

1. High technical score
2. Low financial price
3. Professional of technical degree
4. High volume water supply
5. Successful performance
6. Availability of staff and facilities
7. Technical solution
8. Financial solution

Each of these criteria will be assigned a score, will be weighted proportionally according to their importance. Bidders to submit the details of their bid against the weights. The Nairobi Metropolitan Council/Program (NMC/ WSP E) will award to their contractor whose score is highest score.

DAWAHA 011-4382754/07542028

5.2. Software

The NMC/ WSP E contractor will provide each needed dependent on systems assigned to them in view of the fact that the software used in the WSP E project. The contractor will be required to provide a list of computer of software systems required project such as Supervisory Water Meter Control System (SWMCS), Sewer Sludge Control System, and water quality control systems. The NMC/ WSP E contractor will address the lack of such information in their bid.

5.3. Technical proposals

Contractor will have to provide details of the technical solution and a cost estimate along the technical solution provided in the scope of work. Technical proposal to be prepared and include being filled forms, Technical Proposal, City Water Management Organization, Regional Authority, Government of Kenya, the National Water Commission and other relevant institutions.

Contractor will have to provide a list of the list of O&M, Municipalities and Regional (DAWAHA) will be required to provide information and experience of O&M services provided. Other information is provided in PFI are requested below.

1. UNH/TWAC
2. MHC
3. EC
4. UJWSA
5. WOS
6. JG

4.2: Ministry of Water

Ministry of Water will be responsible with setting Policy and guidelines specific to WWT and provide technical assistance and implementation support.

4.3: UNH/TWAC

UNH/TWAC will provide a technical and financial support for the overall implementation of the FSTP.

Ministry of Information Development will be the department which UNH/TWAC supports for executing the implementation of the WWT. It includes UNH/TWAC National City component. The goal of the department will report directly to the UNH/TWAC Headquarters office and will primarily be responsible for:

1. Coordination of UNH/TWAC National Working Committee to work on establishing a project steering and oversight by forming Committee members with representatives and leading of Ministry of Information and providing technical services
2. Coordinating teams to provide project services including UNH/TWAC, such as Government, International Development, and Research, etc.
3. Specific responsibilities and providing services: agreements
4. Setting up Information Agreement with external communities
5. Monitoring and reporting project progress to the UNH/TWAC
6. Supporting and advising the operation and management of the community based system.

In support of the Component 1: a National committee will be set up by UNH/TWAC – National Director will be responsible to coordinate implementation of the WWT and provide services. The national department is the coordinator in consultation with UNH/TWAC will be responsible for implementation of the WWT national component. UNH/TWAC through UNH/TWAC National City will provide the direction to implementation of existing standards by laws and regulations and therefore following them for the continuity of WWT and building facilities. Some other key facilities will be that people will be required to construct. UNH/TWAC will be responsible for the availability and availability of land provided for construction of WWT and building facilities, and management of public sites.

3.2.3.1. PROJECT OBJECTIVES
The key objectives of the project are:

3.2.3.2. PROJECT MAIN DELIVERABLES

The main deliverables of the project will include:

1. Feasibility studies and implementation of the project;
2. Identification of the project's funding sources, including the identification of the project's funding sources, including the identification of the project's funding sources, including the identification of the project's funding sources;
3. Identification of the project's funding sources, including the identification of the project's funding sources, including the identification of the project's funding sources;
4. Identification of the project's funding sources, including the identification of the project's funding sources, including the identification of the project's funding sources;
5. Identification of the project's funding sources, including the identification of the project's funding sources, including the identification of the project's funding sources;
6. Identification of the project's funding sources, including the identification of the project's funding sources, including the identification of the project's funding sources;
7. Identification of the project's funding sources, including the identification of the project's funding sources, including the identification of the project's funding sources;

3.2.3.3. WSD Steering Committee

The key objective of the project is to establish a WSD Steering Committee (SC) which will be responsible for the project's overall coordination, monitoring, and reporting. The SC will be made up of representatives from the project's funding sources, including the project's funding sources, including the project's funding sources, including the project's funding sources.

The SC will also be responsible for the project's overall coordination, monitoring, and reporting. The SC will be made up of representatives from the project's funding sources, including the project's funding sources, including the project's funding sources, including the project's funding sources.

1. Identifying and securing the project's funding sources;
2. Identifying and securing the project's funding sources;
3. Identifying and securing the project's funding sources;

4. Reporting overall ODFOD initiative progress and performance and providing guidance for improvement (annual)
5. Conduct Reviews as per PFA

2.2.6. Fecal Sludge (FS)

The sludge from water will be a solid substance which will require to be treated for sanitation in low-income settlements. This treatment will require attention to some level higher than that of grey water. This could be through separate tanks or a more robust system to collect, store, pump, and dispose.

Fecal sludge will have to be used for planting and eventually require and manage the community-based resources without dependence on the off-grid solution ODFOD solution PFA will be necessary for:

1. Assessment of necessary equipment to be required
2. Substrate (soil) and distribution in settlement and settlement. Source (transport), storage and use
3. Handling and handling for off-grid sanitation system as a sustainable system and providing guidance to be used in practice of the community
4. Materials, storage, health and training in order of use (initial) government or ODFOD and UNWADA.

2.2.7. Waste Collection

Waste will be responsible for capacity building, education of community, waste collection

ODFOD will conduct with a regular frequency in the low-income areas with an emphasis on waste for the off-grid sanitation. The key role of the off-grid sanitation will be:

1. Building community groups to collect and manage waste processing system with community groups when necessary
2. Assessing community resources to plan and store if required and to set up the necessary waste systems for the community to manage the waste, like water, some method of waste management
3. Establishing a waste analysis and preparing a solution (design, build, implement, operate) and maintenance of the waste collection
4. Preparing relevant approach to coordinate with the community members for compliance for the off-grid sanitation service
5. Sustainable collection of the waste, storage, and usage of off-grid sanitation system

- **Jointly** (JAWASA in partnership with URM (urban municipalities) and National Government) qualified to act as the PMO in operating and managing the completed works.

2.2 SELECTION CRITERIA

JAWASA, in consultation with the Metropolitan Water, Sewerage, Sanitation and Charge will identify contractors which are eligible for the (M&M) facilities subject to the WSP. It is the eligible contractor who will be invited to bid for the PMO. The criteria will include the availability of local resources for the project and the contractor's terms.

Special care must be taken to ensure that the procurement procedure according to the local laws (bidding to suit the interests of other contractors) is applicable. (BIDDING) WSP (it will) cover in this procurement, which should be taken into

The bid evaluation will be the first phase (in planning, permitting and implementing the (M&M) facilities in their cases. A comprehensive review should be given, based on original data and evidence, not from the facts of the planning and implementation.

The results of the ongoing efforts to help the city on the way ahead, will form the basis for the primary efforts by the contractor.

Summary of Institutional Status for Sanitation Practices

Accountability	Policy and guidelines specific to (M&M)
Role	Overall project coordination and implementation support
PMO/MA	Support performance of URM/MA
Urb/MA	Facilitating the establishment and operation of community toilets (CTUs) and the (M&M) and facilitating the development of systems for transportation and treatment of the waste, maintenance and management of public toilets, ensuring the provision of transport
Implementation	Facilitating the operation of (M&M) facilities and toilets, ensuring the proper regulation of waste disposal, facilitating the availability of land for decentralized systems, provide services to provide transport systems
Private sector	Management of infrastructure for transport and treatment, operation
NGOs	Capacity building, establishment of community toilet enterprises

TEA	Notice of Intent (NOI) for effluent disposal
PCMR	Response of Department of Water

6.4 EFFECTIVENESS AND RELIABILITY OF TREATMENT

- 6.1 The plant will become effective on the date of operation for all parties.
- 6.2 The SMC shall remain in force until such Closure of the Sewer WTP (as per Part 6) is mutually agreed by the participants.

7.0 APPENDICES

The SMC may be amended at any time with the written agreement of the participants.

8.0 CONFLICT RESOLUTION

In the event of any differences arising with respect to the provisions of this SMC, the parties will endeavour to find a solution through dialogue and consultation.

9.0 INFORMATION AND NEEDS

- 9.1 The parties to the SMC will attempt to make other all such information in addition to the SMC SMC will be reasonably expected in a timely manner.
- 9.2 Any notices or documents given, made or used by the parties in relation to this SMC will be in writing and will be deemed to have been duly given, made or used in the jurisdiction or province in which it is addressed or delivered to or received by hand, mail, or electronic or any respective address, as listed to the SMC.
- 9.3 Documents hereto may be written, orally or by other means, though the written is preferred. Any notice or request for the Participant or giving such notice will be addressed.
- 9.4 All communications and documents whatsoever may properly and be accepted and to be in the English language.
- 9.5 The following addresses are specified for purposes of this SMC:



Signed by the duly authorized representatives of the parties to the agreement:

Government Secretary Ministry of Water	 The Ministry of Water
Regional Administrator Kiambu District	 The Regional Office
CEO KCCWASA	 The 25, 49-2149
Municipal Director Kiambu	 The
Municipal Director Kiambu	 The
Municipal Director Kiambu	 The
CEO KCCWASA	 The 07/02/2019
Regional Director Kiambu District	 The 07/02/2019
Regional Director Kiambu District	 The 07/02/2019

Appendix IV: Screening Letter from NEMC



THE UNITED REPUBLIC OF TANZANIA
VICE PRESIDENT OFFICE
NATIONAL ENVIRONMENT MANAGEMENT COUNCIL
(NEMC)



Ref: EC/EA/2222/2025

Date: 12th October, 2025

Chief Executive Officer,
Office of Water & Sewerage Authority,
P. O. Box 1222,
Dar es Salaam

Re: SCREENING DECISION OF THE PROJECT BRIEF FOR THE PROPOSED
FECAL SLUDGE TREATMENT PLANT (FSTP) TO BE BUILT AT GOLANI
STREET, KIMBIJI WARD, KILIMBOW DISTRICT, DAR ES SALAAM

Reference is made to the above-mentioned subject.

2. The National Environment Management Council (NEMC) acknowledges receipt of your application attached with a project brief and EIA (Environmental Impact Assessment) Report/Regulation forms for the above project. The project has been registered on 07th September 2025 and assigned with Application Reference Number (ARN) EC/EA/2222/2025. Myself have reviewed the

3. Following the review of the submitted documents, the Council has reviewed a document that was submitted that is a Project Brief Report. This project brief report is provided in October Project Brief which will guide the Council in assessing the project. From the submitted project brief report, the following information must be included to enhance information of the project brief report:

1. Provide your current contact information of the project site including location, phone and internet connectivity etc.
2. Cover page:
 - a. Details of project address of the Council
 - b. Date 'Must' not be less than one (1) year '2025' since inception of '2024' is as per Local Government Authority (LGA) Act and its regulatory legislation.
3. Information on the land ownership must be included in the project brief report.
4. The report should discuss the management of fecal sludge system generated in all phases.
5. EIA and EIA/Regulation forms completed and registered with form of project plans.

Yassin M. Yassin, Director of Project & Environmental Affairs, National Environment Management Council (NEMC)

- ii. Prepare and attach an intelligent and professional layout design for the Detailed Project Report
 - iii. Include in the report terms and conditions of the engagement agreement, experts who conducted the study
 - iv. Detail Environmental Compliance Permit (ECP) and Safety issues (including an Emergency Preparedness and Response Plan)
3. Upon submission of the Detailed Project Report, the Council will arrange for a technical review of the document.
4. Please ensure for the design is in line with Environmental Management Terms and Conditions Requirement, 2017. A permit number for operation will be provided automatically by the water utility once the Detailed Project Report is completed for review.
5. Thank you for your cooperation.


E. T. Mwa
For DIRECTOR GENERAL

Cc: Mr. Humphrey Mwa
P.O. Box 20776
Nairobi, Kenya

Appendix V: Permit to use the Land from the Local Government Authority



JAMHURIA YA MUUNGANO WA TANZANIA
OFISI YA RAIS



KAWALA ZA MACHO NA BERRALI ZA MITIHA

HAIKAMUJUMUI YA MANIPALA KIGAMBOINI

(Kwa maeneo yaliyoitwa kwanza kutokana na historia ya Kigamboni)

Tele: +255 22 2218400
Fax: +255 22 2218400
E-mail: KIDP@kigamboni.go.tz
Web: www.kigamboni.go.tz

A. H. MOSE
KIGAMBOINI
CHK US SALAMA
TANZANIA

Dinaa jibu tafadhali taja:

Nambari: KGMCHM/13/008

Tarehe: 18 Decemba 2021

Alia Mwandaji Mkuu
Mamaza ya Usandamaji Maji na Uvazi wa Mazingira,
P.O. Box 1232,
MUSE SALAMA

**Kwa: IJUMBE YA KUTUMIA ENDO VIMADALA LILILOPO KIBELI KWA KILI YA
UJENO WA SPRAY WA UCHAKATAJI BAJIYAKA**

Tafadhali hukika na kutoa jibu lakini hapa juu:

1. Kwa kuwa jibu ya tarina 071 12021 ambayo ulimba kuoshwa kwenye maboko wa Ferry kwa kili ya ujenzi wa maboko wa kuchakataji maji hizi.
2. Vatakalimu wangu zamani na Viamenzariyotaka DAWASA wiliwaza kutimbia maeneo yaliyopendekera na kichani atakile aniti ilikuwa Mwandaji wa maeneo yote wa Golani kate ya KIMBO kuamba HUKUMU upote vyote kwa kili ya maeneo hizi.
3. Haya hayi kwa kuwa hii kwenye hukumbuzi lakini kuamba Hukumbuzi ya Mamaza ya Kigamboni ulikuwaka kwa kili hapa ulimba wa kichani atakile at, ilikuwa kwa kili ya maeneo yote hizi.
4. Aha, Mamaza hawachika na kwenye kili kama na kuambaa hizi kwa kili ya maeneo hizi.

Kwa hivyo,


Ernest N. Ruvu
MKURUGENZI WA MANIPALA
KIGAMBOINI
(Kwa kili)

Appendix VI: Architectural drawings

GOLANI FAECAL SLUDGE TREATMENT PLANT

- ① FAECAL SLUDGE RECEIVING AND SCREENING UNIT
- ② FAECAL SLUDGE SETTLING AND THICKENING TANKS
- ③ DRYING BEDS
- ④ INTEGRATED SETTLER, ABR & AF
- ⑤ HORIZONTAL FLOW CONSTRUCTED WETLAND
- ⑥ HYDROMECHANICAL SYPHON
- ⑦ VERTICAL FLOW CONSTRUCTED WETLAND
- ⑧ SERVICE BUILDING
- ⑨ POTABLE WATER TANK AND TOWER
- ⑩ TREATED EFFLUENT PUMP STATION
- ⑪ POLISHING POND
- ⑫ BY PRODUCTS RE-USE AREA (TREE NURSERY)
- ⑬ TREATED WATER OVERHEAD TANK

- WASTWEATER/FS PIPE
- EXISTING PATH/ROAD
- FENCE



<p>CLIENT:</p> <p>DAR ES SALAAM WATER SUPPLY & SANITATION AUTHORITY (DAWASA)</p>	<p>CONSULTANTS:</p> <p>DOHWA ENGINEERING CO., LTD DOHWA Engineering CO., LTD IN ASSOCIATION WITH LUPTAN CONSULTS LTD AND WWS</p>	<p>CONTRACTOR:</p> <p>SHANXI CONSTRUCTION ENGINEERING CORPORATION AND MINERAL COMPANY</p>	<p>Project:</p> <p>CONSTRUCTION OF FAECAL SLUDGE TREATMENT PLANTS (FSTP) WORKS IN DAR ES SALAAM</p>	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4">REVISION</th> </tr> <tr> <th>No:</th> <th>Description</th> <th>Made by</th> <th>Date:</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	REVISION				No:	Description	Made by	Date:									<p>Drawing Title</p> <p style="text-align: center;">SITE PLAN - Golani FSTP (120 m3/d)</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>Designed by</td> <td>SHANXI</td> <td>Approved by</td> <td> </td> </tr> <tr> <td>Drawn by</td> <td>SHANXI</td> <td>SHEET No.</td> <td> </td> </tr> <tr> <td>Checked by</td> <td> </td> <td>Scale</td> <td>1:1000</td> </tr> </table>	Designed by	SHANXI	Approved by		Drawn by	SHANXI	SHEET No.		Checked by		Scale	1:1000	<p>Drawing No:</p> <p>FSTP- 108 /SITE PLAN REV02</p> <p>Date:</p> <p>September - 2024</p>
REVISION																																		
No:	Description	Made by	Date:																															
Designed by	SHANXI	Approved by																																
Drawn by	SHANXI	SHEET No.																																
Checked by		Scale	1:1000																															

APPENDIX VII: Geotechnical Report



**SHANXI CONSTRUCTION
ENGINEERING CORPORATION
AND MINERAL COMPANY**

GEOTECHNICAL REPORT

FOR

**THE PROPOSED CONSTRUCTION OF FAECAL SLUDGE
TREATMENT PLANTS (FSTP) WORKS IN DAR ES SALAAM**

PREPARED FOR:

DAR ES SALAAM WATER SUPPLY & SANITATION AUTHORITY (DAWASA)

P.O. BOX 1573

DAR ES SALAAM

January 3, 2024

TABLE OF CONTENTS

1.0 EXECUTIVE SUMMARY	1
2.0 INTRODUCTION.....	1
2.1 Antecedents.....	1
2.2 Objectives	2
2.3 Scope.....	2
2.4 Site and Project Description.....	2
2.4.1 Site Location and Description.....	2
2.4.2 General Project Description	3
3.0 FIELDWORK	4
3.1 General.....	4
3.2 Code of Practice	4
3.3 Methodology	4
3.2.1 Geodetic Coordinates of the Sampling Points	4
3.2.2 Drilling	5
3.2.2.1 Equipment	5
3.2.2.2 Standard Penetration Test	5
3.2.2.3 Borehole Sampling.....	6
3.2.3 Geological Logging of Soils and Rocks	7
4.0 GEOLOGY AND SITE SUBSURFACE CONDITIONS.....	7
4.1 Geology of Tanzania.....	7
4.2 Local Subsurface Conditions	8
4.2.1 Summary of Stratigraphy.....	8
4.2.2 Ground Water.....	9
5.0 ANALYSIS AND DISCUSSION OF TEST RESULTS	9
5.1 Field Tests.....	9
5.1.1 Standard Penetration Test	9
5.2 Laboratory Tests	13
5.2.1 Atterberg Limits.....	13
5.2.1.1 Plasticity Index.....	14
5.2.1.2 Plastic Limit	14

5.2.1.3	Liquid Limit	14
5.2.2	Particle Size Distribution	15
5.2.3	Bulk Density and Moisture Content	16
5.2.4	Direct Shear Parameters.....	17
5.2.5	Unconsolidated Undrained Triaxial Test.....	17
5.2.6	One Dimensional Consolidation	18
6.0	RECOMMENDATIONS.....	20
6.1	General.....	20
6.2	Geotechnical Model.....	21
6.3	Bearing Capacity for Shallow Foundations	21
6.4	Excavation.....	25
6.5	Backfill and Reuse of Excavated Spoil.....	25
7.0	CONCLUSION	26
8.0	LIMITATIONS.....	26
APPENDIX I – Logs and Cross Section		27
	Borehole Logs.....	28
	Geotechnical Cross Section	36
APPENDIX II – Sample Photographs		37
APPENDIX III – References.....		45
	References.....	46
APPENDIX IV – Laboratory Test Reports.....		47

LIST OF TABLES

Table 1 - Geodetic coordinates at the drill points	4
Table 2 – Borehole water levels at completion of drilling.....	9
Table 3 - Summary and interpretation of SPT N-values.....	11
Table 4 - Bearing capacity of soil as computed from corrected N-values.....	12
Table 5 - Laboratory tests performed on soil samples	13
Table 6 - Ratings for compressibility based on liquid limit (Mills et al. 1980).....	14
Table 7 – Atterberg parameters.....	15
Table 8 – Sieve analysis results	16

Table 9 - Summary of soil densities.....	16
Table 10 - Summary of direct shear parameters	17
Table 11 - Undrained shear parameters	18
Table 12 - Summary of consolidation parameters	20
Table 13 - Bearing capacity calculation results	24
Table 14 – Recommended design pressures	24

LIST OF FIGURES

Figure 1 - Satellite image of the project site indicating the locations of the boreholes	3
Figure 2 – SPT Testing at borehole PtE.....	6
Figure 3 - Simplified geological map of Tanzania (Modified from Hester, 1998).....	8
Figure 4 - Chart of bearing capacity factors.....	25

1.0 EXECUTIVE SUMMARY

At the request of DAWASA, SHANXI CONSTRUCTION ENGINEERING CORPORATION AND MINERAL COMPANY recently completed a geotechnical survey that entailed the advancement of 7 No. sampled boreholes at the proposed site for construction of Faecal Sludge Treatment Plants (FSTP) Works at Golani in Dar Es Salaam.

Each of the boreholes was advanced to 10 m below existing ground level. The boreholes encountered alternating layers of clay and sand.

Based on the data obtained from our subsurface exploration, the prevalent soil type is sand. The sand is considered suitable for the support of shallow foundations.

This summary should be used in conjunction with the entire report for design purposes. It should be recognized that full details are not provided in this section, and the report must be read in its entirety for a comprehensive understanding of the items highlighted herein.

2.0 INTRODUCTION

2.1 Antecedents

This report presents the findings of the recently completed geotechnical investigation in support of the proposed construction of a Faecal Sludge Treatment Plants (FSTP) in Dar Es Salaam. The work was commissioned by The Dar Es Salaam Water Supply & Sanitation Authority (DAWASA) and executed by Shanxi Construction Engineering Corporation and Mineral Company.

The purpose of the investigation was to determine the subsoil stratification at the proposed plant site and assess the suitability of existing subsoil materials for foundation support.

The geotechnical investigation, which was completed in September 2023, mainly entailed the rotary drilling of 7 No. geotechnical boreholes (each to a maximum depth of 10 m below existing ground level) at the proposed site, sample collection and laboratory testing of the recovered samples.

This report encompasses the results of the geotechnical investigation and based on this information, it provides geotechnical recommendations relating to the general design of the

proposed foundations. This document also contains brief descriptions of the investigation methods used to acquire the factual data reported herein.

This report should be read in conjunction with “Limitations of the Report” which is appended following the text of the report. The reader’s attention is specifically drawn to this information, as it is essential that it is followed for the proper use and interpretation of this report.

2.2 Objectives

The following were the main objectives of the geotechnical survey:

- a) Determine the subsurface stratigraphy to the full depths of the boreholes.
- b) Provide lithological descriptions of the stratigraphic units encountered in the boreholes.
- c) Evaluate the engineering characteristics of the subsurface materials through in situ and laboratory tests.
- d) Provide an interpretative geotechnical report for the site.

2.3 Scope

To fulfil the abovementioned objectives, the completed scope of the survey is as follows:

- a) Rotary drilling, sampling and logging of 7 No. geotechnical boreholes, each to a depth of 10 m below ground level (bgl).
- b) Execution of Standard Penetration Tests (SPT) on soils and unconsolidated deposits encountered in the boreholes.
- c) Laboratory testing of representative soil samples.
- d) Preparation of this engineering report that outlines field methodologies, documents findings and provides clear geotechnical recommendations based on engineering analysis of the data, our experience and acceptable engineering practice.

2.4 Site and Project Description

2.4.1 Site Location and Description

The proposed plant site is located along an access road in Kimbiji administrative ward of the Dar es Salaam Region of Tanzania.

The ground elevation at the site was measured and found to range between 33.46 m and 40.16 m above mean sea level.

Figure 1 below presents a satellite map of the project site, indicating the geographic locations of the 7 No. drill points.




Figure 1 - Satellite image of the project site indicating the locations of the boreholes

2.4.2 General Project Description

The FSTP project will include construction of the following structures:

- Receiving & screening unit
- Settling-thickening tanks
- Drying beds
- Integrated settler
- Horizontal & vertical flow constructed wetland,
- hydro-mechanical siphon
- Potable water & treated wastewater tank and tower,
- Pump station,
- Service building, and,

- Polishing pond.

3.0 FIELDWORK

3.1 General

The geotechnical field investigation was executed in the period between 9th and 19th September, 2023 and consisted of 7 No. boreholes. The field work was conducted under the supervision of competent personnel, who maintained detailed field records of the various soil strata and groundwater conditions encountered.

3.2 Code of Practice

The requirements given in British Standard BS 5930:2015 (Code of Practice for Site Investigations) were used as a general guide for carrying out the survey.

3.3 Methodology

3.2.1 Geodetic Coordinates of the Sampling Points

The placed geodetic coordinates at the drill points are tabulated below:

Hole ID	Investigated Depth (m)	Placed Coordinates (WGS84, Zone 37 S)		Elevation (masl)
		Easting	Northing	
PtB (or BH1)	10	557138.83	9225884.84	38.11
PtC (or BH2)	10	557287.90	9225836.81	33.46
PtD (or BH3)	10	557215.72	9225813.90	34.40
PtG (or BH4)	10	557210.92	9225708.41	35.20
PtF (or BH5)	10	557150.84	9225765.97	35.00
PtE (or BH6)	10	557054.06	9225815.93	36.97
PtA (or BH7)	10	557069.42	9225905.88	40.16

Table 1 - Geodetic coordinates at the drill points

3.2.2 Drilling

3.2.2.1 Equipment

The boreholes were advanced using a XY-1 rotary drilling rig equipped with augers, core barrels and standard SPT equipment. The drilling equipment also included a mud pump which was used to impel drilling water into the borehole to cool the diamond bit as it advanced through hard strata as well as flush out cuttings from the bottom of the borehole.

3.2.2.2 Standard Penetration Test

Standard Penetration Tests (SPT) were performed in the soil and unconsolidated strata encountered in the boreholes. The dynamic test entailed the driving of a split spoon sampler into the soil layer at the bottom of the borehole by dropping a standard weight (63.5 kg), automatic trip hammer through a standard distance (760 mm). This was followed by recording of the number of blows (N) required to achieve 300 mm penetration (in 150 mm increments) after an initial seating drive of 150 mm or 25 blows, whichever was achieved first. The standard test termination criteria for SPT testing was as follows:

- When the full test drive (300 mm) was achieved, or;
- When a limiting blow count of 50 (N=50), also referred to as penetration ‘refusal’, was reached. The test was also concluded as refusal when no penetration was achieved after several impacts of the hammer.

Based on data summarized by Skempton (1986), the generalized energy ratio (E_r) for our auto-trip hammer is 80%. The equation below can be used to acquire corrected N-values which is dependent on rod length ($C_r = 0.75$), sampler type ($C_s = 1.0$) and hole diameter ($C_d = 1.0$). These correction factors have been adapted from BS (2011).

$$N_{corr} = N \frac{E_r}{60} \times 0.75$$

Note that in this case the corrected N-values are equivalent to the raw field N-values. A tabulated summary of the SPT test results is provided in subsection 5.1.1 of this report.



Figure 2 – SPT Testing at borehole PtE

3.2.2.3 Borehole Sampling

i. Core Sampling

The boreholes were generally advanced using the coring technique. After being carefully extracted from the core barrels, soil and rock cores were placed into grooved, wooden core boxes ensuring that the original depth orientation of each sample was maintained. The typical core box was divided into five grooves, each groove with adequate dimensions for containing one metre of the core section at full recovery. Each core box was labelled to indicate the site name, borehole number, core runs and date of sampling. Colour photographs of the core boxes populated with samples are provided in Appendix II.

ii. Undisturbed Sampling

Relatively undisturbed soil samples were acquired from the SPT sampler.

3.2.3 Geological Logging of Soils and Rocks

Field logging was performed by a qualified engineer who was stationed at the site for the entire duration of the works. Soil samples were subjected to visual-manual inspection to develop material descriptions conforming to BS 5930.

4.0 GEOLOGY AND SITE SUBSURFACE CONDITIONS

4.1 Geology of Tanzania

Numerous studies on tectonics of the region have shown that the many mechanisms for rifting and the tectonic history of rifting is quite complex (Dawson, 2008). On regional scales four major tectonic provinces have been recognized: the western system (Ubendian system), central system (Tanzanian craton partial covered by Dodoma system), mobile Usagaran system and eastern continental and marine sedimentary rocks of Lower Jurassic to Quaternary (Figure 4). The stable Tanzania craton consist of Archean rocks which are granitic complexes, Dodoma system and greenstone belt. The eastern extension of this underlies Mozambique belt contained deformed metasedimentary rocks and intrusions.

The area is characterized by folds and thrusts verging eastward from the orogenic belt. The same characteristic is perceived in the Ubendian system. The Ubendian system comprises of high grade metamorphic rocks of sedimentary and igneous origin. The rocks include granulite, amphibolite, migmatite, gneiss, schist, quartzites and marble. The metamorphic grade of Ubendian system is mainly amphibolite or granulite facies. The usagaran system contains rocks of Paleoproterozoic age that were deposited in geosynclinal troughs. The usagaran system comprises sedimentary rocks and volcanic rocks. In the coast regions and in the parts of the rift, the Mesozoic rocks occur. The Mesozoic sedimentary rocks are alternating transgressive and regressive sequence. The rocks comprise of sandstones, siltstones, mudstone, coral limestones and silty shales. The Cenozoic period consist of sediments and volcanic eruption occurred in several parts of Tanzania. The Neogene volcanic which most occur within East African rift valley overlie Precambrian rocks in the southwest and north eastern part of the

country. The quaternary period is characterized by deposition and erosion cycles related to mainly sea level, climate changes and tectonics.




Figure 3 - Simplified geological map of Tanzania (Modified from Hester, 1998)

4.2 Local Subsurface Conditions

The details of the subsurface conditions encountered during our investigation are presented on the borehole logs and cross section provided in Appendix I. The generalized subsurface profile at the drilling points, as inferred from the subsurface exploration data, is summarized below.

4.2.1 Summary of Stratigraphy

The boreholes encountered soil material from ground level to the maximum depth of investigation of 10 m bgl. The subsoil comprises of alternating layers of very stiff to hard CLAY and medium dense to dense SAND. The predominant soil material at the site is sand.

4.2.2 Ground Water

The table below presents a record of the final water levels measured in the boreholes. Due to the influence of drilling water, these levels do not represent the full equilibrium condition. Different water levels should be expected during construction.

Hole ID	Water Level (m)
BH1	2.2
BH2	1.0
BH3	2.2
BH4	2.0
BH5	1.7
BH6	0.0
BH7	0.5

Table 2 – Borehole water levels at completion of drilling

5.0 ANALYSIS AND DISCUSSION OF TEST RESULTS

5.1 Field Tests

5.1.1 Standard Penetration Test

The table below provides a summary and interpretation of the N-values from the SPT test. It should be noted that since the efficiency of the SPT hammer is 80%, the overall correction factor calculates to 1, i.e. field values are equivalent to corrected values.

Hole ID	Depth (m)		N-value	N_{corr}
	From	To		
BH1	1.5	1.95	14	14
BH1	3	3.45	29	29
BH1	4.5	4.95	31	31
BH1	6	6.45	41	41
BH1	7.5	7.95	42	42

BH1	10	10.45	42	42
BH2	1.5	1.95	14	14
BH2	3	3.45	23	23
BH2	4.5	4.95	27	27
BH2	6	6.45	29	29
BH2	7.5	7.95	32	32
BH2	10	10.45	32	32
BH3	1.5	1.95	24	24
BH3	3	3.45	22	22
BH3	4.5	4.95	38	38
BH3	6	6.45	40	40
BH3	7.5	7.95	41	41
BH3	10	10.45	30	30
BH2	1.5	1.95	22	22
BH2	3	3.45	15	15
BH2	4.5	4.95	20	20
BH2	6	6.45	20	20
BH2	7.5	7.95	30	30
BH2	10	10.45	32	32
BH5	1.5	1.95	18	18
BH5	3	3.45	26	26
BH5	4.5	4.95	23	23
BH5	6	6.45	19	19
BH5	7.5	7.95	24	24
BH5	10	10.45	20	20
BH6	1.5	1.95	21	21
BH6	3	3.45	18	18
BH6	4.5	4.95	22	22
BH6	6	6.45	22	22

BH6	7.5	7.95	29	29
BH6	10	10.45	32	32
BH7	1.5	1.95	16	16
BH7	3	3.45	28	28
BH7	4.5	4.95	31	31
BH7	6	6.45	30	30
BH7	7.5	7.95	35	35
BH7	10	10.45	31	31

Table 3 - Summary and interpretation of SPT N-values

Bowles (1997) recommended the following equations [adopted from Terzaghi and Peck (1967) and Meyerhof (1956, 1974)] to compute the bearing capacity of soils:

$$q_a = \frac{N_{corr}}{F_1} \times K_d \quad \text{for } B \leq F_4$$

$$q_a = \frac{N_{corr}}{F_2} \left(\frac{B+F_3}{B}\right)^2 \times K_d \quad \text{for } B > F_4$$

Where,

q_a = Allowable bearing capacity for 25 mm settlement,

N_{corr} = Statistical average of corrected N-value between $0.5B$ above foundation and $2B$ below foundation,

B = Foundation width,

D = Foundation depth,

$$K_d = 1 + 0.33 \frac{D}{B} \leq 1.33$$

F_1, F_2, F_3, F_4 = Factors for 80% efficiency hammer (N_{80}) which are 0.033, 0.046, 0.3 and 1.2 respectively. It should be noted that factors F_1 and F_2 have been linearly extrapolated from existing N_{55} and N_{70} factors documented by Bowles while factors F_3 and F_4 remain the same.

The equations above assume 25 mm settlement. In general, the allowable pressure (q'_a) for any settlement (ΔH) can be computed as:

$$q'_a = \frac{\Delta H}{25} \times q_a$$

The table below presents a summary of the allowable bearing pressures for footings of various widths founded on the in situ soil at 1.5 m, 2 m, 2.5 m and 3 m bgl.

Foundation Details		K_d	q_a (kN/m ²)	q_r (kN/m ²)
D (m)	B (m)			
1.0	1.0	1.33	742	371
	1.5	1.22	802	401
	2.0	1.17	770	385
	2.5	1.13	710	355
	3.0	1.11	701	350
1.5	1.0	1.33	846	423
	1.5	1.33	874	437
	2.0	1.25	825	412
	2.5	1.20	784	392
	3.0	1.17	735	368
2.0	1.0	1.33	846	423
	1.5	1.33	958	479
	2.0	1.33	879	440
	2.5	1.26	827	414
	3.0	1.22	834	417
2.5	1.0	1.33	927	463
	1.5	1.33	958	479
	2.0	1.33	918	459
	2.5	1.33	870	435
	3.0	1.28	872	436
3.0	1.0	1.33	1008	504
	1.5	1.33	1041	520
	2.0	1.33	994	497
	2.5	1.33	943	471
	3.0	1.33	910	455

N-value taken as statistical average between 0.5B above footing of width B, to 2B below the footing

Table 4 - Bearing capacity of soil as computed from corrected N-values

In view of the fact that Bowles' method scales up Terzaghi's values by about 50%, we have applied a safety factor of 2 to the computed values of q_a to acquire the recommended design value, q_r , listed above.

5.2 Laboratory Tests

Select soil samples recovered from the boreholes were subjected to a program of laboratory tests based on review of sample composition, sample size and to fulfill the general requirements of the contract.

The following subsections present a summary of the parameters directly acquired and/or inferred from the test results. Comprehensive backup sheets of the tests are provided in Appendices and should be concurrently referred to when reading this section.

The table below presents a list of the completed laboratory tests.

Material	Test	No. of Tests
Soils	Atterberg Limits	5
	Sieve Analysis	9
	Bulk Density and Natural Moisture Content	13
	Direct Shear Test	7
	Unconsolidated Undrained Triaxial Shear	6
	One-Dimensional Consolidation	8

Table 5 - Laboratory tests performed on soil samples

5.2.1 Atterberg Limits

The Atterberg tests were performed to investigate whether the soils at the site exhibit the proper consistency to support the proposed structures even as their moisture levels change. Atterberg limit tests are classification tests that determine the liquid limit (LL) and plastic limit (PL) of the soil fraction finer than the No. 40 (0.425 mm) sieve.

Liquid limit is the moisture content at which a soil passes from the liquid to the plastic state and is directly proportional to the compressibility of soil. A cone penetrometer, which

correlates liquid limit to the penetration of a freely falling calibrated cone, was used to determine the liquid limits of the soil specimens.

Plastic limit, defined the moisture content at which a fine-grained soil can no longer be remolded without cracking, was determined by measuring the water content when threads of soil (3 mm in diameter) began to crumble.

Plasticity index (PI), which is essentially the difference between the liquid and plastic limits, indicates the degree of plasticity or the magnitude of the water content over which the soil remains plastic. Since plasticity is attributed to clay, cohesionless soils have no plasticity phase, and therefore their PI is zero.

5.2.1.1 Plasticity Index

The plasticity indices of the test samples were found to range from 22% to 37%, implying highly plastic soil. The plasticity description is based on the qualitative plasticity classification proposed by Burmister (1949).

5.2.1.2 Plastic Limit

The data indicates a range of plastic limits between 15% and 17%.

5.2.1.3 Liquid Limit

The liquid limits of the test samples were determined to vary between 39% to 56%. The table below presents the relationship between liquid limit and degree of compressibility as proposed by Mills *et al.* (1980).

Rating	Liquid Limit (%)	Degree of Compressibility
Low	< 45	Low
Medium	45 – 55	Medium
High	55 – 75	High
Very High	> 75	Very High

Table 6 - Ratings for compressibility based on liquid limit (Mills *et al.* 1980)

Based on the average liquid limit of 46%, the soil at the site is interpreted to have a medium degree of compressibility.

The following is a tabulated summary of the Atterberg limits test results discussed above.

Hole ID	Depth (m)		Liquid Limit	Plastic Limit	Plastic Index
	From	To			
BH1	3.00	3.45	41	15	26
BH6	1.50	1.95	56	17	39
BH7	6.00	9.00	54	17	37
BH7	4.50	4.95	40	17	23
BH7	1.50	1.95	39	17	22

Table 7 – Atterberg parameters

5.2.2 Particle Size Distribution

Particle size distribution analysis evaluates the relative portions of different sizes of soil particles. From this, it is possible to determine whether the soil consists of predominantly gravel, sand, silt or clay sizes and, to a limited extent, which of these size ranges is likely to control the engineering properties of the soil.

Representative soil specimens were analyzed for particle size distribution through wet sieving. The grading test results concur with the borehole logs by indicating prevalence of granular soil at the project site. As indicated on the table below, the recorded fines (< 0.063 mm) from the sieve test range from 3% to 44% averaging at 20%.

Hole ID	Depth (m)		Fines (%) (< 0.063mm)	Sand (%) (0.063 – 2 mm)	Gravel (%) (2mm – 60 mm)
	From	To			
BH1	3.0	6.0	3	97	0
BH2	0.0	3.0	34	66	0
BH2	3.0	6.0	27	71	2
BH2	6.0	9.0	21	77	2
BH3	6.0	9.0	7	93	0
BH4	3.0	6.0	5	93	2
BH4	6.0	9.0	35	63	2
BH5	6.0	9.0	44	56	0
BH6	6.0	9.0	7	93	0

Table 8 – Sieve analysis results

5.2.3 Bulk Density and Moisture Content

The bulk densities (ρ) of the SPT soil samples were determined through direct measurements. The samples were then examined for natural moisture content (w) by oven-drying at 110 °C and expressing the mass lost after drying as a percentage of the resulting dry soil mass. Finally, the dry density (ρ_d) of the samples were calculated from their bulk densities and moisture contents using the equation below:

$$\rho_d = \frac{\rho}{1 + w}$$

The density test results are tabulated below:

Hole ID	Depth (m)		Bulk Density (kg/m ³)	Bulk Unit Weight (kN/m ³)	Dry Density (kg/m ³)	Dry Unit Weight (kN/m ³)	Moisture Content (%)
	From	To					
BH1	0.0	3.0	1987	19.49	1965	19.28	1.1
BH2	1.5	1.95	1980	19.42	1675	16.43	18.2
BH2	-	-	1962	19.25	1736	17.03	13.0
BH2	10.0	10.45	1937	19.00	1616	15.85	19.9
BH3	4.5	4.95	1909	18.73	1716	16.83	11.2
BH3	10.0	10.45	1966	19.29	1873	18.37	5.0
BH4	1.5	1.95	2072	20.33	1794	17.60	15.5
BH4	10.0	10.45	1970	19.33	1276	12.52	54.4
BH5	4.5	4.95	2037	19.98	1637	16.06	24.4
BH6	1.5	1.95	1979	19.41	1736	17.03	14.0
BH6	4.5	4.95	1983	19.45	1753	17.20	13.1
BH7	1.5	1.95	2031	19.92	1815	17.81	11.9
BH7	4.5	4.95	2073	20.34	1745	17.12	18.8

Table 9 - Summary of soil densities

5.2.4 Direct Shear Parameters

The shear strength of a soil is controlled by the effective stress that acts upon it. Disturbed soil samples were remolded and tested for the drained (effective) shear parameters: cohesion (c') and the angle of internal friction (ϕ').

The typical test specimen was placed in a shear box apparatus and subjected to a constant vertical pressure while a horizontal force was applied to the setup such that the specimen sheared in half along a failure plane guided by the two halves of the shear box and failure occurred within about 5 minutes (rate of about 0.01 mm/min). A summary of the direct shear tests is provided below:

Hole ID	Depth (m)		Shear Parameters	
	From	To	ϕ ($^{\circ}$)	c (kN/m ²)
BH1	0.0	3.0	33.7	18.47
BH2	0.0	3.0	33.7	28.79
BH3	0.0	3.0	32.2	25.04
BH3	3.0	6.0	32.7	29.08
BH6	0.0	3.0	30.0	35.26
BH4	2.8	3.0	30.1	21.21
BH4	3.0	6.0	27.8	29.83

Table 10 - Summary of direct shear parameters

5.2.5 Unconsolidated Undrained Triaxial Test

In triaxial tests, a cylindrical soil specimen with a height approximately equal to twice its diameter is placed in a triaxial cell and subjected to three stresses at right angles to each other. The test consists of two phases, the consolidation phase and the shear phase.

The UU (Q) triaxial test was performed on undisturbed soil samples. In the test, each specimen (assumed saturated) was first subjected to a confining pressure and then the principal stress difference applied immediately without permitting drainage (i.e. no consolidation) at any phase of the test. In this case, the applied confining pressure was not entirely carried by the soil skeleton but rather also resulted in an increase in pore water pressure. Since the pore and back

pressures are not measured in the UU test, the results have been interpreted in terms of total stress over a confinement pressure. The UU test was repeated for three different confining pressures and the results are summarized below:

Hole ID	Depth (m)		Undrained Shear Parameters	
	From	To	Angle of Shear Resistance, ϕ_u (°)	Cohesion, c_u (kN/m ²)
BH1	3.0	6.0	11.8	10.9
BH2	9.0	9.45	21.0	25.7
BH3	0.0	3.0	22.8	12.36
BH4	3.0	6.0	20.6	18.8
BH5	0.0	3.0	22.8	12.38
BH6	0.0	3.0	21.0	18.4

Table 11 - Undrained shear parameters

5.2.6 One Dimensional Consolidation

The objective of the consolidation test was to determine the compressibility characteristics of the soil found at the site. The test entailed determination of the magnitude and rate of the consolidation of a saturated or near-saturated specimen of soil in the form of a disc confined laterally, subjected to vertical axial pressure, and allowed to drain freely from the top and bottom surfaces. The consolidation test was performed on undisturbed soil specimens.

Each test sample was loaded axially in increments, whereby each stress increment was held constant until the primary consolidation was complete. The following table provides the results of the consolidation testing including the inferred settlement parameters. The settlement parameters listed in the table are defined below:

σ = Pressure increment (kN/m²)

M_v = Coefficient of volume compressibility (m²/MN)

e = Voids ratio

E_{oed} = Oedometer Modulus (kN/m²)

Hole ID	Depth (m)		σ	M_v	Description	E_{oed}	e
	From	To					

BH1	0.0	3.0	0	-	-	-	0.32
			25	0.54	High	1.9	0.30
			25	0.59	High	1.7	0.28
			50	0.37	High	2.7	0.26
			100	0.17	Medium	5.9	0.24
			200	0.10	Low	10.0	0.22
			400	-	-	-	0.19
BH2	0.0	3.0	0	-	-	-	0.48
			25	0.56	High	1.8	0.45
			25	0.59	High	1.7	0.43
			50	0.37	High	2.7	0.41
			100	0.18	Medium	5.6	0.38
			200	0.10	Low	10.0	0.36
			400	-	-	-	0.33
BH2	3.0	6.0	0	-	-	-	0.34
			25	0.40	High	2.5	0.31
			25	0.49	High	2.0	0.30
			50	0.28	Medium	3.6	0.28
			100	0.16	Medium	6.3	0.26
			200	0.09	Low	11.1	0.24
			400	-	-	-	0.22
BH3	0.0	3.0	0	-	-	-	0.44
			25	0.52	High	1.9	0.41
			25	0.80	High	1.3	0.39
			50	0.44	High	2.3	0.37
			100	0.23	Medium	4.3	0.34
			200	0.12	Medium	8.3	0.31
			400	-	-	-	0.27
BH3	3.0	6.0	0	-	-	-	0.61
			25	0.55	High	1.8	0.58
			25	0.85	High	1.2	0.56

			50	0.44	High	2.3	0.53
			100	0.31	High	3.2	0.49
			200	0.18	Medium	5.6	0.45
			400	-	-	-	0.39
BH4	0.0	3.0	0	-	-	-	0.63
			25	1.00	High	1.0	0.56
			25	1.23	High	0.8	0.52
			50	0.60	High	1.7	0.47
			100	0.32	High	3.1	0.43
			200	0.16	Medium	6.3	0.39
			400	-	-	-	0.34
BH5	3.0	6.0	0	-	-	-	0.63
			25	0.38	High	2.6	0.61
			25	0.60	High	1.7	0.60
			50	0.43	High	2.3	0.57
			100	0.30	Medium	3.3	0.54
			200	0.15	Medium	6.7	0.49
			400	-	-	-	0.45
BH6	0.0	3.0	0	-	-	-	0.43
			25	0.41	High	2.4	0.41
			25	0.66	High	1.5	0.40
			50	0.38	High	2.6	0.38
			100	0.29	Medium	3.4	0.35
			200	0.13	Medium	7.7	0.31
			400	-	-	-	0.28

Table 12 - Summary of consolidation parameters

6.0 RECOMMENDATIONS

6.1 General

The recommendations and conclusions provided herein are based on the following:

- General observations made during field exploration,
- Field and laboratory test results,
- Experience with similar conditions at other sites, and
- Research of generally accepted geotechnical engineering principles and practices.

It should be noted that all interpretations of geotechnical data involve a degree of uncertainty because of the differing origins, inherent variability, and innumerable complexities associated with natural materials. If the encountered subsurface conditions differ from those forming the basis of our recommendations, we should be informed in order to assess the need for amendments.

6.2 Geotechnical Model

Field logs and laboratory sieve analysis confirm that the prevalent soil type at the site is sand soil.

6.3 Bearing Capacity for Shallow Foundations

Typical size (1 m to 3.0 m) spread and strip foundations, both embedded to typical depths between 1.2 m and 3 m below ground level, were considered for bearing capacity analysis using the equations below based on the classic theories by Terzaghi (1943) and the average soil parameters as obtained from laboratory tests.

Strip footings:
$$q_u = cN_c + \gamma D_f N_q + 0.5\gamma B N_\gamma$$

Square foundations:
$$q_u = 1.3cN_c + \gamma D_f N_q + 0.4\gamma B N_\gamma$$

Rectangular foundations:
$$q_u = cN_c \left(1 + 0.3 \frac{B}{L}\right) + \gamma D_f N_q + 0.5\gamma B N_\gamma \left(1 - 0.2 \frac{B}{L}\right)$$

Where,

q_u = Ultimate bearing capacity

c = Soil cohesion

\emptyset = Angle of internal friction

γ = Effective unit weight of soil

B = Width of the foundation

L = Length of the foundation

D_f = Foundation depth

N_c, N_q, N_γ = Terzaghi's bearing capacity factors for general shear failure (see Figure 4)

A factor of safety (F.O.S) of 6 was used to compute the allowable bearing capacity (q_a) from the ultimate capacity. The calculation results are tabulated below:

Foundation Details				q_a (kN/m ²)
Type	D_f (m)	B (m)	L (m)	
Strip	1.2	1.2	>>1.2	333
		1.5	>>1.5	353
		2.0	>>2.0	373
		2.5	>>2.5	393
		3.0	>>3.0	413
	1.5	1.2	>>1.2	359
		1.5	>>1.5	379
		2.0	>>2.0	399
		2.5	>>2.5	419
		3.0	>>3.0	440
	2.0	1.2	>>1.2	402
		1.5	>>1.5	422
		2.0	>>2.0	443
		2.5	>>2.5	463
		3.0	>>3.0	483
	2.5	1.2	>>1.2	446
		1.5	>>1.5	466
		2.0	>>2.0	486
		2.5	>>2.5	506
		3.0	>>3.0	526
	3.0	1.2	>>1.2	489
		1.5	>>1.5	509
		2.0	>>2.0	530

		2.5	>>2.5	550
		3.0	>>3.0	570
Spread	1.2	1.2	1.2	381
		1.5	1.5	397
		2.0	2.0	413
		2.5	2.5	429
		3.0	3.0	446
	1.5	1.2	1.2	407
		1.5	1.5	423
		2.0	2.0	439
		2.5	2.5	455
		3.0	3.0	472
	2.0	1.2	1.2	450
		1.5	1.5	467
		2.0	2.0	483
		2.5	2.5	499
		3.0	3.0	515
	2.5	1.2	1.2	494
		1.5	1.5	510
		2.0	2.0	526
		2.5	2.5	542
		3.0	3.0	559
	3.0	1.2	1.2	537
		1.5	1.5	554
		2.0	2.0	570
		2.5	2.5	586
		3.0	3.0	602
<u>Parameters used:</u>				

$c = 26.81$ (kN/m ²)	- Average of cohesion from direct shear tests
$\phi = 31.45^\circ$	- Average of friction angle from direct shear tests
$\gamma = 19.53$ (kN/m ³)	- Average of bulk unit weight
$N_c = 42.05$	- Acquired from chart of bearing capacity factors
$N_q = 26.72$	- Acquired from chart of bearing capacity factors
$N_\gamma = 24.82$	- Acquired from chart of bearing capacity factors

Table 13 - Bearing capacity calculation results

The bearing capacities of strip and square foundations of intermediate dimensions and/or founded at intermediate depths can be acquired from linear interpolation of the respective values above.

Due to the many possible combinations of length (L) width (B) and depth (D_f) for rectangular foundations, our analysis does not provide bearing capacities for the same. However, the designer can incorporate our soil parameters into the provided equation for rectangular foundations and compute the bearing capacity of the desired configuration of the rectangular foundation. Generally, the bearing capacity of rectangular foundations computed using the classic equations lies between that for similar width strip and spread footings.

The table below presents our recommended design bearing pressures for strip and spread foundations of widths not exceeding 3 m.

Depth (m)	Design Bearing Capacity (kN/m ²)
1.2	330
1.5	355
2.0	420
2.5	445
3.0	485

Table 14 – Recommended design pressures




Figure 4 - Chart of bearing capacity factors

6.4 Excavation

The silty soil at the site can be categorized as Type B to Type C soil according to OSHA (Occupational Safety and Health Administration, USA). Therefore, battered slopes of 1.5H:1V are considered safe when excavating the in situ soil to depths not exceeding 6 m (and above water table). Shoring systems will be required to support excavations extending below the static ground water level.

6.5 Backfill and Reuse of Excavated Spoil

It has been established that the soil at the site consists of both fine and coarse soil, with the latter being predominant. The ‘mixed’ soil is therefore not recommended for reuse as engineering/structural fill.

Instead, granular and non-expansive soil (preferably SC soil) of consistent soil structure can be imported for use as structural backfill. The engineering fill should be placed in 150 mm lifts and compacted to at least 95% of its Standard Proctor maximum dry density. Alternatively, the excavated areas can also be backfilled with selected approved hard-core.

7.0 CONCLUSION

The subsoil condition at the site is primarily granular and suitable for the support of shallow foundations.

8.0 LIMITATIONS

This report was prepared by SHANXI CONSTRUCTION ENGINEERING CORPORATION AND MINERAL COMPANY for the exclusive use of DAWASA. The intent of the report was to provide geotechnical engineering information on the subsurface to support the design and construction of the proposed faecal sludge treatment plant, and not for other purposes. The report is site specific and not applicable to any other property.

This assessment has been carried out using engineering analysis methods consistent with those ordinarily exercised by SHANXI CONSTRUCTION ENGINEERING CORPORATION AND MINERAL COMPANY and other engineering practitioners, working under similar conditions and subject to the time, financial and physical constraints applicable to this project. It must be recognized that there are risks whenever engineering or related disciplines are applied to identify subsurface conditions. A comprehensive sampling and testing programme implemented in accordance with the most stringent level of care may fail to detect certain conditions.

It must also be recognized that the passage of time, natural occurrences, and direct or indirect human intervention at or near the site have the potential to alter subsurface conditions. Therefore, the findings of this geotechnical investigation are valid for the design of the proposed plant assuming no significant time gap between the investigation and actual construction.

Professional judgement was exercised in gathering and analyzing the information reported in this document. The conclusions presented in this report are the product of professional care and competence, but **cannot** be construed as an absolute guarantee. We iterate that if the encountered subsurface conditions differ from those forming the basis of our recommendations, we should be informed in order to assess the need for amendments.

We trust the foregoing information is sufficient for your present requirements in the design and construction of the plant.

APPENDIX I – Logs and Cross Section

Borehole Logs

ABBREVIATIONS AND BASIS OF DESCRIPTIONS

Weathering Grades	Recovery Properties	Fracture Describes	Fracture Index
(Fresh & hard)	TCR Total Core Recovery	Q1 Vein & Root	W1 Rubble Material
(Slightly Weathered)	RDD Rock Quality Designation	N1 Irregular	
(Moderately Weathered)	<u>Sample Type</u>	R1 Rough and Irregular	
(Slightly Weathered)	A1 Ring Sample		
(Completely Weathered)	C1 Core Sample		
(Residual Soil)			

DYNAMIC CONE PENETRATION TEST

Dynamic Cone Penetration Test (DCPT) involves driving a 60" steel cone into the ground using a 3 kg falling hammer over a 575 mm drop height and recording the penetration for every blow.

STANDARD PENETRATION TEST

Standard Penetration Test (SPT) is an in-situ dynamic penetration test that entails the driving of a 60 lb (27.2 kg) weight (called the hammer) through a standard distance (760 mm) and recording the number of blows (N) required to achieve 300 mm penetration after an initial seating blow of 150 mm or 25 blows, whichever is achieved first (AS EN ISO 22476-3). Blow counts in excess of 50 in the 300 mm test phase are recorded as "usual" to penetration and abbreviated "u" in the logs. Below are typical consistency classifications of soils based on N₆₀ values. Note that SPT test correlations with σ_{vc} test are used just to confirm to the consistency based on the blow.

Consistency Soil		Relative Soil	
Soil Type	N - value	Consistency	Equivalent Shear Strength, kPa
Very Loose	< 4	Very Soft	< 12
Loose	4 - 15	Soft	12 - 25
Medium Dense	15 - 30	Firm	25 - 50
Dense	30 - 50	Stiff	50 - 100
Very Dense	> 50	Very Stiff	100 - 200
		Hard	> 200

Source: AS 1418:2013

SPT Correction Factors

Hanna Energy Ratio, $E_c = 20\%$

$E_s = 2.75 \text{ (rod length)}^2 + 4 \text{ (ft)}$

$E_r = 1.0 \text{ (rod diameter)}^2 + 3.33 \text{ (mm)}$

$E_c = 1 \text{ (moderate sampler)}$

$\sigma_{vc} = 1 \times N_{60}$

Source: AS EN ISO 22476-3

Scale: Consistent Penetration Engineering Manual (2014), Section Two: Strength and Prob. 2B2

FIELD MOISTURE DESCRIPTIONS

Dry - refers to a soil sample with a moisture content well below optimum ($w < w_{opt}$), absence of water, e.g. dry to the touch.

Moist - refers to a soil sample with a moisture content at or near optimum ($w \approx w_{opt}$), no visible free water.

Wet - refers to a soil sample with a moisture content well above optimum ($w > w_{opt}$), has visible pore water.

ROCK DESCRIPTIONS

RDD (%)	Rock Mass Quality	Compressive Strength (MPa)	Strength Classification
0 - 25	Very Poor	< 2	Extremely Weak
25 - 50	Poor	2 - 5	Very Weak
50 - 75	Fair	5 - 25	Weak
75 - 90	Good	25 - 50	Medium Strong
90 - 100	Excellent	50 - 100	Strong
		100 - 150	Very Strong
		> 150	Extremely Strong

Source: Rock Mass Rating (RMR) 2012 (Ed. by Bieniawski/2002)

SYMBOLS

☒ Last Record of work taken in the borehole. May not represent full equipment condition.

Project Details		Borehole Details	
Project: Faalil Stage Treatment Plant	 SHAND CONSTRUCTION ENGINEERING & CONSTRUCTION LTD HONGKONG COMPANY	ID: PH (BH1)	Depth (m): 18
Location: Khayji		Coordinates: UTM (Easting): 5822600	UTM (Northing): 20100
Client: Abu Is-Salam Water Supply and Sanitation Authority (AWSSA)		Scale: 1:500	Date: 04/11/2023

BORERHOLE LOG

Penetration Method: Rotary	Drilled by: Washed	Bit Type: Diamond
Log Type: GSI-100	Logged by: Fawzi	Inclination from Vertical: 0°


Depth (m)	Elevation (m)	Soil Description			Moisture (%)	SPT Value	SPT Value
		Soil Type	Color	Texture			
0	20	LT	0	0			
1	19	LT	0	0			
2	18	LT	0	0			
3	17	LT	0	0			
4	16	LT	0	0			
5	15	LT	0	0			
6	14	LT	0	0			
7	13	LT	0	0			
8	12	LT	0	0			
9	11	LT	0	0			
10	10	LT	0	0			
11	9	LT	0	0			
12	8	LT	0	0			
13	7	LT	0	0			
14	6	LT	0	0			
15	5	LT	0	0			
16	4	LT	0	0			
17	3	LT	0	0			
18	2	LT	0	0			

KEY  Sand 	WEATHERING GRADES: I: Fresh & Hard II: Slightly Weathered III: Moderately Weathered IV: Highly Weathered V: Completely Weathered VI: Residual Soil	COHESIONLESS SOILS: Relative Density Very Loose: < 4 Loose: 4-10 Medium Dense: 10-30 Dense: 30-50 Very Dense: > 50	COHESIVE SOILS: Consistency Very Soft: < 2 Soft: 2-4 Firm: 4-8 Stiff: 8-15 Very Stiff: 15-30 Hard: > 30

Project Details		Borehole Details	
Project: Faalil Stage Treatment Plant	 SHAND CONSTRUCTION ENGINEERING & CONSTRUCTION LTD. HONGKONG, CHINA	ID: PC (BH2)	Depth (m): 18
Location: Khayti		Coordinates: UTM 28T 8 (Easting: 613410, Northing: 5422400)	Site (m): 11456 Zone: 28T
Client: Abu Is Salameh Water Supply and Sanitation Authority (AWSSA)		Start Date: 06/12/2013	Finish Date: 10/01/2014

BOREHOLE LOG

Penetration Method: Rotary	Drilled by: Washed	Bit Type: Diamond
Log Type: GSI-100	Trigged by: Casella	Inclination from Vertical: 0°




KEY  Clay  Sand	WEATHERING GRADES: F: Fresh & Hard G: Slightly Weathered H: Moderately Weathered I: Highly Weathered V: Completely Weathered N: Natural Soil	COHESIONLESS SOILS: Relative Density Very Loose: < 4 Loose: 4-10 Medium Dense: 10-30 Dense: 30-50 Very Dense: > 50	COHESIVE SOILS: Consistency Very Soft: < 2 Soft: 2-4 Firm: 4-8 Stiff: 8-15 Very Stiff: 15-30 Hard: > 30
--	---	---	---

Project Details		Borehole Details	
Project: Faalil Stage Treatment Plant		ID: PID (R03)	Depth (m): 18
Location: Khayji		Coordinates: UTM 582187 Easting: 582187 Northing: 5821874	Zone: 37 S
Client: Abu Is-Salam Water Supply and Sanitation Authority (AWASA)		Start Date: 15/06/2023	Finish Date: 16/06/2023

BORERHOLE LOG

Penetration Method: Rotary	Drilled by: Washed	Bit Type: Diamond
Log Type: GSI-100	Trigged by: Casella	Inclination from Vertical: 0°




KEY  Sand	WEATHERING GRADES F: Fresh & Hard G: Slightly Weathered H: Moderately Weathered I: Highly Weathered V: Completely Weathered M: Residual Soil	COHESIONLESS SOILS Relative Density Very Loose: < 4 Loose: 4 - 10 Medium Dense: 10 - 30 Dense: 30 - 50 Very Dense: > 50	COHESIVE SOILS Consistency Very Soft: < 2 Soft: 2 - 4 Firm: 4 - 8 Stiff: 8 - 15 Very Stiff: 15 - 30 Hard: > 30
--	---	--	--

Project Details		Borehole Details	
Project: Faalil Stage Treatment Plant	 SHAND CONSTRUCTION ENGINEERING & CONSTRUCTION LTD HONGKONG COMPANY	ID: PG (011)	Depth (m): 18
Location: Khayji		Coordinates: UTM 28TUB (0.25)	Easting: 482,000 Zone: 28S
Client: Abu Dhabi Water Supply and Sewerage Authority (AWASA)		Start Date: 14/09/2013	Valid Date: 15/09/2013

BOREHOLE LOG

Penetration Method: Rotary	Drilled by: Washed	Bit Type: Diamond
Log Type: GSI-100	Logged by: Fawzi	Inclination from Vertical: 0°




KEY  Sand	WEATHERING GRADES: F: Fresh & Hard G: Slightly Weathered H: Moderately Weathered I: Highly Weathered V: Completely Weathered M: Residual Soil	COHESIONLESS SOILS Relative Density Very Loose: < 4 Loose: 4-10 Medium Dense: 10-30 Dense: 30-50 Very Dense: > 50	COHESIVE SOILS Consistency Very Soft: < 2 Soft: 2-4 Firm: 4-8 Stiff: 8-15 Very Stiff: 15-30 Hard: > 30
--	--	--	--

Project Details		Borehole Details	
Project: Faial Stage Treatment Plant		ID: PF 0019	Depth (m): 18
Location: Khoraji		Coordinates: UTM 35T 548 000 548 000	Zone: 35T
Client: Abu Dhabi Water Supply and Sewerage Authority (AWASA)		Start Date: 06/09/2013	Finish Date: 17/09/2013

BOREHOLE LOG

Penetration Method: Rotary	Drilled by: Washed	Bit Type: Diamond
Log Type: GSI-100	Logged by: Fawzi	Inclination from Vertical: 0°



KEY	WEATHERING GRADES	COHESIONLESS SOILS	COHESIVE SOILS
 Clay  Sand	I: Fresh & Hard II: Slightly Weathered III: Moderately Weathered IV: Highly Weathered V: Completely Weathered VI: Residual Soil	Relative Density Very Loose: < 4 Loose: 4-10 Medium Dense: 10-30 Dense: 30-50 Very Dense: > 50	Consistency Very Soft: < 2 Soft: 2-4 Firm: 4-8 Stiff: 8-15 Very Stiff: 15-30 Hard: > 30

Project Details		Borehole Details	
Project: Faial Stage Treatment Plant		ID: FIE (BIM)	Depth (m): 18
Location: Khatijj		Coordinates: UTM 48QUC642	Elev (m) 36.73
Client: Abu Dhabi Water Supply and Sewerage Authority (AWASA)		UTM: 54226816	Zone: 47 S
		Start Date: 17/06/2015 End Date: 18/06/2015	

BORERHOLE LOG

Penetration Method: Rotary	Drilled by: Washed	Bit Type: Diamond
Log Type: G3-148	Logged by: Fawzi	Inclination from Vertical: 0°


Depth (m)	Soil Type	Soil Description			Moisture	SPT Value	SPT Value				
		Grain Size	Plasticity	Color			2	3	4	5	6
0.0 - 3.0	CL	0.1	0	10	10	10					
3.0 - 10.0	LS	0.6	0	10	10	10	10	10	10	10	10
10.0 - 12.0	LS	0.6	0	10	10	10	10	10	10	10	10
12.0 - 15.0	LS	0.6	0	10	10	10	10	10	10	10	10
15.0 - 18.0	LS	0.6	0	10	10	10	10	10	10	10	10
18.0 - 20.0	LS	0.6	0	10	10	10	10	10	10	10	10
20.0 - 22.0	LS	0.6	0	10	10	10	10	10	10	10	10
22.0 - 25.0	LS	0.6	0	10	10	10	10	10	10	10	10
25.0 - 27.0	LS	0.6	0	10	10	10	10	10	10	10	10

KEY 	WEATHERING GRADES F: Fresh & Hard G: Slightly Weathered H: Moderately Weathered I: Highly Weathered V: Completely Weathered M: Residual Soil	COHESIONLESS SOILS Relative Density Very Loose: < 4 Loose: 4-10 Medium Dense: 10-30 Dense: 30-50 Very Dense: > 50	COHESIVE SOILS Consistency Very Soft: < 2 Soft: 2-4 Firm: 4-8 Stiff: 8-15 Very Stiff: 15-30 Hard: > 30

Project Details		Borehole Details	
Project: Faalil Stage Treatment Plant		ID: FA(007)	Depth (m): 18
Location: Khayji		Coordinates: 13°57'00.4 0.234	Elevation (m): 10.156 Zone: 37 S
Client: Abu Za'aban Water Supply and Sanitation Authority (AWASA)		Start Date: 10/06/2013	Finish Date: 10/06/2013


BORERHOLE LOG

Penetration Method: Rotary	Drilled by: Washed	Bit Type: Diamond
Log Type: G3-100	Logged by: Fawzi	Inclination from Vertical: 0°



KEY  Clay  Sand	WEATHERING GRADES: F: Fresh & Hard G: Slightly Weathered H: Moderately Weathered I: Highly Weathered V: Completely Weathered VI: Residual Soil	COHESIONLESS SOILS: Relative Density Very Loose: < 4 Loose: 4-10 Medium Dense: 10-30 Dense: 30-50 Very Dense: > 50	COHESIVE SOILS: Consistency Very Soft: < 2 Soft: 2-4 Firm: 4-8 Stiff: 8-15 Very Stiff: 15-30 Hard: > 30
--	---	---	---

INFERRED GEOTECHNICAL CROSS SECTION



APPENDIX II – Sample Photographs



DII (Pit): Box 1/2



DII (Pit): Box 2/2



III2 (P/C): Box 1/2



III2 (P/C): Box 2/2



III3 (PID): Box 1/2



III3 (PID): Box 2/2



BH4 (PIG): Box 1/2



BH4 (PIG): Box 2/2



BHS (PIF): Box 1/2



BHS (PIF): Box 2/2



BH6 (PIE): Box 1/2



BH6 (PIE): Box 2/2



III7 (PIA): Box 1/2



III7 (PIA): Box 2/2

APPENDIX III – References

References

1. British Standards Institution (2006) *BS 1377-2016, Method of Test for Soils for Civil Engineering Purposes*. London: British Standard Institution.
2. British Standards Institution (1999) *BS 5930-1999, Code of Practice for Site Investigations*. London: British Standard Institution.
3. Keneth L. (2013). *International Journal of Research in Engineering and Science - A Review of Engineering Geology in Tanzania*.
4. Murthy V.N.S (2007). *Advanced Foundation Engineering*. CBS Publishers and Distributors.
5. Robert W.D. (2010). *Foundation Engineering Handbook 2nd Ed*. Mc Graw Hill, New York.

APPENDIX IV – Laboratory Test Reports



Dar es Salaam Institute of Technology
Civil & Building Engineering Department
Materials Testing Laboratory

TC 001/001 (Part 1H) 1993


ATTERBERGS' LIMITS TEST

CLIENT:
LOCATION:
OPERATOR:
DATE:

SHANTI CONSTRUCTION COMPANY
UNHAJI CDR
JAMES
12.12.2021

SH No. 7
Sample No. 02
Depth(m): 0.20-0.25

Test No.		1	2	3	4	PL	PL
TYPE OF TEST		LL	LL	LL	LL		
Initial dial gauge reading	mm	1.5 (1.7)	1.5 (1.5)	1.5 (1.5)	1.5 (1.5)		
Final dial gauge reading	mm	15.1 (15.4)	15.0 (15.0)	17.4 (17.3)	15.5 (15.1)		
Cone penetration	mm	14.7	17.5	20.8	24.6		
Container No.		T10	T8	T7	T12	T17	T18
Mass of wet soil + container	gm	46.00	44.40	41.80	50.00	41.50	49.70
Mass of dry soil + container	gm	40.00	40.30	41.20	42.40	41.30	49.80
Mass of container	gm	20.30	20.70	20.20	20.10	0.10	3.00
Mass of moisture	gm	6.00	4.10	0.60	7.60	2.20	2.90
Mass of dry soil	gm	13.70	19.60	18.50	12.30	11.20	14.80
Moisture content (%)	%	43.78	21.22	3.24	61.74	19.64	19.59
Cone penetration	mm	14.7	17.5	20.8	24.6		17



Liquid limit:
Plastic limit (PL)
Plasticity index (PI)

14
17
20





Dar es Salaam Institute of Technology
Civil & Building Engineering Department
Materials Testing Laboratory

TD 001 (001) / Part 1 (0) - 1992


ATTERBERG'S LIMITS TEST

CLIENT:
 LOCATION:
 OPERATOR:
 DATE:

SHOHI CONSTRUCTION COMPANY
 ANBAAI, TANZ
 JAMIS
 12.12.2023

RM No. 7
 Sample No. 0PC
 Depth (m) 4.50-4.95

Test No.		1	2	3	4	PL	PL
TYPE OF TEST		LL	LL	LL	LL		
Final soil (moist) weight	gm	16.13	15.13	15.18	15.13		
Final (dry) weight	gm	10.2	10.0	10.1	10.1		
Cone penetration	mm	18.2	17.3	20.5	24.2		
Container No		T10	T6	T7	T12	T17	T18
Mass of wet soil + container	gm	47.50	52.40	53.50	47.80	27.30	25.40
Mass of dry soil + container	gm	41.50	41.00	43.00	41.50	24.10	23.10
Mass of container	gm	26.30	30.40	29.80	27.40	9.40	9.10
Mass of moisture	gm	6.00	6.40	7.00	6.30	2.60	2.30
Mass of dry soil	gm	15.30	16.60	17.10	16.20	15.30	13.80
Moisture content (%)	%	39.20	38.50	40.90	38.90	16.37	16.67
Cone penetration	mm	18.2	17.3	20.5	24.2		17



Liquid limit (L) 40
 Plastic limit (PL) 17
 Plasticity index (PI) 23





Dar es Salaam Institute of Technology
 Civil & Building Engineering Department
 Materials Testing Laboratory

1005 101 104 101 103


ATTERBERG'S LIMITS TEST

CLIENT:
 LOCATION:
 OPERATOR:
 DATE:

SHARI CONSTRUCTION COMPANY
 KIMBA, TAN
 JAMES
 12/13/2011

Run No. 7
 Sample No. 3PT
 Description: L50-100

Test No.	1	2	3	4	PL	FL
Moisture content (%)	12.1	12.5	15.1	15.1	15.1	15.1
Liquid Limit (%)	10.0	10.0	10.0	10.0	10.0	10.0
Plastic Limit (%)	10.0	10.0	10.0	10.0	10.0	10.0
Plasticity Index (%)	0.0	0.0	0.0	0.0	0.0	0.0
Moisture content (%)	12.1	12.5	15.1	15.1	15.1	15.1
Liquid Limit (%)	10.0	10.0	10.0	10.0	10.0	10.0
Plastic Limit (%)	10.0	10.0	10.0	10.0	10.0	10.0
Plasticity Index (%)	0.0	0.0	0.0	0.0	0.0	0.0



Liquid Limit (LL) = 10.0
 Plastic Limit (PL) = 10.0
 Plasticity Index (PI) = 0.0

15
 17
 20

RECEIVED AT THE MATERIALS TESTING LABORATORY
 TO BE TESTED FOR ATTERBERG'S LIMITS TEST
 DATE: 12/13/2011



Dar es Salaam Institute of Technology
Civil & Building Engineering Department
Materials Testing Laboratory

TO 85 1981 | Part 195 - 1993


ATTERBERG'S LIMITS TEST

CLIENT :
 LOCATION :
 OPERATOR :
 DATE :

EMACO CONSTRUCTION COMPANY
 ANNAK, COM
 JAMES
 12.12.2023

BM No. C
 Sample No. SPT
 Depth: 1.50-1.55

Test No.		1	2	3	4	PL	PL
TYPE OF TEST		LL	LL	LL	LL		
Final shear vane reading	mm	1.5	1.6	1.5	1.6		
Final torque reading	mm	76.1	76.3	76.3	76.1		
Cone penetration	mm	14.7	17.6	20.8	24.3		
Container No.		T18	T8	T7	T18	T17	T18
Moisture of wet soil + container	gms	45.85	45.40	47.80	46.70	35.75	34.50
Moisture of dry soil + container	gms	38.38	38.40	40.80	40.20	28.75	28.00
Moisture of container	gms	28.75	28.75	28.75	28.75	8.50	8.00
Moisture of moisture	gms	4.39	7.00	7.00	6.50	3.00	3.20
Moisture of dry soil	gms	12.00	12.00	12.00	12.00	11.00	13.00
Moisture content (%)	%	47.70	59.85	17.38	17.50	18.18	18.18
Cone penetration	mm	14.7	17.6	20.8	24.3		



Liquid limit (L)
 Plastic limit (PL)
 Plasticity Index (PI)

18.18

EMACO CONSTRUCTION PVT. LTD.
 DAR ES SALAAM
 DAR ES SALAAM BRANCH OFFICE
 P.O. BOX 1111 - DAR ES SALAAM
 TEL: 255 22 2521111
 WWW.EMACO.CO.TZ

James



Dar es Salaam Institute of Technology
Civil & Building Engineering Department
Materials Testing Laboratory

FORM 1001 / Part 110 / MS


ATTERBERG'S LIMITS TEST

CLIENT:
 LOCATION:
 OPERATOR:
 DATE:

SIKHA CONSTRUCTION COMPANY
 KIBBIA DUM
 JAMES
 12.12.2023

BH No. 1
 Sample No. SPT
 Depth(s) 3.60-3.65

Test No.		1	2	3	4	PL	FL
TYPE OF TEST		LL	LL	LL	LL		
Flow dial spread reading	mm	1.2	1.2	1.2	1.8	1.5	1.8
Flow dial spread reading	mm	16.3	16.3	16.3	22.1	22.5	26.1
Cone penetration	mm	14.5	14.0	20.8	24.5		
Container fill		T18	T8	T7	T12	T17	T10
Mass of wet soil + container	gms	47.20	51.30	52.10	55.50	23.40	23.50
Mass of dry soil + container	gms	43.70	45.20	45.20	47.50	21.40	21.30
Mass of container	gms	29.40	23.15	23.80	30.00	8.90	8.00
Mass of moisture	gms	3.50	6.10	6.90	7.90	2.50	2.20
Mass of dry soil	gms	14.30	12.05	11.40	17.50	12.50	13.30
Moisture content (%)	%	24.48	50.63	60.53	45.14	19.92	16.54
Cone penetration	mm	14.5	14.0	20.8	24.5		



Liquid limit (LL) 45
 Plastic limit (PL) 13
 Plasticity index (PI) 32

ENGINEERING REGISTRATION BOARD
 TANZANIA
 DAR ES SALAAM INSTITUTE OF TECHNOLOGY
 P.O. BOX 2992 - URBAN MOJIBAO
 Dar es Salaam, Tanzania
 12/12/2023



Oyo vs Salami Institute of Technology
 Civil & Building Engineering Department

Materials Testing Laboratory


CLIENT: SHANU CONSTRUCTION COMPANY
 PROJECT: PROPOSED FACIAL SLUDGE TREATMENT PLANT
 DATE: 14/12/2023

GRAIN SIZE DISTRIBUTION

SAMPLE TYPE	04	05	06	07
SAMPLE No.	1	1	1	1
DEPTH	1.00-2.00	2.00-3.00	3.00-4.00	4.00-5.00
Class (mm)	Percentage passing			
75				
150				
300				
600				
1.18	100	100	100	100
2.50	100	100	100	100
600	100	100	100	100
750	100	100	100	100
900	100	100	100	100
1050	100	100	100	100
1200	100	100	100	100
1350	100	100	100	100
1500	100	100	100	100
1650	100	100	100	100
1800	100	100	100	100
2000	100	100	100	100

CLASSIFICATION

UCS	TC	SC - Medium to High Plasticity	SC - High Plasticity	SC - High Plasticity
U-Expansive	1	2	4	6
U-Non	3	5	5	6
U-Fine	4	6	6	7
U-Medium		7	7	7
U-Coarse		8	8	8



TESTED BY: CHARLES JIMET
 APPROVED BY: DR. JIM JIMET OJINHA
 HEAD OF CIVIL ENGINEERING SECTION / MATERIALS ENGINEERING DEPARTMENT

SHANU CONSTRUCTION COMPANY
 15/12/2023
 PROJECT: PROPOSED FACIAL SLUDGE TREATMENT PLANT
 14/12/2023
 14/12/2023




Dar es Salaam Institute of Technology
Civil & Building Engineering Department
Materials Testing Laboratory

CLIENT: SHARIK CONSTRUCTION COMPANY
PROJECT: PROPOSED FACIAL CLIMATE TREATMENT PLANT
DATE: 14.12.2023

GRAVITY SEPERATION					
SAMPLE TYPE	CO	CC	CE	CE	CE
SOCKETLE No.	1	2	3	4	5
DEPTH (mm)	1.00-3.00	3.00-4.50	4.50-7.50	7.50-10.00	10.00-15.00
Spec. No. (mm)	Percentage passing				
150					
75					
4.75					
75	100	100	100	100	100
150	100	100	100	100	100
300	100	100	100	100	100
600	100	100	100	100	100
900	100	100	100	100	100
1200	100	100	100	100	100
1500	100	100	100	100	100
1800	100	100	100	100	100
2100	100	100	100	100	100
2400	100	100	100	100	100

CLASSIFICATION					
UNCL	SO	SC	SC	SC - Maximum in Top Portion	SC
150mm	1	1	1	2	1
75mm	0	0	0	0	0
4.75mm	1	1	1	1	1
75mm				1	
150mm				1	
300mm				1	
600mm				1	
900mm				1	
1200mm				1	
1500mm				1	
1800mm				1	
2100mm				1	
2400mm				1	



TESTED BY: CHARLES JAMES
APPROVED BY: C.Eng. JAMES J. JUMA
 HEAD OF ELECTRICAL ENGINEERING DEPARTMENT & MATERIALS TESTING LABORATORY

RECEIVED
 MATERIALS TESTING LABORATORY
 DAR ES SALAAM INSTITUTE OF TECHNOLOGY
 P.O. BOX 3589 - DAR ES SALAAM
 TEL: 255 22 261 0000
 14/12/2023



Dar es Salaam Institute of Technology
 Civil Engineering Department
 Materials Testing Laboratory

BULK DENSITY/NATURAL MOISTURE CONTENT DETERMINATION

NO-LAB TEST RESULT

CLIENT: SHANKI CONSTRUCTION COMPANY
 PROJECT: PROPOSED TREATMENT PLANT
 SOURCE: SH 21

SITE: KIMBILI, DAR ES-SALAAM
 DATE: 24.11.2023
 REFERENCE: 0.88-3.96

Test No:		1
Mass of test soil + Sample	g	1872.7
Mass of test soil	g	0
Mass of container	g	1872.7
Length of sample	mm	100.0
Thickness of sample	mm	100.0
Volume of sample	mm ³	993078
Bulk Density	kg/m ³	1867
Dry Density	kg/m ³	1860

Test No:		1
Mass of test soil + tin	g	291.0
Mass of dry soil + tin	g	276.5
Moisture content (M _h) (%)		5.3
Mass of tin	g	100.0
Moisture content (M _h) (%)	17.4	1.7

CLIENT: SHANKI CONSTRUCTION COMPANY
 PROJECT: PROPOSED TREATMENT PLANT
 SOURCE: SH 42

SITE: KIMBILI, DAR ES-SALAAM
 DATE: 24.11.2023
 REFERENCE: 1.00-1.00

Test No:		1
Mass of test soil + Sample	g	371.4
Mass of test soil	g	0
Mass of container	g	371.4
Length of sample	mm	200.0
Thickness of sample	mm	25.0
Volume of sample	mm ³	250034
Bulk Density	kg/m ³	1485
Dry Density	kg/m ³	1475

Test No:		1
Mass of test soil + tin	g	255.7
Mass of dry soil + tin	g	231.7
Moisture content (M _h) (%)		10
Mass of tin	g	30.0
Moisture content (M _h) (%)	17.4	15.3





Dar es Salaam Institute of Technology
Civil Engineering Department
Materials Testing Laboratory

BULK DENSITY/NATURAL MOISTURE CONTENT DETERMINATION

OUT-LAB TEST RESULT

CLIENT: SHANG CONSTRUCTION COMPANY
PROJECT: PROPOSED TREATMENT PLANT
SOURCE: SH 22

SITE: KIBIKU, DAR ES SALAAM
DATE: 24.11.2023

DESCRIPTION:

Test No.		1
Mass of tins + Sample	g	500.2
Mass of tins	g	0
Mass of sample	g	500.2
Length of sample	mm	500.0
Diameter of sample	mm	75.0
Volume of sample	mm ³	220624
Bulk Density	kg/m ³	2268
Dry Density	kg/m ³	1728

Test No.		1
Mass of wet soil = W ₁	g	100.2
Mass of dry soil = W ₂	g	123.8
Moisture content by %		67.1
Mass of tin	g	45.3
Moisture content by %	%	11.0


CLIENT: SHANG CONSTRUCTION COMPANY
PROJECT: PROPOSED TREATMENT PLANT
SOURCE: SH 22

SITE: KIBIKU, DAR ES SALAAM
DATE: 24.11.2023

DESCRIPTION: TO, 00 TO 48

Test No.		1
Mass of tins + Sample	g	500.2
Mass of tins	g	0
Mass of sample	g	500.2
Length of sample	mm	500.0
Diameter of sample	mm	75.0
Volume of sample	mm ³	220624
Bulk Density	kg/m ³	2268
Dry Density	kg/m ³	1816

Test No.		1
Mass of wet soil = W ₁	g	232.5
Mass of dry soil = W ₂	g	201.3
Moisture content by %		15.7
Mass of tin	g	48.0
Moisture content by %	%	19.0





Dar es Salaam Institute of Technology
Civil Engineering Department
Materials Testing Laboratory

BULK DENSITY/NATURAL MOISTURE CONTENT DETERMINATION

OFF-LAB TEST RESULT

CLIENT: IRANDA CONSTRUCTION COMPANY
 PROJECT: PROPOSED TREATMENT PLANT
 SOURCE: BH 02

SITE: KIMBELE, DAR ES SALAAM
 DATE: 24.11.2022
 CONTAINER: 4.50-4.50

Test No.		1
Mass of tin + Sample	g	607.0
Mass of tin	g	0
Mass of sample	g	607.0
Length of sample	mm	32.0
Diameter of sample	mm	55.0
Volume of sample	mm ³	20000
Bulk Density	g/cm ³	30.35
Dry Density	g/cm ³	17.00


Test No.		1
Mass of wet soil + tin	g	200.0
Mass of dry soil + tin	g	187.0
Moisture content (w)	%	6.45
Mass of tin	g	25.0
Natural moisture content	(%)	11.3

CLIENT: IRANDA CONSTRUCTION COMPANY
 PROJECT: PROPOSED TREATMENT PLANT
 SOURCE: BH 02

SITE: KIMBELE, DAR ES SALAAM
 DATE: 24.11.2022
 CONTAINER: 10.09-10.40

Test No.		1
Mass of tin + Sample	g	300.0
Mass of tin	g	0
Mass of sample	g	300.0
Length of sample	mm	100.0
Diameter of sample	mm	55.0
Volume of sample	mm ³	172100
Bulk Density	g/cm ³	1.743
Dry Density	g/cm ³	1.623

Test No.		1
Mass of wet soil + tin	g	100.0
Mass of dry soil + tin	g	95.0
Moisture content (w)	%	5.26
Mass of tin	g	20.0
Natural moisture content	(%)	5.0





**Dar es Salaam Institute of Technology,
Civil Engineering Department,
Materials Testing Laboratory**

BULK DENSITY/NATURAL MOISTURE CONTENT DETERMINATION

DT-LAB TEST RESULT

CLIENT: SHANGI CONSTRUCTION COMPANY
PROJECT: PROPOSED TREATMENT PLANT
SOURCE: SHM

SITE: KIBIKU, DAR ES SALAAM
DATE: 24.11.2023
DEPTH: 1.50-1.65

Test No:		1
Mass of tins + Sample	g	588.0
Mass of tin	g	11
Mass of sample	g	577.0
Length of sample	mm	300.0
Diameter of sample	mm	35.0
Volume of sample	mm ³	2800.0
Wet Density	kg/m ³	206.1
Dry Density	kg/m ³	179.4

Test No:		1
Mass of wet soil + tin	g	227.1
Mass of dry soil + tin	g	215.3
Moisture content (%)		5.5
Mass of tin	g	45.1
Percent moisture content	(%)	15.5

CLIENT: SHANGI CONSTRUCTION COMPANY
PROJECT: PROPOSED TREATMENT PLANT
SOURCE: SHM

SITE: KIBIKU, DAR ES SALAAM
DATE: 24.11.2023
DEPTH: 10.00/10.40

Test No:		1
Mass of tins + Sample	g	375.8
Mass of tin	g	8
Mass of sample	g	367.8
Length of sample	mm	300.0
Diameter of sample	mm	35.0
Volume of sample	mm ³	2800.0
Wet Density	kg/m ³	131.4
Dry Density	kg/m ³	122.6

Test No:		1
Mass of wet soil + tin	g	210.3
Mass of dry soil + tin	g	194.8
Moisture content (%)		7.5
Mass of tin	g	18.9
Percent moisture content	(%)	24.4





Dar es Salaam Institute of Technology
Civil Engineering Department
Materials Testing Laboratory

BULK DENSITY/NATURAL MOISTURE CONTENT DETERMINATION

OIT-LAB TEST RESULT

CLIENT: SHARD CONSTRUCTION COMPANY
PROJECT: PROPOSED TREATMENT PLANT
SOURCE: SH 05

SITE: KIMBELE, DAR ES SALAAM
DATE: 24.11.2023
DEPTH: 4.00-4.50

Test No.		1
Mass of tins + Sample	g	300.0
Mass of tins	g	0
Mass of sample	g	300.0
Volume of sample	cm ³	100.0
Volume of sample	cm ³	100.0
Volume of sample	cm ³	100.0
Bulk Density	kg/m ³	3000
Dry Density	kg/m ³	1800


Test No.		1
Mass of wet soil + tin	g	223.1
Mass of dry soil + tin	g	194.2
Moisture content by %		12.3
Mass of tin	g	25.5
Moisture content by %	%	11.4

CLIENT: SHARD CONSTRUCTION COMPANY
PROJECT: PROPOSED TREATMENT PLANT
SOURCE: SH 05

SITE: KIMBELE, DAR ES SALAAM
DATE: 24.11.2023
DEPTH: 1.50-1.00

Test No.		1
Mass of tins + Sample	g	407.0
Mass of tins	g	0
Mass of sample	g	407.0
Volume of sample	cm ³	100.0
Volume of sample	cm ³	100.0
Volume of sample	cm ³	100.0
Bulk Density	kg/m ³	4070
Dry Density	kg/m ³	3561

Test No.		1
Mass of wet soil + tin	g	300.0
Mass of dry soil + tin	g	280.0
Moisture content by %		6.8
Mass of tin	g	20.0
Moisture content by %	%	6.0





Dar es Salaam Institute of Technology
Civil Engineering Department
Materials Testing Laboratory

BULK DENSITY/NATURAL MOISTURE CONTENT DETERMINATION

DT-LAB TEST RESULT

CLIENT: SHANG CONSTRUCTION COMPANY

SITE: KIMBILI, DAR ES SALAAM

PROJECT: PROPOSED TREATMENT PLANT

DATE: 24.11.2023

SOURCE: SH 05

DEPT CODE: A.30-4.05

Test No:		1
Mass of test tin + Sample	g	572.3
Mass of test tin	g	0
Mass of sample	g	572.3
Length of sample	mm	381.0
Diameter of sample	mm	100.0
Volume of sample	mm ³	2960.84
Bulk Density	kg/m ³	1933
Dry Density	kg/m ³	1762

Test No:		1
Mass of test tin + tin	g	252.1
Mass of dry soil + tin	g	232.2
Moisture content by Ho		7.12
Mass of tin	g	24.7
Moisture content by oven	17%	12.1

CLIENT: SHANG CONSTRUCTION COMPANY

SITE: KIMBILI, DAR ES SALAAM

PROJECT: PROPOSED TREATMENT PLANT

DATE: 24.11.2023

SOURCE: SH 07

DEPT CODE: E.08-1.01

Test No:		1
Mass of test tin + Sample	g	500.1
Mass of test tin	g	0
Mass of sample	g	500.1
Length of sample	mm	300.0
Diameter of sample	mm	90.0
Volume of sample	mm ³	2034.94
Bulk Density	kg/m ³	2458
Dry Density	kg/m ³	1813

Test No:		1
Mass of test tin + tin	g	180.6
Mass of dry soil + tin	g	173.1
Moisture content by Ho		0.9
Mass of tin	g	24.7
Moisture content by oven	17%	1.8





Dar es Salaam Institute of Technology,
Civil Engineering Department,
Materials Testing Laboratory

BULK DENSITY/NATURAL MOISTURE CONTENT DETERMINATION

ON-LAB TEST RESULT

CLIENT: ENVAOS CONSTRUCTION COMPANY

SITE: KUREHA, DAR ES SALAAM

PROJECT: PROPOSED TREATMENT PLANT


DATE: 24.11.2023

SOURCE: BH 07

OUR CODE: 10-4.05

Test No:		T
Mass of tub + Sample	g	199.4
Mass of tub	g	0
Mass of sample	g	199.4
Length of sample	mm	350.5
Diameter of sample	mm	25.0
Volume of sample	cm ³	2800.4
Bulk Density	kg/m ³	2223
Dry Density	kg/m ³	1748

Test No:		T
Mass of wet soil = W ₁	g	170.1
Mass of dry soil = W ₂	g	152.3
Moisture content by tea		0
Mass of tin	g	24.5
Moisture content by oven	%	10.2








Govt. Golden Institute of Technology
Civil Engineering Department
Rohini, Trilokpur, Calicut.

Project: Design of a 300mm dia. RCC column
Date: 13.11.2023
Group No: 6-003-24
NAME: Pr. A. Anish
Enr No: 18
Institution: Golden Institute of Technology


DIRECT SHEAR TEST

Normal force (kN)	Normal force (kN)		Normal force (kN)		Normal force (kN)		Vertical stress (kN/m ²)	Horizontal stress (kN/m ²)	Angle of friction (φ)
	Applied	Reaction	Applied	Reaction	Applied	Reaction			
0	0	0	0	0	0	0	0	0	
10	10	10	10	10	10	10	10	10	
20	20	20	20	20	20	20	20	20	
30	30	30	30	30	30	30	30	30	
40	40	40	40	40	40	40	40	40	
50	50	50	50	50	50	50	50	50	
60	60	60	60	60	60	60	60	60	
70	70	70	70	70	70	70	70	70	
80	80	80	80	80	80	80	80	80	
90	90	90	90	90	90	90	90	90	
100	100	100	100	100	100	100	100	100	
110	110	110	110	110	110	110	110	110	
120	120	120	120	120	120	120	120	120	
130	130	130	130	130	130	130	130	130	
140	140	140	140	140	140	140	140	140	
150	150	150	150	150	150	150	150	150	
160	160	160	160	160	160	160	160	160	
170	170	170	170	170	170	170	170	170	
180	180	180	180	180	180	180	180	180	
190	190	190	190	190	190	190	190	190	
200	200	200	200	200	200	200	200	200	
210	210	210	210	210	210	210	210	210	
220	220	220	220	220	220	220	220	220	
230	230	230	230	230	230	230	230	230	
240	240	240	240	240	240	240	240	240	
250	250	250	250	250	250	250	250	250	
260	260	260	260	260	260	260	260	260	
270	270	270	270	270	270	270	270	270	
280	280	280	280	280	280	280	280	280	
290	290	290	290	290	290	290	290	290	
300	300	300	300	300	300	300	300	300	



TESTED BY: Pr. A. Anish
DATE: 13.11.2023

APPROVED BY: [Signature]
DATE: 13.11.2023



Dept of Polymer Institute of Technology
 (CIVIL Engineering Department)
 Materials Testing Laboratory

Material: Steel Specimen: Charpy Test: Impact

Prepared by: [Signature]
 Checked by: [Signature]
 Date: 10/10/2023

Sl. No.	Impact Test (Charpy)		Impact Test (Drop Weight)		Average Energy (J)	Standard Deviation (J)	Remarks
	Energy (J)	Deflection (mm)	Energy (J)	Deflection (mm)			
1	100	10	100	10	100	10	100%
2	100	10	100	10	100	10	100%
3	100	10	100	10	100	10	100%
4	100	10	100	10	100	10	100%
5	100	10	100	10	100	10	100%
6	100	10	100	10	100	10	100%
7	100	10	100	10	100	10	100%
8	100	10	100	10	100	10	100%
9	100	10	100	10	100	10	100%
10	100	10	100	10	100	10	100%
11	100	10	100	10	100	10	100%
12	100	10	100	10	100	10	100%
13	100	10	100	10	100	10	100%
14	100	10	100	10	100	10	100%
15	100	10	100	10	100	10	100%
16	100	10	100	10	100	10	100%
17	100	10	100	10	100	10	100%
18	100	10	100	10	100	10	100%
19	100	10	100	10	100	10	100%
20	100	10	100	10	100	10	100%
21	100	10	100	10	100	10	100%
22	100	10	100	10	100	10	100%
23	100	10	100	10	100	10	100%
24	100	10	100	10	100	10	100%
25	100	10	100	10	100	10	100%
26	100	10	100	10	100	10	100%
27	100	10	100	10	100	10	100%
28	100	10	100	10	100	10	100%
29	100	10	100	10	100	10	100%
30	100	10	100	10	100	10	100%
31	100	10	100	10	100	10	100%
32	100	10	100	10	100	10	100%
33	100	10	100	10	100	10	100%
34	100	10	100	10	100	10	100%
35	100	10	100	10	100	10	100%
36	100	10	100	10	100	10	100%
37	100	10	100	10	100	10	100%
38	100	10	100	10	100	10	100%
39	100	10	100	10	100	10	100%
40	100	10	100	10	100	10	100%
41	100	10	100	10	100	10	100%
42	100	10	100	10	100	10	100%
43	100	10	100	10	100	10	100%
44	100	10	100	10	100	10	100%
45	100	10	100	10	100	10	100%
46	100	10	100	10	100	10	100%
47	100	10	100	10	100	10	100%
48	100	10	100	10	100	10	100%
49	100	10	100	10	100	10	100%
50	100	10	100	10	100	10	100%

Total Energy (J)	100
Average Energy (J)	100
Standard Deviation (J)	10



Prepared by: [Signature]
 Checked by: [Signature]
 Date: 10/10/2023

Approved by: [Signature]
 Date: 10/10/2023



Department of Technology
Civil Engineering Department
Molecular Training Laboratory

Project: **Investigation of the effect of temperature on the rate of reaction**
Date: **10/11/2021**
Group: **Lab 101**
Member: **By: 3 Names**
No. of members: **3**
Project committed test: **100%**

TABLE 1: DATA 1

Temperature (°C)	Rate of reaction (min⁻¹)		Normal test (min)		Standard deviation (min)
	Initial	Final	Initial	Final	
25	0	120	1	120	0
30	1	175	3	170	7
35	2	225	7	165	15
40	4	275	11	160	20
45	6	325	15	155	25
50	8	375	20	150	30
55	10	425	25	145	35
60	12	475	30	140	40
65	15	525	35	135	45
70	18	575	40	130	50
75	20	625	45	125	55
80	22	675	50	120	60
85	25	725	55	115	65
90	28	775	60	110	70
95	30	825	65	105	75
100	32	875	70	100	80
105	35	925	75	95	85
110	38	975	80	90	90
115	40	1025	85	85	95
120	42	1075	90	80	100
125	45	1125	95	75	105
130	48	1175	100	70	110
135	50	1225	105	65	115
140	52	1275	110	60	120
145	55	1325	115	55	125
150	58	1375	120	50	130
155	60	1425	125	45	135
160	62	1475	130	40	140
165	65	1525	135	35	145
170	68	1575	140	30	150
175	70	1625	145	25	155
180	72	1675	150	20	160
185	75	1725	155	15	165
190	78	1775	160	10	170
195	80	1825	165	5	175
200	82	1875	170	0	180
205	85	1925	175	0	185
210	88	1975	180	0	190
215	90	2025	185	0	195
220	92	2075	190	0	200
225	95	2125	195	0	205
230	98	2175	200	0	210
235	100	2225	205	0	215
240	102	2275	210	0	220
245	105	2325	215	0	225
250	108	2375	220	0	230
255	110	2425	225	0	235
260	112	2475	230	0	240
265	115	2525	235	0	245
270	118	2575	240	0	250
275	120	2625	245	0	255
280	122	2675	250	0	260
285	125	2725	255	0	265
290	128	2775	260	0	270
295	130	2825	265	0	275
300	132	2875	270	0	280
305	135	2925	275	0	285
310	138	2975	280	0	290
315	140	3025	285	0	295
320	142	3075	290	0	300
325	145	3125	295	0	305
330	148	3175	300	0	310
335	150	3225	305	0	315
340	152	3275	310	0	320
345	155	3325	315	0	325
350	158	3375	320	0	330
355	160	3425	325	0	335
360	162	3475	330	0	340
365	165	3525	335	0	345
370	168	3575	340	0	350
375	170	3625	345	0	355
380	172	3675	350	0	360
385	175	3725	355	0	365
390	178	3775	360	0	370
395	180	3825	365	0	375
400	182	3875	370	0	380
405	185	3925	375	0	385
410	188	3975	380	0	390
415	190	4025	385	0	395
420	192	4075	390	0	400
425	195	4125	395	0	405
430	198	4175	400	0	410
435	200	4225	405	0	415
440	202	4275	410	0	420
445	205	4325	415	0	425
450	208	4375	420	0	430
455	210	4425	425	0	435
460	212	4475	430	0	440
465	215	4525	435	0	445
470	218	4575	440	0	450
475	220	4625	445	0	455
480	222	4675	450	0	460
485	225	4725	455	0	465
490	228	4775	460	0	470
495	230	4825	465	0	475
500	232	4875	470	0	480
505	235	4925	475	0	485
510	238	4975	480	0	490
515	240	5025	485	0	495
520	242	5075	490	0	500
525	245	5125	495	0	505
530	248	5175	500	0	510
535	250	5225	505	0	515
540	252	5275	510	0	520
545	255	5325	515	0	525
550	258	5375	520	0	530
555	260	5425	525	0	535
560	262	5475	530	0	540
565	265	5525	535	0	545
570	268	5575	540	0	550
575	270	5625	545	0	555
580	272	5675	550	0	560
585	275	5725	555	0	565
590	278	5775	560	0	570
595	280	5825	565	0	575
600	282	5875	570	0	580
605	285	5925	575	0	585
610	288	5975	580	0	590
615	290	6025	585	0	595
620	292	6075	590	0	600
625	295	6125	595	0	605
630	298	6175	600	0	610
635	300	6225	605	0	615
640	302	6275	610	0	620
645	305	6325	615	0	625
650	308	6375	620	0	630
655	310	6425	625	0	635
660	312	6475	630	0	640
665	315	6525	635	0	645
670	318	6575	640	0	650
675	320	6625	645	0	655
680	322	6675	650	0	660
685	325	6725	655	0	665
690	328	6775	660	0	670
695	330	6825	665	0	675
700	332	6875	670	0	680
705	335	6925	675	0	685
710	338	6975	680	0	690
715	340	7025	685	0	695
720	342	7075	690	0	700
725	345	7125	695	0	705
730	348	7175	700	0	710
735	350	7225	705	0	715
740	352	7275	710	0	720
745	355	7325	715	0	725
750	358	7375	720	0	730
755	360	7425	725	0	735
760	362	7475	730	0	740
765	365	7525	735	0	745
770	368	7575	740	0	750
775	370	7625	745	0	755
780	372	7675	750	0	760
785	375	7725	755	0	765
790	378	7775	760	0	770
795	380	7825	765	0	775
800	382	7875	770	0	780
805	385	7925	775	0	785
810	388	7975	780	0	790
815	390	8025	785	0	795
820	392	8075	790	0	800
825	395	8125	795	0	805
830	398	8175	800	0	810
835	400	8225	805	0	815
840	402	8275	810	0	820
845	405	8325	815	0	825
850	408	8375	820	0	830
855	410	8425	825	0	835
860	412	8475	830	0	840
865	415	8525	835	0	845
870	418	8575	840	0	850
875	420	8625	845	0	855
880	422	8675	850	0	860
885	425	8725	855	0	865
890	428	8775	860	0	870
895	430	8825	865	0	875
900	432	8875	870	0	880
905	435	8925	875	0	885
910	438	8975	880	0	890
915	440	9025	885	0	895
920	442	9075	890	0	900
925	445	9125	895	0	905
930	448	9175	900	0	910
935	450	9225	905	0	915
940	452	9275	910	0	920
945	455	9325	915	0	925
950	458	9375	920	0	930
955	460	9425	925	0	935
960	462	9475	930	0	940
965	465	9525	935	0	945
970	468	9575	940	0	950
975	470	9625	945	0	955
980	472	9675	950	0	960
985	475	9725	955	0	965
990	478	9775	960	0	970
995	480	9825	965	0	975
1000	482	9875	970	0	980

Fig 1: Graph of rate of reaction vs temperature




Fig 2: Graph of rate of reaction vs time





City of Batesville Office of Public Works
 Civil Engineering Department
 Municipal Testing Laboratory


PROJECT: Highway Project, State Investment #1421
DATE: 11.11.2011
OFFICE: 115-3-42
SCALE: 1/4" = 1'-0"
BY: MM
CHECKED: MM

PROJECT LOCATION: Highway Construction Company

Stationing	Vertical		Horizontal		Vertical Curve		Horizontal Curve		Remarks
	PC (Sta)	PVI (Sta)	PI (Sta)	PT (Sta)	Grade (%)	Grade (%)	Radius (ft)	Delta (deg)	
1+00	1+00	1+00	1+00	1+00	0.00	0.00	1000	0	Start of Curve
1+10	1+10	1+10	1+10	1+10	0.00	0.00	1000	0	
1+20	1+20	1+20	1+20	1+20	0.00	0.00	1000	0	
1+30	1+30	1+30	1+30	1+30	0.00	0.00	1000	0	
1+40	1+40	1+40	1+40	1+40	0.00	0.00	1000	0	
1+50	1+50	1+50	1+50	1+50	0.00	0.00	1000	0	
1+60	1+60	1+60	1+60	1+60	0.00	0.00	1000	0	
1+70	1+70	1+70	1+70	1+70	0.00	0.00	1000	0	
1+80	1+80	1+80	1+80	1+80	0.00	0.00	1000	0	
1+90	1+90	1+90	1+90	1+90	0.00	0.00	1000	0	
2+00	2+00	2+00	2+00	2+00	0.00	0.00	1000	0	End of Curve



Checked: MM
Approved: MM
Date: 11/11/2011



**Dr. V. Siddesh Institute of Technology
Civil Engineering Department
Measurment Testing Laboratory**

PROJECT: STRENGTH EVALUATION OF REINFORCED CONCRETE COLUMN
DATE: 10.02.2022
DEPT: CIVIL
LAB: CIVIL
PAGE NO: 2


STUDENT NAME: [Blank]
ROLL NO: [Blank]
GROUP: [Blank]

Table 1: Test Data

Sl. No.	Concrete Properties		Steel Properties		Reinforcement Details		Remarks
	Compressive Strength (MPa)	Modulus of Elasticity (GPa)	Yield Strength (MPa)	Tensile Strength (MPa)	Area (mm ²)	Spacing (mm)	
1	38	20	460	580	100	150	
2	38	20	460	580	100	150	
3	38	20	460	580	100	150	
4	38	20	460	580	100	150	
5	38	20	460	580	100	150	
6	38	20	460	580	100	150	
7	38	20	460	580	100	150	
8	38	20	460	580	100	150	
9	38	20	460	580	100	150	
10	38	20	460	580	100	150	
11	38	20	460	580	100	150	
12	38	20	460	580	100	150	
13	38	20	460	580	100	150	
14	38	20	460	580	100	150	
15	38	20	460	580	100	150	
16	38	20	460	580	100	150	
17	38	20	460	580	100	150	
18	38	20	460	580	100	150	
19	38	20	460	580	100	150	
20	38	20	460	580	100	150	
21	38	20	460	580	100	150	
22	38	20	460	580	100	150	
23	38	20	460	580	100	150	
24	38	20	460	580	100	150	
25	38	20	460	580	100	150	
26	38	20	460	580	100	150	
27	38	20	460	580	100	150	
28	38	20	460	580	100	150	
29	38	20	460	580	100	150	
30	38	20	460	580	100	150	

Sl. No.	Load (kN)	Displacement (mm)	Stress (MPa)	Strain
1	0	0	0	0
2	10	1.5	10	0.00075
3	20	3.0	20	0.0015
4	30	4.5	30	0.00225
5	40	6.0	40	0.003
6	50	7.5	50	0.00375
7	60	9.0	60	0.0045
8	70	10.5	70	0.00525
9	80	12.0	80	0.006
10	90	13.5	90	0.00675
11	100	15.0	100	0.0075
12	110	16.5	110	0.00825
13	120	18.0	120	0.009
14	130	19.5	130	0.00975
15	140	21.0	140	0.0105
16	150	22.5	150	0.01125
17	160	24.0	160	0.012
18	170	25.5	170	0.01275
19	180	27.0	180	0.0135
20	190	28.5	190	0.01425
21	200	30.0	200	0.015
22	210	31.5	210	0.01575
23	220	33.0	220	0.0165
24	230	34.5	230	0.01725
25	240	36.0	240	0.018
26	250	37.5	250	0.01875
27	260	39.0	260	0.0195
28	270	40.5	270	0.02025
29	280	42.0	280	0.021
30	290	43.5	290	0.02175
31	300	45.0	300	0.0225
32	310	46.5	310	0.02325
33	320	48.0	320	0.024
34	330	49.5	330	0.02475
35	340	51.0	340	0.0255
36	350	52.5	350	0.02625
37	360	54.0	360	0.027
38	370	55.5	370	0.02775
39	380	57.0	380	0.0285
40	390	58.5	390	0.02925
41	400	60.0	400	0.03
42	410	61.5	410	0.03075
43	420	63.0	420	0.0315
44	430	64.5	430	0.03225
45	440	66.0	440	0.033
46	450	67.5	450	0.03375
47	460	69.0	460	0.0345
48	470	70.5	470	0.03525
49	480	72.0	480	0.036
50	490	73.5	490	0.03675
51	500	75.0	500	0.0375
52	510	76.5	510	0.03825
53	520	78.0	520	0.039
54	530	79.5	530	0.03975
55	540	81.0	540	0.0405
56	550	82.5	550	0.04125
57	560	84.0	560	0.042
58	570	85.5	570	0.04275
59	580	87.0	580	0.0435
60	590	88.5	590	0.04425
61	600	90.0	600	0.045
62	610	91.5	610	0.04575
63	620	93.0	620	0.0465
64	630	94.5	630	0.04725
65	640	96.0	640	0.048
66	650	97.5	650	0.04875
67	660	99.0	660	0.0495
68	670	100.5	670	0.05025
69	680	102.0	680	0.051
70	690	103.5	690	0.05175
71	700	105.0	700	0.0525
72	710	106.5	710	0.05325
73	720	108.0	720	0.054
74	730	109.5	730	0.05475
75	740	111.0	740	0.0555
76	750	112.5	750	0.05625
77	760	114.0	760	0.057
78	770	115.5	770	0.05775
79	780	117.0	780	0.0585
80	790	118.5	790	0.05925
81	800	120.0	800	0.06
82	810	121.5	810	0.06075
83	820	123.0	820	0.0615
84	830	124.5	830	0.06225
85	840	126.0	840	0.063
86	850	127.5	850	0.06375
87	860	129.0	860	0.0645
88	870	130.5	870	0.06525
89	880	132.0	880	0.066
90	890	133.5	890	0.06675
91	900	135.0	900	0.0675
92	910	136.5	910	0.06825
93	920	138.0	920	0.069
94	930	139.5	930	0.06975
95	940	141.0	940	0.0705
96	950	142.5	950	0.07125
97	960	144.0	960	0.072
98	970	145.5	970	0.07275
99	980	147.0	980	0.0735
100	990	148.5	990	0.07425
101	1000	150.0	1000	0.075
102	1010	151.5	1010	0.07575
103	1020	153.0	1020	0.0765
104	1030	154.5	1030	0.07725
105	1040	156.0	1040	0.078
106	1050	157.5	1050	0.07875
107	1060	159.0	1060	0.0795
108	1070	160.5	1070	0.08025
109	1080	162.0	1080	0.081
110	1090	163.5	1090	0.08175
111	1100	165.0	1100	0.0825
112	1110	166.5	1110	0.08325
113	1120	168.0	1120	0.084
114	1130	169.5	1130	0.08475
115	1140	171.0	1140	0.0855
116	1150	172.5	1150	0.08625
117	1160	174.0	1160	0.087
118	1170	175.5	1170	0.08775
119	1180	177.0	1180	0.0885
120	1190	178.5	1190	0.08925
121	1200	180.0	1200	0.09
122	1210	181.5	1210	0.09075
123	1220	183.0	1220	0.0915
124	1230	184.5	1230	0.09225
125	1240	186.0	1240	0.093
126	1250	187.5	1250	0.09375
127	1260	189.0	1260	0.0945
128	1270	190.5	1270	0.09525
129	1280	192.0	1280	0.096
130	1290	193.5	1290	0.09675
131	1300	195.0	1300	0.0975
132	1310	196.5	1310	0.09825
133	1320	198.0	1320	0.099
134	1330	199.5	1330	0.09975
135	1340	201.0	1340	0.1005
136	1350	202.5	1350	0.10125
137	1360	204.0	1360	0.102
138	1370	205.5	1370	0.10275
139	1380	207.0	1380	0.1035
140	1390	208.5	1390	0.10425
141	1400	210.0	1400	0.105
142	1410	211.5	1410	0.10575
143	1420	213.0	1420	0.1065
144	1430	214.5	1430	0.10725
145	1440	216.0	1440	0.108
146	1450	217.5	1450	0.10875
147	1460	219.0	1460	0.1095
148	1470	220.5	1470	0.11025
149	1480	222.0	1480	0.111
150	1490	223.5	1490	0.11175
151	1500	225.0	1500	0.1125
152	1510	226.5	1510	0.11325
153	1520	228.0	1520	0.114
154	1530	229.5	1530	0.11475
155	1540	231.0	1540	0.1155
156	1550	232.5	1550	0.11625
157	1560	234.0	1560	0.117
158	1570	235.5	1570	0.11775
159	1580	237.0	1580	0.1185
160	1590	238.5	1590	0.11925
161	1600	240.0	1600	0.12
162	1610	241.5	1610	0.12075
163	1620	243.0	1620	0.1215
164	1630	244.5	1630	0.12225
165	1640	246.0	1640	0.123
166	1650	247.5	1650	0.12375
167	1660	249.0	1660	0.1245
168	1670	250.5	1670	0.12525
169	1680	252.0	1680	0.126
170	1690	253.5	1690	0.12675
171	1700	255.0	1700	0.1275
172	1710	256.5	1710	0.12825
173	1720	258.0	1720	0.129
174	1730	259.5	1730	0.12975
175	1740	261.0	1740	0.1305
176	1750	262.5	1750	0.13125
177	1760	264.0	1760	0.132
178	1770	265.5	1770	0.13275
179	1780	267.0	1780	0.1335
180	1790	268.5	1790	0.13425
181	1800	270.0	1800	0.135
182	1810	271.5	1810	0.13575
183	1820	273.0	1820	0.1365
184	1830	274.5	1830	0.13725
185	1840	276.0	1840	0.138
186	1850	277.5	1850	0.13875
187	1860	279.0	1860	0.1395
188	1870	280.5	1870	0.14025
189	1880	282.0	1880	0.141
190	1890	283.5	1890	0.14175
191	1900	285.0	1900	0.1425
192	1910	286.5		

TRIAXIAL SHEAR TEST REPORT



Type of Test: Unconsolidated Undrained

Sample Type: UNSATURATED

No.	Peak Stress, kPa		Fail. Stress, kPa		Vol. Change, %		Final Water Content, %	
	Cell	Back	Cellular	Shear	Deviator	Shear	Pre	Post
1	50.0	0.0	22.5	4.4			100.0	50.0
2	100.0	0.0	45.0	8.8			100.0	100.0
3	150.0	0.0	67.5	13.2			100.0	100.0

Sample Parameters

No.	% Water Content	Dry Comp. Agno	Ratio mm	Void Ratio	Diameter mm	Height mm	Spun Size mm
1	122	100	100.0%	0.3493	50.8	248	75
2	122	100	100.0%	0.3493	50.8	134	75
3	122	100	100.0%	0.3493	75.4	122	75

Mohr-Coulomb Strength Parameters

Strength intercept, $c = 11.7$ kPa
 Friction angle, $\phi = 11.8$ deg
 Tangent $\alpha = 2.1$

Material Description

Client: SHANXI CONSTRUCTION COMPANY

Date Sampled: 12.12.2023

Project: PROPOSED FACCAL SLUDGE TREATMENT PLANT

File: RIMBIJI

Location: RIMBIJI - DSM

Remarks:
 URBAN AREA
 (DEPTH 1M)
 500G, 50g






Sample Number: 14, Report: 3.00-0.00

TRIAXIAL SHEAR TEST REPORT

Figure 1

Tested & Prepared By: CHAN, TS, JAMES


12/12/2023




Client: **SHANU CONSTRUCTION COMPANY**
 Project: **PROPOSED FACIAL SLUDGE TREATMENT PLANT**
 Loc: **KIMBLU - DSM** Depth: **Depth: 1.00-2.00m Sample**
 No. of Project: **BH NO.1** Figure: **2**

Tested & Prepared: **By: CHHISS-JAMES**

Handwritten signature and date: 12/1/2019

TRIAxIAL SHEAR TEST REPORT



Type of Test: Unconsolidated Undrained

Sample Type: UNCONSOLIDATED

No.	Fluid Stress, kPa		Total Stress, kPa		Ult. Stress, kPa		"WATER"	
	Cell	Back	Deviator	Strain, %	Deviator	Strain, %	%	%
1	10.0	8.0	13.5	4.4			100	20.0
2	10.0	11.0	14.0	4.7			100	17.0
3	10.0	11.0	14.0	5.7			100	14.0

Sample Parameters

No.	% Water Content	Dry Dens. g/cm ³	Satur. Ratio	Void Ratio	Diameter mm	Height mm	Shear Rate s ⁻¹
1	16.1	2091	100.0%	0.2673	70.0	140.0	1.4
2	17.1	2091	100.0%	0.2673	71.0	142.0	1.4
3	18.1	2091	100.0%	0.2673	71.0	141.7	1.4

Main Geotechnical Strength Parameters

Note(s) Description

Shear strength, $c = 15.7$ kPa
 Friction angle, $\phi = 21.0$ deg
 Tangent $c = 6.18$

CLIENT: SHANXI CONSTRUCTION COMPANY

Date Sampled: 12.12.2023

Project: PROPOSED FACIAL SLUDGE TREATMENT PLANT

File: KIMBLI-DSM

Location: KIMBLI-DSM

Remarks: FOR BENCHING FAC? DRAINAGE SYSTEM






LABORATORY: 3009-9-2016 Number 10

TRIAxIAL SHEAR TEST REPORT

Figure 1

Tested & Prepared By: CHARLES JAMES


 12/12/2023




CHINA SHANXI CONSTRUCTION COMPANY
FUJIAN PROPOSED FACIAL SLUDGE TREATMENT PLANT
Location: KIMBIJI - DSM

Figure 2 BH 2 Depth: 0.00-3.45m Sample No.: U4


 [Signature]
 12/10/2019

TRIAXIAL SHEAR TEST REPORT








No.	Type of Test: Unconsolidated Undrained				Sample Type: UNSATURATED			
	Fluid Phase: kPa		Soil Phase: kPa		Ult. Stress: kPa		"MOISTURE"	
	Cell	Back	Drainage	Strain, %	Drainage	Strain, %	%	%
1	3000	0.00	0.00	5.0			14.70	50.00
2	10000	0.00	0.00	5.0			22.40	100.00
3	0.000	0.00	200.00	5.0			27.60	100.00

No.	Sample Parameters						
	% Water Content	Dry Density (kg/m ³)	Settlement (%)	Void Ratio	Diameter (mm)	Height (mm)	Shear Rate (1/min)
1	13.1	1.94	100.0%	0.360	30.00	140.00	1.40
2	0.1	1.94	100.0%	0.360	30.00	140.00	1.40
3	13.1	1.90	100.0%	0.360	30.00	140.00	1.40

Moisture-Cohesion Strength Parameters	Moisture Description
Total Strength intercept: $c = 12.36 \text{ kPa}$ Friction angle: $\phi = 23.8 \text{ deg}$ Target: $\phi = 0.41$	
Client: SHANXI CONSTRUCTION COMPANY Project: PROPOSED FACIAL SLUDGE TREATMENT PLANT Sample Number: 1-3 Depth: 0.0-3.0m	Date Sampled: 12.12.2021 File: KIMOLJI-BSM Remarks: BOREHOLE No. 3 DEPTH 0.0-3.0m
TRIAXIAL SHEAR TEST REPORT	

Tested & Prepared By: CHARLES JAMES





Client: SHANGHAI CONSTRUCTION COMPANY
 Project: PROPOSED FAECAL SLUDGE TREATMENT PLANT

Loc: KIBBLE - DS18


Figure | Depth: 0.0-2.0m | Sample No: 7/20

Tested & Prepared By: CHARLES JAMES



Charles James

TRIAXIAL SHEAR TEST REPORT



Type of Test: Consolidated Undrained

Sample Type: UNSATURATED

No.	Final Press. (kPa)		Fail. Stress (kPa)		Dr. Stress (kPa)		Void Ratio	
	Cell	Back	Deviator	Strain %	Deviator	Strain %	e_v	e_u
3001	500	00	118.5	4.7	118.5	4.7	1.44	1.00
3002	1000	00	173.0	3.7	173.0	3.7	1.27	1.00
3003	1500	00	212.1	5.8	212.1	5.8	1.13	1.00

Sample Parameters

No.	% Water Content	Dry Density (kg/m ³)	Spec. Grav. (G _s)	Void Ratio	Diameter (mm)	Height (mm)	Spun Rate (1/min)
3001	61.5	1800	100.0%	1.440	70.0	140.0	1.4
3002	61.8	1900	100.0%	1.300	70.0	140.0	1.4
3003	63.7	1968	100.0%	1.030	70.0	140.0	1.4

State Colours Strength Parameters

Material Description

Test
 Strength (kPa) at $\sigma'_v = 100$ kPa
 Friction angle, $\phi = 28.6$ deg
 Tangent $c = 0.0$

Client: SHANXI CONSTRUCTION COMPANY

Date Sampled:

Project: PROPOSED FACIAL SLUDGE TREATMENT PLANT

12.12.2023

File: FINANCE
 PROJECT 2/4
 Remarks






Sample Numbers: 3.00-6.0m

PROJECT 05/04

TRIAXIAL SHEAR TEST REPORT

Tested & Prepared By: CHARLES JAMES






Client: SHARJI CONSTRUCTION COMPANY
 Project: PROPOSED FAECAL SLUDGE TREATMENT PLANT

Scale: 3.00-6.00mm BH 4 Date: _____

Tested & Prepared By: CHARLES JAMES

SHARJI CONSTRUCTION COMPANY
 PROJECT: PROPOSED FAECAL SLUDGE TREATMENT PLANT
 Date: _____
Charles James

TRIAXIAL SHEAR TEST REPORT



Type of Test: Unconsolidated Undrained

Sample Type: UNSATURATED

No.	Fluid Stress, kPa		Total Stress, kPa		Ult. Shear, kPa		Friction %	
	Cell	Back	Deviator	Strain %	Deviator	Strain %	%	%
1	30.00	0.00	97.67	14			21.07	50.00
2	10.00	0.00	102.87	30			22.46	100.00
3	0.00	0.00	222.43	10			27.94	100.00

Sample Parameters

No.	% Water Content	Dry Comp. (kg/m ³)	Spun-off (%)	Void Ratio	Disturbed (mm)	Height (mm)	Shear Rate (1/min)
1	10.0	1700	100.0%	0.360	70.00	50.00	1.00
2	10.0	1700	100.0%	0.360	70.00	50.00	1.00
3	10.0	1700	100.0%	0.360	70.00	50.00	1.00

Mini-Coupled Strength Parameters

Material Description

Total
 Strength parameter, c' = 15.16 kPa
 Friction angle, ϕ' = 23.8 deg.
 Tangent β' = 0.44

CHENGSHANKI CONSTRUCTION COMPANY


Project: PROPOSED FACIAL SLUDGE TREATMENT PLANT






Location: WIMBULU -075W
 Depth: 0.0-3.0m BH NO.3

Date Sampled:
 12.10.2023

TRIAXIAL SHEAR TEST REPORT
 Dar Es Salaam, Tanzania

Tested & Prepared By: CHARLES JAMES


 Charles James




Client: SHARXI CONSTRUCTION COMPANY
 Project: PROPOSED FAECAL SLUDGE TREATMENT PLANT
 Depth: 0.0-3.0m
 Figure 1 Sample No.: 111 BH No. 5

Tested & Prepared By: CHARLES JAMES

Handwritten signature and date: Charles James 20/12/2020

TRIAxIAL SHEAR TEST REPORT




No.	Type of Tests Conducted/Used				Sample Type: UNSATURATED			
	Full Pave. (kPa)	Back	Full Stress (kPa)	Strain %	Un. Stress (kPa)	Strain %	W _c	W _L
1	74.4	0.0	107.7	47			157.7	20.5
2	100.0	0.0	137.8	54			210	100.0
3	166.0	0.0	214	41			274.6	100.0

Sample Parameters							
No.	% Water Content	Dry Density (g/cm ³)	Sat. Water (kPa)	Void Ratio	Diameter (mm)	Height (mm)	Strain Rate (mm/min)
1	45.8	1.227	100.0%	1.000	75.0	100.0	1.0
2	100.0	1.237	100.0%	1.000	75.0	100.0	1.0
3	40.0	1.217	100.0%	1.000	75.0	100.0	1.0

Moisture Content Strength Parameters	Mass/Description
Test Shear Stress $\tau = 18.4 \text{ kPa}$ Friction angle $\phi = 21.0 \text{ deg}$ Intercept $c = 0.00$	
Client: SHANXI CONSTRUCTION COMPANY Project: PROPOSED FACIAL SLUDGE TREATMENT PLANT Location: KENBIJI - GSM Depth: 0.80-3.0m	Date Sampled: 12.12.2023 File Remarks: H02020203 DEPTH 0.8-3.0m
TRIAxIAL SHEAR TEST REPORT	Figure

Tested & Prepared By: CHARLEE JAMES


 12/12/2023



Client: SHANJI CONSTRUCTION COMPANY
 Project: PROPOSED FAECAL SLUDGE TREATMENT PLANT
 Depth: 0.00-3.0m Project No: 2019
 Figure 1.1.1


Tested & Prepared By: CHARLES JAMES

Charles James

Consolidation Test - Void Ratio Plotting Program

Soil Name	CLAY	Scale	100
Soil Description	CLAY	Scale	100
Soil Classification	CLAY	Scale	100
Soil Color	CLAY	Scale	100
Soil Moisture	CLAY	Scale	100
Soil Weight	CLAY	Scale	100
Soil Volume	CLAY	Scale	100
Soil Density	CLAY	Scale	100
Soil Specific Gravity	CLAY	Scale	100
Soil Liquid Limit	CLAY	Scale	100
Soil Plastic Limit	CLAY	Scale	100
Soil Shrinkage Limit	CLAY	Scale	100
Soil Swell Potential	CLAY	Scale	100
Soil Compression Index	CLAY	Scale	100
Soil Recompression Index	CLAY	Scale	100
Soil Preconsolidation Pressure	CLAY	Scale	100
Soil Compression Ratio	CLAY	Scale	100
Soil Recompression Ratio	CLAY	Scale	100
Soil Compression Curve	CLAY	Scale	100
Soil Recompression Curve	CLAY	Scale	100
Soil Compression Ratio	CLAY	Scale	100
Soil Recompression Ratio	CLAY	Scale	100
Soil Compression Curve	CLAY	Scale	100
Soil Recompression Curve	CLAY	Scale	100

Vertical Stress (lb/in ²)	100	200	300	400	500	600	700	800	900	1000
Void Ratio	0.75	0.74	0.73	0.72	0.71	0.70	0.69	0.68	0.67	0.66
Vertical Stress (lb/in ²)	100	200	300	400	500	600	700	800	900	1000
Void Ratio	0.75	0.74	0.73	0.72	0.71	0.70	0.69	0.68	0.67	0.66
Vertical Stress (lb/in ²)	100	200	300	400	500	600	700	800	900	1000
Void Ratio	0.75	0.74	0.73	0.72	0.71	0.70	0.69	0.68	0.67	0.66
Vertical Stress (lb/in ²)	100	200	300	400	500	600	700	800	900	1000
Void Ratio	0.75	0.74	0.73	0.72	0.71	0.70	0.69	0.68	0.67	0.66
Vertical Stress (lb/in ²)	100	200	300	400	500	600	700	800	900	1000
Void Ratio	0.75	0.74	0.73	0.72	0.71	0.70	0.69	0.68	0.67	0.66
Vertical Stress (lb/in ²)	100	200	300	400	500	600	700	800	900	1000
Void Ratio	0.75	0.74	0.73	0.72	0.71	0.70	0.69	0.68	0.67	0.66




ENGINEERING REGISTRATION BOARD
 EXCISES
 REGISTRATION DIVISION OF TECHNOLOGY
 HOUSE 208 - ONE SOLOMAN
 STREET, MANILA
 PHILIPPINES
 DATE: 10/1/2013

Classification and Void Ratio Plotting Program

Project Name	[Blank]		Date	[Blank]
Client	[Blank]		Location	[Blank]
Site	[Blank]		Project No.	[Blank]
Operator	[Blank]	Scale	[Blank]	[Blank]


Liquid Limit (%)	62	62.2	27.9	25.0	49.8	62.1	62.7	62.7
Plasticity Index (%)	20	19	19	19	19	20	19	19
Shrinkage (%)	10.1	9.8	9.1	8.8	8.9	8.8	8.9	8.9
Moisture Content (%)	104	100	102	104	102	101	100	100
Specific Gravity	2.70	2.70	2.70	2.70	2.70	2.70	2.70	2.70
Void Ratio	0.41	0.39	0.37	0.36	0.36	0.37	0.36	0.36
Relative Density (%)	4	39	34	34	39	39	40	40



RECEIVED BY THE STATE DEPT
 OF TRANSPORTATION
 LABORATORY DIVISION OF TECHNICAL
 SERVICES DIVISION
 1000 WEST 11th AVENUE
 DENVER, COLORADO 80202
[Signature]

Consolidation test - Soil Name: Peatling (Project)			
Soil No.	101	Soil Name	Peatling
Soil Type	Clay	Soil Description	...
Soil Color	...	Soil Consistency	...
Soil Moisture	...	Soil Temperature	...
Soil Weight	...	Soil Volume	...
Soil Density	...	Soil Specific Gravity	...

Soil No.	101	102	103	104	105	106	107	108
Soil Name
Soil Type
Soil Color
Soil Moisture
Soil Weight
Soil Density
Soil Specific Gravity
Soil Temperature
Soil Volume




ENGINEERING CONSULTING GROUP
INDONESIA
PT. ECG INSTITUTE OF TECHNOLOGY
 Jl. Raya 100 - 115, Cilandak Barat,
 Jakarta Selatan 12430, Indonesia
 Telp. (021) 7500 1000
 Fax. (021) 7500 1001
 Email: info@ecg.co.id

[Handwritten Signature]
 Date: ...

Consolidation Test - Test Data Plotting Form			
Project	[Blank]		Date
Site	[Blank]		Time
Test No.	[Blank]		Operator
Soil	[Blank]		Scale No.
Notes	[Blank]		Test No.

Initial Sample Height	10.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0
Final Sample Height	9.5	9.5	9.5	9.5	9.5	9.5	9.5	9.5
Initial Thickness	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
Final Thickness	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95
Initial Area	100	100	100	100	100	100	100	100
Final Area	90	90	90	90	90	90	90	90
Initial Volume	100	100	100	100	100	100	100	100
Final Volume	90	90	90	90	90	90	90	90
Initial Density	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
Final Density	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1




CONSOLIDATION TEST REPORT FORM
 PROJECT NO. [Blank]
 TEST NO. [Blank]
 OPERATOR [Blank]
 DATE [Blank]

[Handwritten Signature]
 11/27/2023

Consolidation Test - Void Ratio vs Log Pressure			
Soil Name	SAND		Lab. No.
Soil No.	SAND		100
Soil Description	SAND		100
Soil No.	SAND		100
Soil Description	SAND		100


Initial Void Ratio	0.75	0.75	0.75	0.75	0.75	0.75	0.75
Final Void Ratio	0.70	0.70	0.70	0.70	0.70	0.70	0.70
Change in Void Ratio	0.05	0.05	0.05	0.05	0.05	0.05	0.05
Initial Pressure (kN/m ²)	100	200	400	800	1600	3200	6400
Final Pressure (kN/m ²)	100	200	400	800	1600	3200	6400
Initial Void Ratio	0.75	0.75	0.75	0.75	0.75	0.75	0.75
Final Void Ratio	0.70	0.70	0.70	0.70	0.70	0.70	0.70




ENGINEER'S PRIVATE SEAL
 YAGASA
 HANSHUWA SANGYO CO. LTD.
 TOKYO, JAPAN
 No. of [Signature]

Comprehensive - Void Ratio Plot Log Pressure			
Project Name	Road and Bridge		Date
Client	Government of Tanzania		Scale
Site	Tanzania - Dar es Salaam		Sheet No.
Soil Name	Clayey Sand	Soil No.	10
Test No.	10	Test Date	2023

Vertical Stress (kPa)	100	200	300	400	500	600	700	800
Void Ratio (e)	0.75	0.72	0.70	0.68	0.65	0.62	0.58	0.55
Swelling Ratio (s)	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09
Compression Index (C _c)	0.005	0.01	0.015	0.02	0.025	0.03	0.035	0.04
Preconsolidation Pressure (p _c)	400	400	400	400	400	400	400	400
Initial Void Ratio (e ₀)	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75
Final Void Ratio (e _f)	0.55	0.55	0.55	0.55	0.55	0.55	0.55	0.55
Compression Ratio (C _r)	0.005	0.01	0.015	0.02	0.025	0.03	0.035	0.04



ENGINEERING REGISTRATION BOARD
 TANZANIA
 DAR ES SALAAM
 INSTITUTE OF TECHNOLOGY
 MINISTRY OF INFRASTRUCTURE
 DEVELOPMENT
 2023/02/20



GOLANI FSTP SITE PLAN SHOWING DRILLING POINTS FOR GEOTECHNICAL INVESTIGATION

COORDINATES OF THE PROPOSED GEOTECHNICAL SURVEY POINTS

Pt A	X=9225905.878	Y=557068.421	Z=40.155
Pt B	X=9225884.842	Y=557138.834	Z=38.106
Pt C	X=9225836.811	Y=557287.895	Z=38.456
Pt D	X=9225813.901	Y=557215.719	Z=34.400
Pt E	X=9225815.932	Y=557054.059	Z=36.973
Pt F	X=9225763.970	Y=557130.838	Z=35.000
Pt G	X=9225708.414	Y=557210.900	Z=35.200

				PROJECT THE PROPOSED FSTP AT GOLANI WATER TREATMENT PLANT		CLIENT THE STATE OF PALESTINE			DATE 2024
				No.	Revision	Drawing No.	Drawing Title	Drawing Scale	